ENGINEERING NEWS-RECORD

Their worry? Getting aid to sewage works rolling *p. 23*

ANN ARBOR MICH
313 N 1 ST
UNIVERSITY MICROFILM
S B POWER

A McGRAW-HILL PUBLICATION



World's longest suspension bridge stretches four miles across the Straits of Mackinac joining Michigan's upper peninsula with the rest of the state.

Wrought Iron Plates protect Mackinac Bridge pilings against double-trouble



Welded wrought iron plates extending ten feet above and eight feet below the waterline, form a bulwark of protection against corrosion and ice.

Engineers on the $100 million Mackinac Bridge faced this problem: what material could most economically protect the bridge's concrete substructure against recurrent wet-dry corrosion and abrasion by ice?

Consulting Engineer D. B. Steinman, New York, met these requirements by specifying over 270 tons of ⅜-inch wrought iron plates. These plates do double-duty . . . combatting corrosion and guarding pilings against stress and subsequent spalling under dense ice formations.

Wrought iron can cut maintenance costs in your installation, too. Our booklet, "Wrought Iron for Bridge Construction," tells you how and why. Write for a copy.

A. M. Byers Company, Pittsburgh, Pa. Established 1864. Division Offices in Boston, New York, Philadelphia, Washington, Atlanta, Chicago, St. Louis, Houston, San Francisco.

Available in Canada and throughout the world

BYERS *Wrought Iron Tubular and Hot Rolled Products*

ALSO ELECTRIC FURNACE QUALITY STEEL PRODUCTS

Look at the evidence of

MURPHY

"TRUE DIESEL" OPERATION

Look inside a Murphy Diesel for the reasons why Murphy engines are noted for economy, dependability and long life. You'll find design features ordinarily found only in large diesel engines . . . the "true diesel" features offered by no other engine in Murphy's size and power range.

Look for these features in your next diesel engine. Ask your Murphy Diesel Dealer to explain the advantages of "true diesel" operation for your power requirements.



Plain, Open Combustion Chamber

The Murphy Diesel's plain, open combustion chamber, like that of time-tested larger engines, assures *complete* combustion. Murphy owners get maximum power from each drop of fuel with less engine wear.

Precisely Controlled Fuel Injection

In the Murphy Diesel, fuel injection for each cylinder is accurately controlled by a simple injector unit which serves as both pump and nozzle. High pressure fuel lines are eliminated. There is no erratic, irregular injection, no after-dribbling or air binding.





4 Valves for Better Breathing

Four valves per cylinder in Murphy Diesels have greater breathing capacity than conventional 2-valve design and permit higher power output. Because they run cooler, they rarely have to be ground. Valve troubles are virtually unknown.



Instant Response to Load Change

The exclusive Hydraulic Servo-Type Governor on a Murphy Diesel harnesses lubricating oil pressure to adjust injector controls for instantaneous response to changing power requirements. If lube oil pressure should drop below a safe level, the governor automatically shuts off the engine.

35ON

MURPHY DIESEL COMPANY

5321 W. Burnham St., Milwaukee, Wisconsin

SALES . . . PARTS . . . SERVICE

Throughout the Nation

MURPHY DIESEL

Heavy-Duty Power

for Construction

Murphy Diesel Engines and Power Units are available in sizes from 96 to 264 H.P. Engine speeds are 1200 and 1400 rpm. "Packaged" generating units from 64 to 165 K.W.

New Dormitory, Lewis and Clark Campus, Portland, Oregon, Donald M. Drake Company, Gen. Con.

Pouring Second Lift on High Wall with Symons Forms

24 ft. wall poured in two lifts with Symons Forms. Scaffolding attached to forms makes easier setting and stripping of top forms. Note absence of bracing and minimum waling.

Symons Engineering and Customer Service includes the details of a forming job from start to finish. Our engineering staff is experienced with all types of forming and will furnish complete form layouts and job cost sheets on form work—at no charge to the customer. This service enables the contractor to get a clear picture of his job (its cost, bill of materials and labor saving methods).

Our salesmen are trained on form erection, pouring and stripping methods and give regular on-the-job service.

Symons Forms, Shores and Column Clamps may be rented with purchase option, all rentals to apply on purchase price.

Symons

SYMONS CLAMP & MFG. CO. Dept. K-6
4263 Diversey Avenue, Chicago 39, Illinois

Please send information on items checked:
☐ Forms ☐ Shores ☐ Column Clamps

Name_____
Firm_____
Address_____
City_____ Zone_____ State_____

ENGINEERING NEWS-RECORD

EIGHTY-SECOND YEAR OF PUBLICATION

ABP ABC MEMBER

Editorial Offices, 330 W. 42nd St., New York 36, N. Y.
New York - LOngacre 4-3000; Chicago - MOhawk 4-5800; San Francisco - DOuglas 2-4600; Washington - REpublic 7-6630

Waldo G. Bowman, Editor

Highways, Airports—Transportation

Eugene E. Halmos, Jr., *Senior Editor*
John R. Owen, Edward M. Young, Jr.

Buildings, Bridges—Structures

Frederick S. Merritt, *Senior Editor*
Edward R. Wood, James B. Sullivan

Rivers, Sanitation—Water Use

Arthur J. Fox, Jr., *Senior Editor*
Howard Jacoby

Finance, Labor—Management

Clyde C. Henning, *Associate Editor*
Charles J. Harding, John Flanagan

Regional Editors

J. Roland Carr, *Chicago, 520 N. Michigan Ave.*
Lauress L. Wise, *San Francisco, 68 Post St.*

Copy, Presentation—Production

Stanley C. Jensen
Marcellino V. Leggiero
Barbara Lamb
Harry W. Jensen, *Presentation*
Ruth Solomon, *Makeup*
John C. Greenough, *Printing*

Statistics, Prices, Costs—Business News

Elsie Eaves, *Manager*
Julia Mahoney, *Construction Reports*
Mildred Wetzel, Loretta Felix, Marion Sciorra, Florence Dembek
James Webber, *Economics*
Ruth I. Carlson, Marie Roessler, Evelyn Huber

Editorial Research and Indexing

Helen Rich
Eva Glerat, Rene Hay
Patricia Witschger, Marianne Stern

Consulting Editors

Van Tuyl Boughton, *New York*
Nathan A. Bowers, *San Francisco*

Washington News Bureau, Room 1189 National Press Building: G. B. Bryant, Jr., *Manager*, Glen Bayless, A. E. Adams, Roy Calvin, Ernest Conine, John C. L. Donaldson, Jay Flocken, Boyd France, V. Craig Richter, Sam Justice, Arthur J. Kraft, D. O. Loomis, Gladys Montgomery, A. L. Moore, Seth Payne, M. A. Reichek, Caroline Robertson, V. B. Smith.

Domestic News Bureaus: Atlanta, 801 Rhodes-Haverty Bldg., Pat Henry; **Cleveland,** 1510 Hanna Bldg., R. E. Cochran; **Detroit,** 856 Penobscot Bldg., Harry Homewood; **Houston,** 1203 Prudential Bldg., J. A. Lee; **San Francisco,** 68 Post Street, M. C. Ralston; **Los Angeles,** 1125 W. Sixth St., John Shinn; **Seattle,** 6040 Fifth Ave., N.E., Ray Bloomberg.

Correspondents: Albany, Albuquerque, Augusta, Me., Austin, Boston, Boulder, Baltimore, Birmingham, Bismarck, Charleston (W. Va.) Charleston (S. C.), Columbus, Cincinnati, Cleveland, Chicago, Cheyenne, Dallas, Denver, Des Moines, Detroit, Durham, Harrisburg, Helena, Houston, Hartford, Indianapolis, Jackson, Miss., Jacksonville, Jefferson City, Kansas City (Mo.), Lansing, Lincoln, Little Rock, Miami, Memphis, Minneapolis, Montgomery, Milwaukee, New Orleans, Norfolk, Omaha, Oklahoma City, Philadelphia, Pittsburg, Portland (Ore.), Providence, Phoenix, Pierre, St. Louis, Schenectady, Springfield (Ill.), Syracuse, St. Paul, Seattle, Salt Lake City, Spokane, Topeka, Trenton, Wilmington. **Canada:** Montreal, Toronto, Ottawa, Victoria, Regina.

McGraw-Hill Economics Department: Dexter M. Keezer, director; W. H. Chartener

Foreign News Bureaus: Editor, John Wilhelm, **New York;** G. W. Schroeder, **Bonn;** Sharokh Sabavala, **Bombay;** William J. Coughlin, **London;** John H. Kearney, **Mexico City;** John O. Coppock, **Paris;** Dan Kurzman, **Tokyo;** Peter Weaver, **Rio de Janeiro. Correspondents:** Amsterdam, Athens, Bangkok, Bogota, Brussels, Buenos Aires, Caracas, Copenhagen, Geneva, Havana, Helsinki, Johannesburg, Lima, Madrid, Melbourne, Oslo, Rome, Stockholm, Sydney, Tehran and 21 other principal cities and countries.

Robert F. Boger, Publisher

ENGINEERING NEWS-RECORD Vol. 157, No. 14, October 4, 1956

Published weekly by McGraw-Hill Publishing Company, James H. McGraw (1860-1948), Founder. **Executive, Editorial, Advertising and Subscription Offices, McGraw-Hill Building, 330 W. 42nd St., New York 36, N. Y.** Publication Office, 99-129 North Broadway, Albany 1, N. Y. Donald C. McGraw, President; Paul Montgomery, Executive Vice-President; Joseph A. Gerardi, Executive Vice-President and Treasurer; Hugh J. Kelly, Executive Vice-President; John J. Cooke, Secretary; Nelson Bond, Executive Vice-President, Publications Division; Ralph B. Smith, Vice-President and Editorial Director; Joseph H. Allen, Vice-President and Director of Advertising; J. E. Blackburn, Jr., Vice-President and Circulation Director. **SUBSCRIPTIONS:** Address correspondence to Engineering News-Record—Subscription Service, 99-129 North Broadway, Albany 1, N. Y., or 330 W. 42nd St., New York 36, N. Y. Allow one month for change of address. Subscriptions are solicited only from persons with an identifiable commercial or professional interest in construction and building. **Position and company connection must be indicated on subscription orders.** Single copies 35¢. Subscription rates—United States and possessions, $6.00 a year; $9.00 for two years; $12.00 for three years. Canada $8.00 a year; $12.00 for two years; $16.00 for three years. Other Western Hemisphere and the Philippines, $15.00 a year; $25.00 for two years; $30.00 for three years. All other countries $20.00 a year; $30.00 for two years; $40.00 for three years. Second class mail privileges authorized at Albany, New York. Printed in U. S. A.

Copyright 1956 by McGraw-Hill Publishing Co., Inc.—All Rights Reserved.



25 NORTHWESTS for LAMBERT BROS., INC. Knoxville Tenn.

AND, it would be tough without a *Real* Rock Shovel. But, Lambert Bros., whose business is Rock, knows equipment. It is significant that year after year they have bought Northwests for their extensive operations.

Every Northwest is a *Real* Rock Shovel. A Northwest doesn't waste time! No stutter—no restarts—no dipper juggling either in the bank or in getting the load into the truck. The cycle is smooth. Operation is easy. The Northwest Dual Independent Crowd utilizes force most other independent crowd shovels waste. The swing takes hold smoothly—no jerks, no grabs—the dipper is up and out—over the truck and back—up and out—over the truck and back, minute by minute, hour after hour! That's why you see big output figures in connection with Northwests.

Northwest equipment is profitable equipment to own. That is the reason why one out of every three Northwest Shovels sold is a repeat order in the hands of a successful contractor.

There are many other advantages you should ask about.

NORTHWEST ENGINEERING COMPANY
1502 Field Bldg., 135 South LaSalle Street, Chicago 3, Illinois

BUILD BETTER ROADS TODAY · FOR A GREATER AMERICA · See you at the ROAD SHOW CHICAGO Jan. 28-Feb. 2, 1957 AMERICAN ROAD BUILDERS ASSOCIATION

NORTHWEST

CRAWLER and TRUCK MOUNTED SHOVELS • CRANES • DRAGLINES • PULLSHOVELS

PRODUCTION PLUS · MEANS MONEY ·

S80-12-IC

Why Marfak gives better, longer-lasting bearing protection

THE REASON lies in *Texaco Marfak's* unique "sealing-in" action. *Marfak stays in* chassis bearings, even under heavy shock loads on rugged terrain—forming an effective seal against dust and dirt, preventing rust. And *Marfak's* tough lubricating film keeps wear at a minimum. Results—longer life for all parts, lower maintenance costs.

Texaco Marfak Heavy Duty does the same outstanding job in wheel bearings. It shuts out dirt and mud, assures safer braking and extra thousands of miles between lube jobs. No seasonal change is needed.

If you prefer a multi-purpose lubricant for chassis, wheel bearing, water pump and other grease lubrication — new, lithium-base *Texaco Marfak Heavy Duty Special 2* is your answer.

More than 625 million pounds of Texaco Marfak have been sold.

Here are two more Texaco names to remember: *Texaco Track Roll Lubricant* for smoother-working, fully protected crawler mechanisms; *Texaco Universal Gear Lubricant EP* to assure more dependable, lower-cost performance from differentials and transmissions.

Get the full story on cost-cutting Texaco lubricants from a Texaco Lubrication Engineer. Just call the nearest of the more than 2,000 Texaco Distributing Plants in the 48 States, or write:

The Texas Company, 135 East 42nd Street, New York 17, N. Y.

TEXACO

TEXACO



SIMPLIFY YOUR LUBRICATION—Ask your Texaco Lubrication Engineer about Texaco's Simplified Lubrication Plan. It lets you handle all major lubrication with *no more than six* Texaco products. You'll save time and money, avoid lubrication errors.

Lubricants and Fuels

FOR ALL CONTRACTORS' EQUIPMENT



for powering heavy duty excavators...

P&H diesels give you double value

1. Money Making Power...

For steady production at a high profit you can't beat the P&H Diesel 687-C18 for powering heavy duty excavators. It has the power, response and stamina to give you smooth, fast work cycles with every excavator attachment. You do more work, faster, at a lower cost.

A rugged, fast accelerating engine with a high torque, this 6-Cylinder P&H Diesel furnishes power to successfully handle the variable loads and momentary overloads encountered especially in shovel, dragline and trench-hoe services.

Costly down-time for restarts is held to a bare minimum. When heavy digging is encountered, the 2-Cycle P&H Diesel 687-C18 has the reserve power and punch to "pull through" without stuttering or stalling.

2. Money Saving Power...

Also, with a P&H Diesel you burn fewer gallons of low-cost fuel, you operate with less down-time for servicing and repairs, you experience longer periods between overhauls.

These money saving features of P&H Diesel power result from the extra reserve of power which is built into the P&H Engine 687-C18 for heavy duty excavator service. Reserve power minimizes engine stress and strain created by momentary overloads—adds to engine life—lowers maintenance costs—contributes to fuel economy.

P&H Diesel money making and money saving power add up to more power at lower operating cost for greater production and more profit for you.

It will pay you to investigate P&H Diesel's unique double values for the powering of your heavy duty excavators from 1½ to 2 yards in size.

P&H Diesel Engine Division
Harnischfeger Corporation
Crystal Lake, Illinois

Please send me complete information on P&H Diesel Engine 687-C18 for powering heavy duty excavators.

Name_____

Company_____

Street_____

City_____ Zone____ State_____

For Modern Engineering Look to

HARNISCHFEGER

P&H DIESEL ENGINE DIVISION
Crystal Lake, Illinois

V-LOK Gets a School Under Roof Faster, Reduces Erection Costs

THIS BROCHURE DEFINES V-LOK CONSTRUCTION FOR SCHOOL MEN





THIS DESIGN MANUAL WILL BE A DEFINITE AID IN DESIGNING ANY SCHOOL PLAN

Designs Readily Into School Layouts

V-LOK provides a simple, fast erection method of steel framing a school. With the steel frame erected and the building roofed in a matter of days, every other operation is speeded up. A school designed for V-LOK—or conventional framing changed over to V-LOK—is the greatest single step the Architect and School Board can take to reduce school costs and advance occupancy date. Your General Contractor who erects ONE V-LOK school will be the first to ask for another V-LOK job. Add up the many plus values you are assured when you design and build with V-LOK and you have the one, complete answer to the school situation. Do you have our V-LOK literature?

GREATEST ADVANCEMENT IN 50 YEARS OF STEEL CONSTRUCTION

STANDARDIZED STEEL BUILDING PRODUCTS

MACOMBER INCORPORATED

CANTON 1, OHIO

• ENGINEERING • FABRICATING AND ERECTING •

NAILABLE STEEL JOISTS
•
LONGSPANS
•
BOWSTRING ROOF TRUSSES
•
METAL DECK
•
V-LOK STEEL FRAMING
•
STRUCTURALS



SIMPLE DESIGN – Short head Viber vibrators are simple in design and have few parts as indicated in cut-away picture above. Head assembly with replaceable rubber tip is shown at left. Assembly with 3-finned steel-cast tip at right.

Short Head Viber Vibrators Offer Major Advantages in Placement of Concrete

VIBER VIBRATOR heads are short, easy to manipulate – simple, easy to maintain. Simple construction of the Viber head makes a compact assembly which maneuvers easily around steel and into awkward, hard-to-reach places.

The Viber design utilizes a single eccentric weight in a heat-treated alloy steel housing. Other parts are one bearing at each end of the weight and a grease seal. Viber patented replaceable rubber tip is standard equipment, with 3-finned steel cast tip optional.

Viber heads are light weight, ranging from 6 to 16 pounds . . . 11 to 12 inches in length and are available in four diameters – 1¾ in., 2⅛ in., 2½ in. and 3 in.

Flexible shaft driven, Viber vibrators are powered by electricity, gasoline or air . . . easily adapted to varying job conditions. They are high speed, operating at speeds between 8500 and 11,000 rpm.



Model E Electric



Model P Pneumatic



Model G Gasoline

Viber Replaceable Rubber Tips

Viber rubber tips save contractors thousands of dollars yearly by preventing damage to forms of plywood and other expensive materials. In addition, since most wear on a vibrator occurs on the end of the housing, use of replaceable rubber tips greatly extends housing life.

Viber vibrators are effective. More work can be done in less time and with minimum danger of damage to forms by using the high speed low amplitude type of vibrator pioneered by VIBER.

For complete information on Viber vibrators and address of nearest distributor, write Viber Company, 726 South Flower St., Burbank, Calif. Dept. 7E10.

VIBRATORS SINCE 1931

Reader Comment

Columbia River Potential

SIR—In the very interesting article "Impasse Over Columbia River Power" (ENR Aug. 23, p. 21), there appears to be some confusion between kw and kwh. I refer to the statement in the first column on page 22 which states, "The basin's maximum power potential is about 32 billion kwh . . ." I think you meant 32 million kw; the correct figure as indicated subsequently in the article. Measured in kwh, the potential energy would be about 217 billion kwh.

DANIEL J. FEE
San Francisco Regional Office
Federal Power Commission

Correction

SIR—I would like to call attention to a slight typographical error in the highway trailer "truck mounted borer" story carried on p. 74 of ENR, Sept. 20 issue.

You will note that the fourth line of the second paragraph refers to a "120 deg" operational radius, whereas it should be "180."

EDWARD BRAUSE
Merritt-Chapman & Scott Corp.
New York City

Port Change Clarified

SIR—In your Sept. 13 issue, p. 64, the article "Ecuador Port Plans Change on Advice from U. S. Engineers" states that the Government of Ecuador has abandoned plans for the development of the port of Guayaquil and has decided to construct a new port on a nearby estuary as a result of a study made by a team of U. S. Army Engineers.

Actually, the Ecuadorian government had decided to construct the port at the new location prior to the team's study, but the International Bank requested a review of the tidal hydraulic features of the project to insure that the correct decision had been made and that there were no unforeseen problems

Engineering News-Record welcomes expression of opinion from its readers. Comment should be as brief as possible and pertinent to subjects of current construction importance.

Letters should be addressed: Editor, Engineering News-Record, 330 W. 42nd St., New York 36, N. Y.



IN WASHINGTON, D. C. *

WASTE DISPOSAL OFFICIALS SPECIFY

TYLOX-Jointed PIPE LINES

TO REDUCE COST—LENGTHEN LIFE OF NEW SEWERS AND DRAINS

More and more city, state and Federal officials concerned with sewerage and drainage construction are specifying TYLOX Rubber Joints for the pipe lines they plan. Washington, D. C.'s new sewers at Kenilworth and Deane Avenues is only typical of this trend. When its designers called for this champion of all sewerage and drainage pipe-jointing materials, they gave the public "most for their waste disposal tax dollar" these three ways:

FASTER PIPE-LAYING—TYLOX-Jointed pipe goes together faster . . . eliminates "wet trench" delays and permits immediate back-filling. Reduces job costs by reducing man hours.

NO JOINT LEAKS—TYLOX Gaskets seal "rubber-tight" under compression. Water can't pass in or out of the pipe to cause pollution or bring on problems with roots or sediment. And naturally-resilient TYLOX **flexes** to protect joints from rupture due to surface loads or soil stresses.

NO CORROSION—Made of specially compounded rubber, TYLOX Joints are immune to sewerage or industrial waste acids and alkalies. TYLOX outlasts the pipe itself.

* **LOCATION:** Kenilworth & Deane Avenues, Washington, D. C.

ENGINEERS: Sanitary Engineering Dept., Government of the District of Columbia.

CONTRACTOR: J. L. Mellvane Co., Washington, D. C.

PIPE: Vitrified Plate-Lined Concrete Pipe, manufactured by United States Concrete Pipe Company, Cleveland, Ohio.



This rubber-tight mechanical seal stays tight "for the life of the line."

5008

Write today for more details and illustrated performance histories on TYLOX. Read the facts, and assure fast-working, leak-proof and non-deteriorating joints for your pipe jobs with a specification for TYLOX RUBBER JOINTS.

HAMILTON KENT MANUFACTURING COMPANY

KENT, OHIO

427 West Grant St. Orchard 3-9555



NEW CONCEPT IN COMPACTION!

VIBRO-PLUS **TERRAPAC**

VIBRATORY ROLLER

"Terrapac" compacts faster, better and deeper in fewer passes than ordinary 30-50 ton rollers yet weighs only 3½ tons. Saves hours of valuable time because maximum density can usually be achieved in only 2 passes . . . Light enough to be easily handled on any fill or for quick transport . . . Also useful as a static roller if desired.



CONVENTIONAL STATIC COMPACTION

Rollers relying on weight alone produce friction forces between individual soil particles that prevent densification at any great depth.



TERRAPAC DYNAMIC COMPACTION

Vibratory forces, transmitted to soil in all directions, reduces friction — facilitates relocation of particles at far greater depths.

An actual field test under State Highway supervision showed that a specified 100% standard proctor density could be obtained at a 24" depth after 2 passes with a "Terrapac" . . . A 15 ton smooth roller required 20 passes to obtain specified density at only an 8" depth!

VIBRO + PLUS

PRODUCTS, INCORPORATED

STANHOPE, NEW JERSEY No. 41-6

. . . Reader Comment

which would prove excessively difficult and costly in the new port and deep-draft waterway.

J. H. Douma
Hydraulic Engineer
Office, Chief of Engineers
Washington 25, D. C.

CALENDAR

University of Illinois and Portland Cement Assoc., seven lectures on thin-shell concrete structures, Navy Pier, Chicago, Ill., 7 pm to 9 pm, Oct. 9, 16, 23.

Federation of Sewage and Industrial Wastes Associations, annual convention, Hotel Statler, Los Angeles, Calif., Oct. 8-11.

Noise Abatement Symposium, seventh annual meeting, Hotel Sherman, Chicago, Ill., Oct. 11-12.

Sixth Annual Drilling Symposium, The University of Minnesota, Minn., October 11, 12, 13, 1956.

Rail Steel Bar Association, fall meeting, Sheraton-Mount Royal Hotel, Montreal, Canada, Oct. 15-16.

American Society of Civil Engineers, annual convention, Wm. Penn Hotel, Pittsburgh, Pa., Oct. 15-19.

The Construction Section, National Safety Council, Conrad Hilton Hotel, Chicago, October 22 and 23.

National Safety Council, 44th National Safety Congress and Exposition, Oct. 22-26, Chicago, Ill., Hotels Conrad Hilton, Congress, LaSalle and Morrison, Oct. 22-23.

American Concrete Institute, 9th annual regional meeting, Sheraton-Mount Royal Hotel, Montreal, Canada, Oct. 24-25.

National Society of Professional Engineers, fall meeting, The Greenbrier, White Sulphur Springs, W. Va., Oct. 25-26.

Society for Experimental Stress Analysis, Deshler-Hilton Hotel, Columbus, Ohio, Oct. 31-Nov. 2.

West Coast Noise Symposium, third annual meeting, noise in buildings, Institute of Aeronautical Sciences Auditorium, Los Angeles, Calif., Nov. 12-13.

American Public Health Association, annual convention, Convention Hall, Atlantic City, N. J., Nov. 12-16.

Associated Equipment Distributors, 38th annual meeting, Conrad Hilton Hotel, Chicago, Jan. 27-30.

American Road Builders Association, annual meeting and road show, Chicago Amphitheater, Jan. 28-Feb. 2.

CLIPPER *Sells* MORE...
Because CLIPPER *Sells* QUALITY!



BLADE *for* BLADE
CUT *for* CUT...
Your BEST BUY is CLIPPER!

● Clipper offers the only complete range of specifications in ABRASIVE, BREAK-RESISTANT and DIAMOND BLADES for cutting all masonry products...and only from Clipper can you get FACTORY-TRAINED REPRESENTATIVES to help you with your cutting problems. For FIRST QUALITY Products and FIRST QUALITY Service call Clipper . . .

You Cannot Buy A Better Blade than Clipper!

Remember...
CLIPPER *Sells* MORE
Because...
CLIPPER *Sells* QUALITY!

Clipper KANSAS CITY, MO.

Better Mail the Coupon NOW!

● Genuine Clipper Products are Sold Only Direct, by Factory-Trained Representatives from Factory Branches in Principal Cities, Coast to Coast. Consult Your Phone Book, or Mail Coupon for Same-Day Service.

CLIPPER MANUFACTURING CO.
2812 N.E. Warwick • Kansas City 8, Mo. 315X

- ☐ Send complete information on N.E.W. Clipper Triple-Reinforced Break-Resistant Blades. I'd also like to know about:
- ☐ Clipper Diamond Blades
- ☐ Clipper Masonry Saws
- ☐ Clipper Abrasive Blades
- ☐ Clipper Concrete Saws
- ☐ Please have my FACTORY-TRAINED REPRESENTATIVE Call on me.

NAME _____

ADDRESS _____

CITY _____ STATE _____

IT'S HERE!

THE BIG ADVANCE IN 2-WAY RADIO

Bendix DYNA-COM

. . . and here are 10 ways it helps CONTRACTORS and BUILDERS save money

Coordinates men and equipment ★ Speeds repairs Expedites orders faster ★ Cuts no-load miles ★ Improves operator's morale ★ Controls field operations Cuts down-time ★ Enables equipment to be shifted quickly from one site to another ★ Helps meet emergencies in minimum time ★ Eliminates vehicle messenger miles

Good communication is vital in keeping projects running smoothly and in meeting construction deadlines. And that's just what Bendix*Dyna-Com Radio gives you. Good, clear, dependable communications. Radio contact frees superintendents and field foremen from extra miles of driving making routine checks. It allows them to spend more time at critical points where they are needed most. Bendix Dyna-Com Radio provides the instant voice contact between all key personnel that results in smoother, on-schedule operation. It prevents duplication of work effort, eliminates lost time for both men and equipment.

FROM SUPPLY BASE TO CONSTRUCTION SITE Bendix 2-Way Radio performs many time-saving functions from supply base to construction site. In addition to solving traffic control problems, it enables you to put equipment where it is needed most in minimum time. Loading tie-ups are avoided, material flow speeded. Complete coordination of men, supplies and equipment through use of Bendix 2-Way Radio boosts over-all efficiency.



NEW!

Dyna-Com Mobiles Cover all frequency ranges: 25-54 mc; 144-174 mc; 450-470 mc. Available in power outputs from 15 to 60 watts. Interchangeable between 6 and 12 volt vehicles without modification.

NEW!

Dyna-Com Portables Greater versatility and flexibility than any other portable equipment. Compact, lightweight, full 1-watt output. Extra-long battery life. Complete line of accessories including a transistorized, plug-in loud-speaker.

NEW!



Dyna-Com Consoles and Base Stations For 25-54 mc; 144-174 mc; 450-470 mc; delivering from 20 to 60 watts output. Operate from 117 volt AC power lines. Quality engineered for performance and appearance.

NEW!

Bendix Bantam For low-power, limited range application as a mobile unit or base station. Provides more than 1-watt power output. Operates from 6, 12, 24, 32 volts DC or 117 volts AC without modification or costly converters. Adds flexibility to any communications system.

COMPLETE NEW LINE OF PRECISION-BUILT FM MOBILE UNITS AND BASE STATIONS FOR ALL FREQUENCIES!

The result of over 5 years laboratory research and development, Bendix Dyna-Com is the first big advance in 2-way radio in over a decade. All new from chassis to cabinet, each model incorporates all the latest improvements which have made Bendix the foremost leader in railroad and aviation communications; in airborne navigation; in radar and in military electronics.

For example, Dyna-Com's unitized design sets a new standard for performance and dependability. It features plug-in, interchangeable chassis construction which speeds service and saves maintenance costs. Any chassis in the Dyna-Com line can be transferred, without adjustment or modification, between mobile units and base stations.

Find out how Bendix Dyna-Com can boost the efficiency of your organization. Let a Bendix Communications Engineer survey your communication needs without obligation. Call or mail the coupon today for full information on Dyna-Com—*the first big advance in 2-way radio!* *Reg. U. S. Pat. Off

Bendix Radio

DIVISION OF BENDIX AVIATION CORPORATION BALTIMORE 4, MD.

Bendix Radio
Mobile Sales, Dept. E
Baltimore 4, Md.

Gentlemen:

Please send me complete details about Bendix Dyna-Com 2-Way Radio.

☐ 25-54 mc. ☐ 450-470 mc.
☐ 144-174 mc. ☐ Bantam ☐ Portable

Name_____

Title_____

Firm_____

Street_____

City_____ State_____

the man at the controls doesn't wear kid gloves

he has a tough job to do and needs equipment that can take it!

HENDRIX

DRAGLINE BUCKETS

FILL FASTER

HANDLE EASIER

DUMP CLEANER

A TYPE FOR EVERY DIGGING PURPOSE

¼ to 40 Cubic Yards

See you at the ROAD SHOW — CHICAGO
Jan. 28-Feb. 2, 1957

Hendrix Lightweight DRAGLINE BUCKETS

All Hendrix Buckets available without perforations

HENDRIX MANUFACTURING CO., Inc.
MANSFIELD, LOUISIANA

Drafting Department Heads! Now Is the Time to Gear Your Department to Meet Growing Production Demands!

NOW Is the Time to Get Your New, Modern Bruning Copyflex Machine!

Copyflex Model 500—Top mechanical speed of 40 f.p.m., front or rear delivery, automatic separation and stacking, many other features.

The boom in production means more pressure than ever for engineering drawings and prints. Right now is the time to replace that old inadequate reproduction machine you've been putting up with—now's the time to get a modern, efficient Bruning Copyflex.

In just the last year, Bruning has introduced five new, advanced machine models, one of which is shown at the left. These machines offer you the famous problem-free operation of Copyflex . . . no exhaust venting, no plumbing or auxiliary equipment, no installation other than an electrical connection. They bring you faster reproduction speed and a host of operator conveniences such as fast return of originals, automatic separation, front or rear delivery. They are the efficient, economical, modern reproduction machines that will help you boost your drafting room output, keep costs at a minimum.

Now is the time to act. Mail the coupon below. You'll be glad you did!

BRUNING Copyflex

Best Process! Best Machines! Best Selection of Materials!

Specialists in Copying Since 1897

CHARLES BRUNING COMPANY, INC., 4700 MONTROSE AVE., CHICAGO 41, ILL.

In Canada: Charles Bruning Co. (Canada) Ltd., 105 Church St., Toronto 1, Ont.

Charles Bruning Company, Inc., Dept. 103M
4700 Montrose Ave., Chicago 41, Illinois

Please send me information on Copyflex process and Model 500 machine.

Name_____ **Title**_____

Company_____

Address_____

City_____ **County**_____ **State**_____



Extra Value makes the difference in Contract Bonds

AN INDEMNITY BOND covered the contractor on this lift slab dormitory built for U. S. Navy at Little Creek, Va.

INDEMNITY of North America is one of the leading independent markets for surety bonds. The extra value it gives is measured in . . . *Carrying capacity; Service* with agents and offices in principal cities of the free world; *Preferred rates* and *Prompt attention* for qualified contractors. For extra value in your bonding requirements see an INDEMNITY agent or your own broker.

One of the North America Companies which are headed by Insurance Company of North America, founded 1792

Protect what you have ©

INDEMNITY INSURANCE COMPANY OF
NORTH AMERICA
Philadelphia

GULF PRODUCTS *and* FINE SERVICE

keep equipment rolling on Maryland Expressway



Relocating 4.676 miles of Route 5, a 4-lane expressway, from Clinton to T. B., Maryland. Contractor J. O. & C. M. Stuart, Inc., of Washington, D. C., have been using Gulf products for more than 20 years.

On this expressway relocation project, contractor J. O. and C. M. Stuart, Inc., use nothing but Gulf products.

The Stuarts have been Gulf customers since 1935 . . . because they know they can always depend on Gulf for quality products, helpful petroleum engineering counsel and prompt delivery. They use Gulf Dieselect Fuel and Gulf Super Duty Motor Oil for their diesels . . . Gulfpride Oil for their trucks . . . Gulflex A, the multi-purpose grease, for all automotive equipment . . . and tough Gulf Lubcote to protect open gears and wire rope on the job.

1400 Gulf warehouses are at your service, too. Why not find out exactly how they can serve you? Send the coupon now for your copy of the new booklet "Gulf and Your Business."

GULF

Gulf Oil Corporation • Gulf Refining Company
1822 Gulf Building, Pittsburgh 30, Penna. ENR

Without any obligation on my part, send me a copy of the new booklet "Gulf and Your Business."

NAME_____

TITLE_____

COMPANY_____

CITY_____ ZONE____ STATE_____

THE FINEST PETROLEUM PRODUCTS FOR ALL YOUR NEEDS

CONTRACTORS GUIDE to Ryerson Steels and Services

Supply problems are delaying many construction projects today, but you can keep jobs moving ahead unhampered by steel shortages when you build with reinforced concrete—and depend on Ryerson reinforcing service.

So for your buying convenience here's a quick review of Ryerson steel products—all in good supply—and Ryerson services for contractors—all readily available to you.

See your Ryerson Steels catalog for the complete list of products—including all construction steel accessories, threaded bars, turnbuckles, caisson rings, etc., and write for our bulletin (No. 70-2) on specialized reinforcing service.



RE-BARS—New-billet, deformed reinforcing bars in stock at 15 Ryerson plants. Designed for highest bonding power, bars conform to all building codes and to ASTM specs. A-15-52T and A-305-50T.



WIRE FABRIC—Electric-welded fabric of cold drawn wire in rolls available from stock in a wide range of standard gauges and spacings. Special gauges and spacings furnished to order.



SPIRALS, for column reinforcement—Made from hot rolled wire rod or cold drawn wire in ¼", ⅜", ½" and ⅝" diameters complete with channel spacers. Collapsible for shipment.



OPEN WEB STEEL JOISTS—All welded, designed for maximum strength, minimum weight in accord with Dept. of Commerce standards. Available in 4' to 40' lengths and 8" to 20" depths.



DETAILING—Expert Ryerson detailers can furnish complete setting diagrams and bending details that effect substantial reduction in re-bar placement costs.

FABRICATING SERVICE—Modern equipment and competent personnel to cut, bend, weld, thread or otherwise prepare any tonnage of construction steels are ready to work for you at Ryerson.

POSITIVE IDENTIFICATION—Permanent tags that cannot be defaced or torn off accurately identify every piece of Ryerson reinforcing steel—so correct placement on the job is quick and sure.

STEEL FORMS for concrete joist construction—Standard removable steel forms, slip or nail-down type, furnished in 20" or 30" widths. Special filler forms in widths of 10, 15, 20 and 30 inches.



DEPENDABLE DELIVERIES — Huge Ryerson stocks and big fabricating capacity enable us to meet most any delivery requirement. Your schedule sets the pace—Ryerson steel rolls to meet it.

RYERSON STEEL

JOSEPH T. RYERSON & SON, INC. • PLANTS AT: NEW YORK • BOSTON • WALLINGFORD, CONN. • PHILADELPHIA • CHARLOTTE, N. C. • CINCINNATI CLEVELAND • DETROIT • PITTSBURGH • BUFFALO • CHICAGO • MILWAUKEE • ST. LOUIS • LOS ANGELES • SAN FRANCISCO • SPOKANE • SEATTLE.

ENGINEERING NEWS-RECORD

Vol. 157, No. 14 October 4, 1956

Number of copies printed this issue: 75,606

CONTENTS

NATIONAL AFFAIRS

How to Spend a Half-Billion Dollars 23
Sewer Gas Responsible for Two Deaths 25
APWA Convention Attacks Problem of Authorities vs City Officials 26
Turbine Issue Persists on Dam Projects 27
Missouri River Basin Argument Starts Anew 27
Illinois Kicks Off Tollroad Program 28
Dome Built in Reverse—Top First 29
NSPE Meeting to Discuss Ideal Registration Law 32
State Funds Still Sought for Expressways 32
Federal Agencies Approve Changes in Columbia Basin Compact 35

FEATURES

Scrapers in Tandem Do Biggest Highway Dirt Job 36
New Data on How Materials Behave 45
Chemicals Dry Up Pump Pit Job 49

INTERNATIONAL

Grandstand Tops a 5-Story Clubhouse 55
Volta River Bridge Nears Completion 56
Indian Board Decides on Rubble Masonry for Dam 58

RESEARCH

Pilot Project Probes Paraboloid 65
Lightning Fires in Oil Tanks Prevented 66

NEW PRODUCTS

Rotary Drill Makes 7⅜-in. Hole in Rock 73
Leveling Plane Tested on Road Project 74
Tool Clinch-Fastens Panels 75
Drill's Integral Pusher Leg Automatically Retracted 76
Gooseneck Crane for Low Clearance Jobs 78
Ditcher Digs in Its Own Tracks 80
Molded Insulation for Pipes Is Light and Strong 85
Publications 86

FIELD AND OFFICE

Fabric Added to Bus-Stop Pad 91
Asphalt Cap Solves Seawall Problem 92

BUSINESS AND FINANCE

Awards Set September Record 141
Consulting Engineer Business Up 5% in 1955 142
Commerce Dept. Sees $122.2-Billion Outlay for Future Work 144
10,000 Home City Under Way 144

LABOR

Shades of the American Plan 147
Truce Reached in Dispute at Hanford AEC Project 147
Fringe Benefits Grow in Significance 148
Eisenhower, Nixon, Reuther Discuss Shorter Workweek 148
Teamster Pension Plan Adds Early Retirement 150

Reader Comment 8
Calendar 10
Washington Observer 21
Obituaries 94
Legal 99
Unit Prices 107
Materials Prices 110
Construction Reports 112
Scoreboard 140
Editorials 164

Back issues of ENGINEERING NEWS-RECORD *are generally available for the previous six months. Price 35¢ each copy except Annual Cost Issue. Semi-annual indexes will be sent on request.* ENGINEERING NEWS-RECORD *is also indexed in Industrial Arts Index and Engineering Index.*

THE CONSTRUCTION WEEK

BY-PASS AROUND MOSCOW—The Soviet Union has embarked on a major highway construction program that will speed east-west travel in its European area—and permit rapid evacuation of Moscow. A key part of the plan calls for encircling Moscow with a 50-mi-long belt parkway to divert transit traffic from the city and provide internal communication between numerous spoke-like thoroughfares radiating from the center of the capital. The parkway featuring two 20-ft-wide roadways, will girdle the city at an average distance of eight miles from the Kremlin.

INSPECTION STANDARDS SET UP—The Concrete Industry Board of New York City appears ready to take its first definite step to upgrade concrete. At its next meeting, it will act on a proposed Manual of Recommended Practice for Inspection and Testing of Concrete Materials and Concrete. Included are recommendations that qualified testing laboratories be employed by the owner or architect-engineer and not by the contractor and that competitive bidding should not be the basis for selecting a testing laboratory. No procedure has been announced yet for enforcing the recommended practice.

PERFORMANCE-STANDARDS CODE—An unusually liberal building code will go into effect in Seattle, Wash., Oct. 10. For example, instead of spelling out requirements for steel design, the code prescribes that steel be used in a manner conforming to "accepted American engineering practices and subject to rational analysis." Requirements for plastering are confined to fireproofing applications, no limitations being placed on plaster for decorative purposes. Replacing a 14-year-old code, the new regulations were prepared by Talbot Wegg, who now has returned to private practice as an architect.

TOO MUCH, TOO SOON?—With their worries over getting a national highway program through Congress now well past, the Institute of Traffic Engineers found a new set of problems to worry about. Specifically, this was their concern: Maybe there's more money and more work available than the country is able to absorb. Speakers at an annual meeting in San Francisco listed these facts: Factual data are lacking to back the 41,000-mi program; some states haven't legislative setups to cope with the program; public support has still to be marshalled for specific projects; administrative changes are needed in the states to prevent loss of time in the program; there aren't enough engineers available.

3 GENERATIONS BUILD WEST COAST CONSTRUCTION EMPIRE



Starting 76 years ago, as a small contractor, Adolph Teichert built the versatile organization that has what it takes to lick the big ones pictured above. Today, when you see a giant West Coast job—quarrying, earth-moving, road, rail bed, military base or dam building—it's a fair bet that A. Teichert & Son, Inc., have a hand in it! Earthmover shown above has Goodyear Hard Rock Rib tires on front wheels, Hard Rock Lug on rear.

Now Goodyear "is there" with 3-T Nylon Cord Tires... TUBELESS or TUBE-TYPE

For well over 2 years, Goodyear Triple-Tempered 3-T NYLON CORD tires have been breaking records for stamina and endurance on the toughest jobs in our land.

And now your savings can be even greater—your tube and flap troubles ended forever—with Goodyear *tubeless* tires for every type vehicle *regardless of size!*

Leading equipment manufacturers have adopted Goodyear tubeless tires as standard—or will supply them as specified. Or you can convert your present equipment to Goodyear tubeless. Get the facts from your Goodyear dealer.

Goodyear, Truck Tire Dept., Akron 16, Ohio



FOR EACH JOB, THERE'S A COST-CUTTING GOODYEAR TIRE BUILT WITH 3-T NYLON CORD

Buy and Specify

GOODYEAR

MORE TONS ARE HAULED ON GOODYEAR TRUCK TIRES THAN ON ANY OTHER KIND

Road Lug, All-Weather, Sure-Grip—T. M.'s The Goodyear Tire & Rubber Company, Akron, Ohio

Look for this sign; there's a Goodyear Dealer near you.

WASHINGTON OBSERVER

The new credit relief for lower cost housing will be followed with more government aid if the hoped-for remedies fail to shore up the industry. Administration officials hope the lower down payment provisions and easier borrowing from the Federal National Mortgage Assn., and home loan banks will help, at least in smaller towns and less populated regions. Housing industry spokesmen are still pessimistic.

But Administration economists see the problem of availability of credit to segments of the economy—housing, small business, farming—as a long-term one. They figure: A tight money rein on industry generally is probably going to be a way of life for some time to come because of the prospects of continuing demands for money and materials from capital expansion programs of industry.

So special easing devices are going to be needed for particular cases. One now being pushed by the Administration: resort to a little used function of the district Federal Reserve Banks permitting loans to businessmen who can't obtain them elsewhere. Another publicized by last week's meeting at the White House of small businessmen: The Small Business Administration has up to $50 million to lend, the lure to attract a contractor or businessman to come and get it.

The Federal Housing Administration is changing its policy in order to convince lenders they can make advance commitments to builders for housing. A builder now will be permitted to absorb more than a 2½% discount to the lender in assuming mortgages on houses he may have to take on if sales are temporarily sluggish.

•

Niagara Mohawk Power Co. wants to rebuild part of its plant that slid into the Niagara River last June. It has filed an application with Federal Power Commission to rebuild one generating unit partially damaged by the slide. The company previously has gotten behind the attempt of the New York State Power Authority to build a new Niagara plant, in exchange for some of the power the proposed publicly-owned plant would generate.

•

The military is moving toward using contractors more and more for operating and maintaining installations and equipment—instead of uniformed personnel.

A good example is the so-called DEW Line, the Distant Early Warning radar network being built across the roof of the continent in the Arctic. The Air Force is about to award IT&T's Federal Telephone and Radio Co. a contract to maintain and operate the system.

•

Corps of Engineers is under new management this week as Maj. Gen. Emerson C. Itschner takes over from Lt. Gen. Samuel D. Sturgis, Jr. Itschner is the youngest Chief of Engineers in more than 100 years—he's 53. He's been preparing for the take-over since last August when the White House announced his appointment; he just got back a week or so ago from a round-the-world tour of overseas operations.

Itschner has primary job of following through on long-range problems already being tackled—on personnel, getting and keeping good engineers from West Point, R.O.T.C., and civilian life; keeping the Corps' position as a combat outfit; keeping the Air Force happy without a Corps of Engineers of its own; and keeping its record up on civil works construction. Also, there's the important job of keeping its foot in the White House door in cases where other agencies—Agriculture and Interior, for example—also are called upon for advice. (ENR next week will have a detailed report of these problems and Itschner's plans to handle them.)

PRECAST, PRESTRESSED CONCRETE FOR *Speed and Economy*



M. C. SCHRANK COMPANY,
Factory and Warehouse, Bridgeton, N. J.

General Contractor: **MESSICK BROTHERS**, Bridgeton, N. J.

Prestressing Engineer: **KEAST & HOOD**, Philadelphia

Precast, Prestressed Members Produced and Erected by:
FORMIGLI CORPORATION, Berlin, N. J. · Philadelphia, Pa.

66 Precast Bays Go Up in 11 Days

● Winter often slows concrete work, but on this concrete building in Bridgeton, N. J., columns, beams and floor members were factory precast and shipped to the site from 30 miles away. As a result, 66 precast bays went up in 11 days on this new 120 by 220-ft. industrial building in Bridgeton, N. J.

Key to fast erection was the use of all precast components. Precast 38-ft.-long columns support 19-ft. pretensioned beam soffits that, in turn, carry 1½-in.-thick, precast channels, 24 in. wide by 10 in. deep by 19 ft. 4 in. long. These channels form the base for a 2-in. cast-in-place concrete topping that comprises the floor surface.

The prestressed beam soffits form the bottom half of the web of a composite T-beam, completed when the topping was placed. Beam soffits were prestressed to carry both the dead load of the channels plus that of the topping. Prestressing was accomplished by tensioning sixteen ⅜-in. strands.

All components were cast at the Berlin, N. J. plant of the Formigli Corporation and shipped to site by truck. Fast, economical erection again confirms the importance of quality members fabricated to closest tolerances under factory-controlled conditions.

Confirmed again, too, is the advantage of using 'Incor'* 24-Hour Cement for the assembly-line production speed which means maximum output with minimum form investment—with the big quality plus that always goes hand in hand with the use of America's FIRST high early strength portland cement.

*Reg. U. S. Pat. Off.

LONE STAR CEMENTS COVER
THE ENTIRE CONSTRUCTION FIELD

LONE STAR CEMENT CORPORATION

Offices: ABILENE, TEX. • ALBANY, N.Y. • BETHLEHEM, PA.
BIRMINGHAM • BOSTON • CHICAGO • DALLAS • HOUSTON
INDIANAPOLIS • KANSAS CITY, MO. • NEW ORLEANS • NEW YORK
NORFOLK • RICHMOND • WASHINGTON, D.C.

LONE STAR CEMENT, WITH ITS SUBSIDIARIES, IS ONE OF THE WORLD'S LARGEST CEMENT PRODUCERS: 18 MODERN MILLS, 38,000,000 BARRELS ANNUAL CAPACITY

The Team:

Mark D. Hollis, Chief Sanitary Engineering Officer of the U. S. Public Health Service has 8½ years in the job. But until now, he hasn't had construction grants to worry about.

Gordon E. McCallum, with the rank of Sanitary Engineer Director, knows the states' problem from long experience in PHS regional offices.

Arve H. Dahl, McCallum's brand new assistant is 40-year-old newcomer to this level of PHS administration.

The Task:

How to Spend a Half-Billion Dollars

There is reason to believe that eventually it will be administered to good effect, but so far the nation's new Water Pollution Control Law is a deterrent, rather than a stimulant to sewage treatment plant construction.

While the complicated machinery of federal aid is being assembled by federal and state water pollution control agencies, sewage works projects in many places are being held up in hopes of grants from the federal government.

This was certainly to be expected, this period of confusion. For while the law as enacted (ENR July 5, p. 28) put responsibility for construction grants properly in the hands of state sanitary engineers, it prescribed only principles and left a heavy burden of administration to be worked out by the stage agencies and by the U. S. Public Health Service. This is taking time.

During September, as the law reached three months in force, ENR checked with Assistant Surgeon General Mark D. Hollis for a report on overall progress by PHS. Gordon McCallum, chief of the Water Supply and Water Pollution Control Branch within PHS, and his lieutenant, Arve H. Dahl, were consulted on procedures. Then a group of key state sanitary engineers were reached for their intimate knowledge of how the law is affecting and will affect sewage plant construction in their states.

In all quarters there is resignation to this new law of the land. Few if any of those contacted are happy with it. It should be remembered that both the Public Health Service engineers and those engineers of state and interstate agencies whose views were voiced before passage of the law, expressed doubts that its grants-in-aid provision would do good. This was established in the ENR-sponsored conference on the question in St. Louis last spring (ENR June 7, p. 40).

Now, two-thirds of the state sanitary engineers contacted state flatly that the law has become a deterrent to sewage works construction. The other third say that it has not slowed progress yet, but they expect it to do so.

Most of these men believe that the $50-million annual appropriation for grants, for the ten-year aid period prescribed in the law, is just not enough money to do the job of stimulating water pollution control.

• **Determined to make aid work**—But despite these reservations, there is an expressed determination in the states to see that the available money is spent to best advantage. And in Washington, there is a determination to get the aid rolling as soon as possible to end this initial period of halt and hesitation.

Barring some unforeseen hitch, Mark Hollis and company think they are now only weeks away from getting the grant program into operation. McCallum and Dahl have thrashed out many of the problems with officials of every state in a series of meetings through August and September. At the federal level there remain questions of which types of projects are proper candidates for aid—questions such as whether incompleted work started since the July 31 cutoff date established for the law is now eligible for aid. (On one side, giving aid to such projects would not be stimulating new construction; on the other hand, withholding aid from work just started will deter those about to start from going

To get federal aid:

Check to be sure you have . . .

- ☑ Description of project—new plant, extension, etc.
- ☑ Estimate of costs—total and a breakdown
- ☑ Size of grant requested
- ☑ Evidence that the project is part of the State water pollution control plan
- ☑ Idea of whether and how it will conserve water
- ☑ Authority to finance, build and operate the project
- ☑ Source and supply of funds available for both construction and operation
- ☑ Measure of population to be served
- ☑ Legal description of site
- ☑ Schedule for bids, awards and construction
- ☑ Any available engineering reports, plans and specifications

Then you face a series

You
Submit application
You, or your consulting engineer, for you, will make application to your state water pollution control agency.

PHS
Approves plans
Approval of plans by PHS means bids may be asked and contracts awarded. PHS will also approve contract awards, as a final requirement.

You
Get your money

ahead—as may already be happening.)

At the state level the basic problem is how to establish priorities for disbursement of the aid. From their meetings with state agencies around the country, the PHS people report that this problem will be solved without any difficulty. But from what the state sanitary engineers say, it remains a tough nut, yet to be cracked.

It is at the municipal level that real enthusiasm for the federal-aid idea is to be found. PHS already has received unsolicited queries for information from 4,000 communities.

Other queries are directed to the state agencies. The interest so far has been tremendous.

• **Machinery being assembled**—All that can be told the cities for now is that the application forms for financial aid are in the Bureau of the Budget for approval (a necessary prerequisite) and that the bureau has asked Surgeon General Burney for criteria governing propriety of federal aid before it issues its approval. Such propriety criteria are not intended or expected to infringe on the primary role of apportioning the aid which is given to the states under the law.

Forms awaiting Budget Bureau clearance cover the steps to be taken from a city's application for a grant to actual award of the grant by the Surgeon General. These steps will be about as presented in the accompanying box, but this is not necessarily the exact sequence. It is not intended to make all states conform to a rigid, federally dictated procedure.

PHS regional offices will figure heavily in administration of the aid provision. They will be on hand to fill in personnel gaps in state agencies and help process applications. It is also expected that consulting engineers will help expedite things by discussing with state agencies the proposed projects of their clients, the municipalities.

State sanitary engineers are as much or more concerned with criteria as are their cousins in PHS. But while PHS is involved in establishing propriety of aid, the states must find ways of fixing priority for it. Projects certified for aid by the states are intended under the law to have priority on the basis of financial as well as water pollution need. And the financial need is a quantity not previously of so much concern to state sanitary engineers.

• **Figuring who should get aid**—Indiana's Blucher Poole says his Stream Pollution Control Board is considering the median income of families and unrelated individuals as a measure of a community's ability to pay. H. E. Moses in Pennsylvania plans to use average income in some way.

California's Vinton Bacon reports study of a point system based on assessed valuation per capita and construction costs per capita. A high construction cost and low valuation would be good

Mark Hollis . . .

"Reports from around the country indicate that for the moment letting of contracts for the construction of sewage treatment works has slowed down somewhat. City officials are naturally reluctant to take any steps which in their opinion might make it difficult or impossible for their communities to qualify for a federal grant under the new program. We are confident that this situation will clear up in a relatively short time. As the President pointed out in approving the new act, federal aid will not be available to all communities. The President urged that 'no community with sufficient resources to construct a needed sewage treatment project without federal aid, postpone that construction simply because of the prospect of a possible federal grant.' I am sure that communities with the necessary resources will see the good sense of the President's advice and that those communities which can go ahead on their own will do so."

of steps similar to these . . .


State
Qualifies application
If your project qualifies and has priority for aid, your application will be forwarded to the regional office of the Public Health Service.
PHS
Approves application
Regional office will check your project against federal criteria (now being drawn). If project passes test, PHS will make construction grant offer to you.
You
Submit plans
You accept offer and go ahead with preparation of plans and specs. Plans and specs must then get approval.
State
Qualifies plans
Finished plans and specs are submitted through the state regulatory agency to the PHS regional office.

evidence of a city's need for aid, it is figured. However, California in its present thinking would be influenced more by the pollution need than by the financial situation in establishing its priorities. This is not final policy, yet.

There's additional evidence that the state sanitary engineers may concern themselves more with pollution than economics where they set priorities for aid:

Washington's E. F. Eldridge expects to assign priorities on a basis of how acutely a plant may be needed. Ohio's Fred H. Waring indicates the Pollution Control Board there will have to make financial needs secondary to pollution control needs if the available amount of money is to be made to do most good.

John Wakefield of Florida's Bureau of Sanitary Engineering points out a peculiar problem there: The $5,000 homestead exemption, resulting in low taxes, has meant that almost all recent projects have been revenue financed. Fiscal reports from cities will be needed to determine where aid is needed in future revenue-financed work.

• **Its possible effects**—ENR correspondents have asked in the states whether the federal money will inspire cities planning primary treatment to build secondary treatment instead. Not if primary facilities were the right answer in the first place, was the concensus.

It was asked if the aid, which definitely is intended to favor the smaller communities, might not discourage the desirable regional approach with communities banding together. Only Michigan's Loering Oeming, and Eldridge of Washington thought this could happen. D. F. Smallhorst in Texas thinks the law could conceivably have the opposite effect, encourage the authority approach.

In Texas, incidentally, Smallhorst has been put in charge of a Division of Water Pollution Control newly organized under the State Department of Health—just since passage of the federal water pollution law. V. M. Ehlers is still state sanitary engineer.

With most of these key state sanitary engineers unhappy over, but resigned to, federal aid, some go so far as to suggest the three-month-old law be changed.

A Kansas spokesman says: Either eliminate the construction grants provision or make enough money available so that every eligible community could receive aid to 30% of project cost.

Actual recommended changes under consideration by the State and Territorial Health Officers include: Redistribution of grant funds to place the money in states where projects are ready for construction; increase in appropriations to permit construction grants to all eligible projects.

• **Its long-range effect**—With all the present unrest and disruption of construction's progress, this phase of getting the pollution law to work should be over soon and should not have had either serious or lasting effect. There are rays of sunlight coming through even now as some states report no lagging of cities under order to build plants. The smart communities with plants ready to build are reported to realize that a sizable future cost increase might erase any federal aid they might get by waiting. And in several states it is evident from requests for information that communities not formerly planning sewage works have new interest in building facilities since the aid money became available. Incidentally, federal officials guess that 80% of the grants money will go to cities under 125,000 population. The law specifies a minimum of 50%.

Finally, behind the passing cloud of confusion there is the brightest light of all: Sewage works construction overall is booming, headed for a $600-million year, according to ENR's forecast. Despite tight money, and even granting some slowdown through the current period of waiting-for-aid, ENR predicts another $600-million year next year (ENR Sept. 13, p. 144) in this ever-lagging field of construction which has never in the past amounted to more than $431 million in contract awards (1953) and which only last year was back to $402 million.

Of course, final effect of the $50 million in federal aid this year and $500 million of the next 10 years remains to be seen.

Result of a Rescue

Sewer gas is responsible for two deaths in N. Y.

Two men were killed last week at Hastings-on-Hudson, N. Y., while assisting in the rescue of a third man who had been overcome by fumes inside a sanitary sewer.

During the rescue efforts, both men also were overcome by the fumes and were carried by flowing waste for more than a half-mile through an underground trunk sewer. The victims were employees of the Westchester County Department of Public Works.

The third man, an employee of a sewer contractor, later was reported in serious condition at a nearby hospital where he had been taken for immediate treatment.

Police said the accident occurred while the contractor's employee was connecting a 6-in. service sewer pipe to the 8-ft trunk sewer that leads to the county sewage disposal plant. When he called for assistance, the two county employees entered the manhole and started to lift him to other rescuers at the surface. A few moments later they were swept from view.

Members of the rescue party recovered the bodies of the men at a manhole opening scarcely three miles from the disposal plant.

APWA convention hears some pointed answers to the problem of . . .

Authorities vs. Elected City Officials

A spirited attack on special governmental units highlighted the 62nd annual convention of the American Public Works Association held in Fort Worth, Tex., last week.

Spearheading the assault was Dennis O'Harrow, Executive Director of the American Society of Planning Officials who lead off a four-man panel. Mincing no words in characterizing local authorities, he said, "We exchange one set of intelligent politicians sensitive to the citizens wishes for a group of inept politicians who, because of their amateur standing, don't give a damn about the citizens."

O'Harrow made clear this sweeping statement did not apply to all special districts and authorities, and granted that one category of these agencies—those established to pass over political boundaries—may sometimes be justified. But this was all he allowed. He saw great danger in the multiplicity of special agencies established to escape financial debt limits (adjust the debt law); to undertake projects of doubtful governmental concern such as buildings for industry (there are better ways to attract industry); and to avoid imaginary political messes by removing the operation from the direct control of regular municipal authorities.

The danger, in O'Harrow's view which was enthusiastically applauded by most of the 1,000 convention registrants, is that the more single-purpose governmental units, the more obstacles to orderly municipal planning and growth.

Edward E. Reid, Executive Director of the Alabama League of Municipalities, followed O'Harrow and gave him support by showing how Alabama cities, by the intelligent use of some very liberal extraterritorial controls granted by the state legislature, have avoided the formation of special units of government. There are no state laws authorizing their formation and there has been no demand for them.

Some of the powers granted to Alabama cities in the public works field are the authority to construct street and sewers within three miles of the corporate limits and to assess property owners for same; the authority to extend gas, electric and water systems for an unlimited distance and the authority to enforce subdivision, planning and zoning regulations up to five miles outside their corporate limits.

Panelist August O. Spain, Chairman of the Department of Government at Texas Christian University, gave indirect support to the O'Harrow-Reid position by boosting home-rule annexation laws of Texas. Those laws enable cities to annex contiguous areas in a relatively unencumbered manner and are a boon to orderly, well planned growth, in Spain's opinion.

• Employee Training

Another panel—on employee training—pointed up the growing interest and action being taken by public works leaders on the manpower problem, more serious in the municipal field than in many others. The avid attention and favorable comments of the audience was the most significant aspect of the discussions; much of what the speakers said was old hat, at least to personnel men.

The final panelist called on APWA to add to its national staff an expert to devote full time to employee development. Chances are that the association will respond.

APWA's training committee is soon to publish a comprehensive report and the convention went on record requesting engineering colleges to include a municipal option in their undergraduate curricula and to offer a master's degree in municipal engineering and administration.

• Municipal Sanitation

Municipal sanitation received a big play in two general session papers. One by Andrew W. Mulrain, New York City's Commissioner of Sanitation, described Gotham's $60-million a year ten-phase clean city program. Among the points: a house-by-house survey to ascertain the source of the 300 million pounds of material that annually finds its way to the streets of New York, a 300-man inspection force that in 1955 gave out 130,000 summonses resulting in $500,000 worth of fines, alternate-day alternate-side-of-street parking regulations rigidly enforced by tow trucks (minimum fine $15 plus $10 towing charge), and a no fooling around crackdown on owners of empty lots wherein if necessary the Sanitation Department cleans them up and charges costs to owner's tax bill.

Scottish visitor N. M. Wilson, president of the International Association of Public Cleansing, reviewed refuse disposal and street cleaning practices in Great Britain (much the same as in the U.S.) and then voiced great confidence in a recent composting system employed by his own Edinburgh Sanitation Department. Refuse enters a revolving drum and forms a finely divided material that easily and quickly composts with liquid sludge from the sewage treatment plant in three to five days, producing a dry, inoffensive compost of first-class value as a fertilizer.

In a "shirt sleeve" session on refuse disposal, Lou Weaver, U.S. Public Health Service sanitary engineer, pointed out that the increasing rate of installation of garbage disposal grinders in households indicates that by 1965 about half of the urban population of 84 million will be using this method. Weaver also documented the trend toward sanitary landfills (which the British euphemistically call land reclamation)—800 cities now compared to 100 in 1946.

• Electronics

Applications of electronics in public works were surveyed by Howard Jacoby, Associate Editor of ENGINEERING NEWS-RECORD in a general session talk. He measured the ever-growing use of elec-

State to Be Asked to Curb Authorities

A new law designed to bring all state and local commissions and authorities under uniform administrative and budgetary control will be asked of the 1957 Pennsylvania legislature by Attorney General Herbert B. Cohen.

Concerned over purported abuses of power by many such groups—notably the Pennsylvania Turnpike Commission, with which the Leader Administration has been carrying on a running battle—Cohen has stated: "The correction of this situation should be one of the first problems tackled by the next legislature."

As a result of findings in recent investigations into activities of the Delaware River Bridge Commission and the Turnpike Commission (ENR Sept. 13, p. 24), the Attorney General has started a study of financial operations of 977 municipal authorities (ENR June 14, p. 139).

Cohen says: "The free hand accorded themselves by the larger commissions has set a trend which finds most of the local authorities adopting the same independent policy on their operations."

In an open bid to eliminate or at least hamstring the commission type of government, the Democratic Administration will ask for controls on the Delaware River Joint Toll Bridge Commission, the Pennsylvania Turnpike Commission, the Delaware River Power Authority, and more than 500 local authorities.

ROBERT L. ANDERSON . . .
. . . New APWA President

tranic computers in engineering, in terms of its application in highway design and construction (ENR July 19, p. 29), design of rigid frame structures, analyzing water distribution systems by the Hardy Cross method and preparing construction progress reports. Other recent applications of electronics described were use of FM radio to replace multiconductor cable in transmitting control signals to traffic lights, radar traffic detection in a system that automatically and continuously allocates green time to favor the heaviest traffic flow, and measurement of liquid levels—using radioactive isotopes in a float.

In another general session talk, Maj. Gen. J. S. Bragdon, special presidential-assistant for public works planning, stated the case for advance planning.

A point of probable controversy in connection with the interstate highway system was touched on by Stanley C. Palmer, City Engineer on Kansas City, Mo. He felt he mirrored the views of his contemporaries in other cities as he called for urban portions of the interstate system to be located and designed for maximum usage by local traffic instead of primarily for through traffic.

For APWA, the Fort Worth meeting was the biggest ever (1,415 registrants, including wives, and 68 exhibitors). Robert L. Anderson, Superintendent of Public Works for Winnetka, Ill. was elected President, succeeding Edward P. Decher of Newark, N. J. Sol Ellenson, Director of Public Works in Newport News, Va. is the new vice president.

Casimir Rogus, engineering head of New York City's Sanitation Department received the Charles W. Nichols Award, a $500 prize for leadership in municipal sanitation. The second annual ENGINEERING NEWS-RECORD Fellowship, a $1,000 stipend for advanced study of public works engineering or administration, went to Dan Blankenship of Corona Del Mar, Calif., who will do his post-graduate work at the University of Oklahoma.

U.S. vs. Foreign

Turbine issue persists at Ft. Gaines, Priest Rapids

The question, "U. S. or foreign turbines?" continues to be an issue at two projects this week—the Ft. Gaines, Fla., hydropower plant and Priest Rapids Dam.

As a result of a taxpayer's suit, the Grant County (Washington) Public Utility District has decided to go ahead with plans to accept British-made turbines on Priest Rapids Dam project.

Merritt-Chapman & Scott Corp., contractors on the job, originally had submitted the British bid in their contract bid. Later it was decided to switch to turbines made by Allis-Chalmers, which would have cost an additional $500,000 (ENR Sept. 20, p. 26). The taxpayer's suit was filed to prevent this switch and the commissioners, rather than delay the project, decided to go ahead with the British turbines, which are to cost approximately $12 million.

The PUD commissioners had decided to switch to Allis-Chalmers on the basis that this company was experienced in the manufacture of large turbines, the British firm was not.

Commissioner George Shuster said the legal delay, combined with the river's high water stages, would set the project back at least a year.

• **Ft. Gaines project**—The Corps of Engineers in re-advertising for bids on the supply of turbines for the Ft. Gaines, Fla., hydropower plant has sidestepped—temporarily—the issue of "Buy American" from U. S. suppliers.

For four months American turbine manufacturers have been waiting to see if the Corps of Engineers would award the contract to English Electric Co., whose bid was approximately 17% lower than the nearest U. S. bid.

Officials of the Corps state that they are re-advertising for bids on the basis of "ambiguities" in the specifications submitted by both U. S. and foreign suppliers.

The Eisenhower Administration has been under sharp criticism for months for lowering the preferential margin to U. S. manufacturers from the traditional 25% to as low as 6% to give foreign suppliers a better chance in the American market. Turbine as well as generator and transformer manufacturers have complained that with the reduction foreign suppliers can underbid U. S. competition at will.

Recently the Hydraulic Section of the National Electrical Manufacturers Assoc. presented its case to the Office of Defense Mobilization. The NEMA group told the ODM that the decision as to whether federal procurement of hydraulic turbines should be limited to American suppliers could not continue on a case-by-case basis.

"The industry is too vulnerable to federal procurement policies to survive piecemeal determination of its future," said the NEMA.

In support of its argument for tighter restrictions on foreign suppliers, the NEMA said that the market for U. S. suppliers abroad already had been destroyed by foreign manufacturers.

Navigation or Power

The Missouri River Basin argument starts anew

First evidence of a new rift between supporters of power and navigational interests was evident last week at a meeting of the Missouri Basin Inter-Agency Committee at Mitchell, S. D.

It came after a talk by Joe W. Grimes, chief engineer and executive officer of the South Dakota Water Resources Commission. Grimes' speech emphasized the importance of winter generation of power at the Army Engineers' and Bureau of Reclamation's Missouri River dams.

Generally, water stored in the winter time is released in summer to maintain a navigable depth in the Missouri River during the summer.

Winter production, Grimes declared, governs the amount of firm power that can be produced and therefore increases total revenue obtainable from the sale of electric power from the dams.

"Releases for a single purpose (i. e. navigation) is not compatible with the concept of multiple purpose operation," he said. "Put rather bluntly, I believe that we have let and are letting our desire to please people in the basin warp our business judgment and that we have made and are making some commitments which our water supply so far will not justify."

Grimes' remarks brought opposition from supporters in the lower basins who regard navigation as a big factor in the future of that area.

Gov. Leo Hoegh of Iowa, who is chairman of the Missouri River States Committee, said: "I feel that there are three objectives in the development of the Missouri River. They are flood control—which has been accomplished—navigation, industrial development and use of power."

"All three must survive," Governor Hoegh said. "There must not be a favoring of one over the other to such an extent that we will lose any. Certainly navigation must be strengthened because it helps us industrially. But the objectives of the development are about in the order I've outlined."

Illinois Kicks Off Tollroad Program

Construction now is under way on Illinois' 193-mi system of tollroads—with target completion dates of Dec. 31, 1957, for the northwest route to Rockford and South Beloit, and the east-west route to Aurora, and one year later for the Tri-State route encircling Chicago.

Groundbreaking ceremonies, held Sept. 22 in a cornfield beside U.S. Highway 20, just east of Rockford, officially marked the start of construction on the $415-million project. Following speeches by Gov. William G. Stratton of Illinois, and Charles Dearing, Executive Director of the Illinois State Toll Highway Commission, a $1-million fleet of earthmoving equipment went to work in earnest.

Public Constructors, Inc. Camden, N. J., holds a $3-million contract for constructing a 4.8-mi section of four-lane divided highway on the Chicago-Rockford route, which was the scene of groundbreaking ceremonies (ENR Aug. 30, p. 24). The company has 440 calendar days to complete the section.

Major contract items on this section of tollroad together with unit prices submitted by Public Constructors include: roadway excavation, 1,100,000 cu yd at $0.43; selected subgrade, 60,000 cu yd at $2.50; 100,000 cu yd of granular subbase at $2.50; a 10-in. reinforced portland cement concrete pavement, 180,000 sq yd at $5.60; and 3-in. bituminous concrete shoulders, 105,000 sq yd at $1.25.

Public Constructors' unit bid prices for bridge construction include: $45 per cu yd for reinforced concrete; $0.11 per lb for reinforcing steel; $2.00 per lin ft for erecting both 36-in. and 48-in. prestressed concrete beams; $55 per lin ft for furnishing and driving prestressed concrete cylinder piles; and $5 per lin ft for furnishing and erecting the aluminum handrail.

As explained by Dearing, this 4.8-mi initial construction section near Rockford will be representative of the project as a whole. "The toll-way system will embody the latest advances in highway travel convenience," said Dearing.

This so-called northwest route will provide direct access from the Rockford-Beloit area to downtown Chicago through a direct connection with the Northwest Expressway. There will be no traffic lights or stop signs and—with the exception of a brief pause at toll barriers—no interruption to the flow of high speed traffic. Passenger car tolls for the 88-mi route will be $1.25 one way. For lesser distances, passenger car tolls will average 1.6 cents per mile.

The 80-mi Tri-State route starts on Chicago's south side, and cuts through and around the Chicago metropolitan area to connect with U. S. Highway 41 just south of Wisconsin line. The 25-mi east-west route is a continuation of the Congress Street Expressway, merging with U. S. Highway 30, a short distance west of Aurora. The 88-mi northwest route begins at U. S. 51 just south of South Beloit, crosses the Fox River north of Elgin, and connects with the Northwest Expressway.

Placing Record Claimed For Submarine Pipeline

Working 16 hours a day for five days, the Collins Construction Co., Port Lavaca, Tex., completed a 60,000-ft pipeline under Corpus Christi Bay, Sept. 17, for what is claimed to be a world's record for speed on this type of job. The 10¾ in. dia concrete-coated steel pipe, will carry natural gas to a Reynolds Metals Co., plant at La Quinta, Tex.

Water at the site is up to 55 ft deep, and there were winds up to 35 mph at some stages of the operations. The line was installed in 4,000-ft sections, using special methods of lateral control and controlled buoyancy and flotation developed by the contractor. According to S. V. Collins, president of the company, the cost of laying the marine line compared favorably with that of lines of the same type and quality laid on land.

The previous world's record for submarine pipelines was established in 1953 when J. Ray McDermott placed 55,000 ft of the same dia pipe in 14 days in waters offshore of Louisiana.

Westinghouse to Develop Reactor for Yankee Electric

Westinghouse Electric Corp. has been awarded the contract to develop the nuclear reactor for Yankee Atomic Electric Company's new atomic electric generating station near Rowe, Mass.

The Atomic Energy Commission will assist in the development and operation of the 134,000-kw station which is scheduled for completion in 1960. Estimated cost of the new station is $35 million.

Yankee Electric, with headquarters in Boston, was formed by 12 of the major electric companies in New England for the specific purpose of building this commercial atomic power plant.

The nuclear portion of the plant will be of the pressurized water type, similar to the one which is being installed in the nation's first full-scale atomic electric plant at Shippingport, Pa.

The Dalles Dam: The Finish Is in Sight

With Oregon's magestic Mt. Hood in the background, The Dalles Dam project nears completion with final closure of the river scheduled for Mar. 1, 1957.

Looking downstream on the Corps of Engineers' $260-million giant, the entrance to the old The Dalles-Celilo Canal may be seen in the foreground along with the east fish ladder, a concrete non-overflow section, the powerhouse, another non-overflow section and then the spillway dam across the river.

Beyond the spillway dam is the Wasco County Dam with the navigation lock at extreme right.

Col. Jackson Graham is the Portland District Engineer in charge of the new multiple purpose project.



TOP OF DOME was framed at ground level, then raised a few feet by gin poles so other trusses could be attached. Procedure was repeated until all parts were assembled.

GIN POLE with hand winch was one of five used to raise frame during job.



AFTER COMPLETION of the 117-ft-dia, 46-ft-high frame, it was covered with 1,112 plastic-bonded glass-fiber panels, a few of which appear in the photo (arrow).

BUCKMINSTER FULLER in completed aluminum framework of dome he designed.

Dome Built in Reverse—Top First

A new aluminum and reinforced-glass-fiber dome manufactured for the U.S. Marine Corps is said to be the biggest such structure yet built. Designed as a portable hangar or repair shop, the prototype test model has a base diameter of 117 ft and a center height of 46 ft. Although the dome covers an area of 10,700 sq ft, it weighs less than 52,000 lb. It can be disassembled into packages of 100 lb or less and transported in two cargo planes.

Framing for the dome comprises 80 plane triangular trusses, measuring about 22 ft on a side, and other extruded members. The main triangles are subdivided into 16 smaller triangles, each framing a shallow pyramid of glass fiber bonded with polyester resin.

Adjacent trusses are joined at the corners by bolts and gusset plates. All frame members are made of aluminum alloy. The glass-fiber panels attached to the frame weigh 13 lb each.

The dome is designed for 20-psf vertical load, 150-mph wind and the weight of a jet fighter plane, suspended inside from several points. No structural function is assigned to the glass-fiber panels.

A novel method of erection was adopted by the Washington Aluminum Co., of Baltimore, manufacturers of the dome, in setting it up for display. Beginning at ground level, they assembled the five uppermost trusses of the dome. Then, by means of five gin poles set up around the site, they raised the assembled trusses a few feet off the ground and attached more trusses. They repeated the procedure until the assembly was complete.

Auxiliary lines from the gin poles were used during erection to handle sub-assemblies too heavy for man-handling. The final lift, elevating the top of the dome 46 ft above the ground, imposed a load of about 16,000 lb on the five gin poles. Each gin pole was equipped with a hand winch and operated by one man.

After being displayed in Baltimore, the dome will be disassembled and flown to the Mojave Desert for field testing by the Marine Corps. Simplified by a nine-color coding system for parts, field assembly will take 30 men 2½ days, according to the manufacturer's estimate.

The dome was designed by R. Buckminster Fuller, designer of the Ford Rotunda dome (ENR May 28, 1953, p. 31).

ADVERTISING

This advertisement appeared in *The Saturday Evening Post*, Sept. 29, 1956.

North Carolina's new U.S. 70—a four-lane divided highway with safe, gentle curves.

BLACK MOUNTAIN GRADE WAS A KILLER

Driving the old U.S. 70, east of Asheville, Paul Smith used to dread those hairpin turns. Now, on one of North Carolina's most spectacular highways, he makes the 1000-foot climb safely—in one third the time!

The mountain ranges of North Carolina rise out of the Piedmont like the side of a roof. When the original U.S. 70 was built, 30 years ago, its two narrow lanes of concrete scaled Black Mountain by a series of switchbacks. In the eight miles between Old Fort and Ridgecrest, there were 84 turns so sharp that trailer trucks could barely negotiate them. The roadside cliffs were scarred by many crashes.

Paul Smith, local businessman, says, "Only a year ago the best time I could make on that stretch was 20 minutes, and I drove it with my heart in my mouth." Today North Carolina's Highway Commission has relocated the route, building a four-lane divided expressway that cuts the distance to 5.7 miles, the time to 6¼ minutes. Long, sweeping curves and easy grades, none steeper than 6%, permit a safe speed limit of 55 miles an hour.

Those huge cuts and fills cost a lot of money, but everyone agrees now that it's worth it.

North Carolina has a progressive highway program. Its secondary system is one of the best in the country; and in proportion to area and population its 32,100 miles of paved roads lead all other states. Yet an estimated $610,000,000 needs to be spent on primary highways in the next decade. Federal highway aid will bring closer the dates when interstate expressway sections will be open to traffic. However, the basic problem of financing these and all other roads remains with the states.

Good roads save more than they cost—in time, in lives, and in actual cash. For proof, and for suggestions on how you can help, write for free booklet, "Road Block." Send a card today to Dept. 10, Caterpillar Tractor Co., Peoria, Illinois, U.S.A.

CATERPILLAR

REG. U. S. PAT. OFF.

DIESEL ENGINES • TRACTORS • MOTOR GRADERS
EARTHMOVING EQUIPMENT





Old U.S. 70—a narrow two-lane road with 84 hairpin turns.

Wherever you see Caterpillar machines working on your roads, you can be sure your state is getting its money's worth.

THAT BACKS THE ROADS YOU BUILD

The powerful impact of advertisements like the one on the opposite page, running in full color in *The Saturday Evening Post*, has helped rouse America to the need for new highways. Building them is your business. And you can build them faster and at lower cost today because of the great new equipment Caterpillar puts at your disposal.

In the same region of North Carolina described in the *Post* advertisement, Asheville Contracting Co. is using Cat* DW21 Tractors and No. 21 Scrapers, push-loaded by D8s. In the photograph they are shown at work on the construction of a new section of U. S. 70, bypassing Morganton and Hickory, N. C. It's a job that requires moving 3,500,000 cu. yd. of clay and shale rock, with plenty of deep cuts and fills.

Superintendent W. W. Ledbetter says: "In twelve years using construction equipment, it is my opinion that Caterpillar builds the best. It's more dependable—more economical—and there's good dealer service."

Caterpillar research, engineering and manufacturing are geared to a single goal: to provide you with constantly improved machines—to help you do more work and make more profit. Year by year they give you greater power and efficiency, longer work life. And Caterpillar Dealers back you with reliable service and parts you can trust.

Caterpillar Tractor Co., Peoria, Illinois, U. S. A.

CATERPILLAR*

*Caterpillar and Cat are Registered Trademarks of Caterpillar Tractor Co.

LEADERSHIP IN ACTION

Supplemental Guide

NSPE meeting to discuss an ideal registration law

The fall meeting of the National Society of Professional Engineers, to be held in White Sulphur Springs, W. Va., Oct. 25-26, will give members their first opportunity to examine in detail the completed draft of an "ideal" registration law, which a committee of the society has drawn up.

The purpose of the law is to provide a guide in writing amendments to state registration laws. It is not intended, it is stated, to replace the Model Law but to supplement this existing guide with a document that includes more present day thinking on some important questions.

One of these questions is the practice of engineering by corporations, and on this the Ideal Law states: "Professional Engineers may practice under this act as individuals, partners, or through joint stock associations or corporations. In the case of practice through a joint stock association or corporation, it shall be required at all times that the chief executive officer and a majority of the other executive officers and a majority of the directors be professional engineers under this Act." The Ideal Law also poses other modern questions to guarantee lively discussion, both at this meeting and later at the spring meeting (Charleston, S. C., Feb. 15-16, 1957) when other engineer organizations will be invited to take part.

As is usual for these meetings, the NSPE executive committee will convene in White Sulphur Springs the day before the convention begins.

Superstructure Bids Asked For St. Lawrence Crossing

Bids will be opened Oct. 10 for the superstructure of the international high-level bridge across the South Cornwall Island Channel of the St. Lawrence River, together with viaduct spans on both approaches and earthfill and pavement of the mainland approach.

The bridge, a suspension type, to cost $6 million, will have a 900-ft main span and 450-ft side spans (ENR Aug. 2, p. 22). There will be 2,145 ft of viaduct spans. The New York State approach fill will be 680 ft long on a 4% grade.

According to the Buffalo, N. Y., District of the Corps of Engineers, construction agent for the St. Lawrence Seaway Development Corp., the project must be ready for traffic by July 1958.

Substructure is to be built by the St. Lawrence Seaway Authority of Canada and is scheduled for completion by October 1957.

Skyhook for Surveying

Power dam reconnaissance in the rugged Cascade Mountains of southwestern Washington—ordinarily a slow and rigorous process—is making faster and easier progress, thanks to the helicopter.

One job benefiting from the airborne assist—the fourth phase of a five-part scheme sponsored by Pacific Power & Light Co.—is the Muddy hydroelectric project. It will be built on the upper Lewis River, a Columbia River tributary that runs through a steep-walled canyon high in the Cascades.

With the helicopter, pipe and other drill gear are hauled across ravines and over ridges to prospective sites. Ordinarily a four-hour trek using pack animals, the job now requires only about four minutes.

The first two phases of the program are already in operation, in the form of a pair of power dams—100,000-kw Merwin and 133,000-kw Yale. Third step is proposed Swift Dam, with a 256,500-kw potential that PP&L will develop jointly with Cowlitz PUD.

Nuclear Information Group Will Aid Utility Companies

A six-man committee to study various types of nuclear power plants was formed recently in New York by the Edison Electric Institute with the prime mission of keeping the private utility companies informed on new developments.

The committee, all top utility executives, will be headed by James F. Fairman, engineering vice president of Consolidated Edison Co.

According to Donald S. Kennedy, president of the Institute, the new group will have $150,000 at its disposal for investigations and will use outside engineering and consulting firms as it sees fit.

Who Will Pay?

Ohio mayors still solicit state-financed expressways

Mayors of Ohio's largest cities plan to continue their fight for state funds in building expressways through their cities.

They received encouragement recently in Columbus at a highway conference when Detroit Commissioner of Public Works Glen C. Richards declared that states should pay for such expressways through cities.

Under present federal-state arrangements the federal government pays 90% of the cost of the interstate highways and the states provide 10%. But Ohio agrees to its responsibility of 10% of the cost only in areas that are located outside metropolitan city limits (ENR July 26, p. 24).

In opposition to this stand Richards said: "The state cannot build only the rural portions of such highways and leave them at the city limits."

Regardless of attempts to compromise, the Ohio Highway Construction Council is standing pat on the formula that cities provide the 10% for expressways inside the city limits.

Support for the mayors came recently from Gov. Averell Harriman of New York. He announced that New York State cities having urban arterial projects designated as part of the interstate system would not have to contribute to the cost because the state would put up the 10% for both city and rural routes.

Record Won't Be Broken Yet, One Long Becomes Two Shorts

Sometimes records for records' sake must go. What would have been one of the world's longest pipeline suspensions—1,300 ft—will now be two shorter spans, one of 700 ft and another of 600 ft. The spans are part of a 70-mi gilsonite-water-slurry pipeline from Bonanza, Utah, to Grand Junction, Colo. Gilsonite is a pure asphalt found mainly in Utah.

A contract has been let to United States Steel Corp. by American Gilsonite Co. to build one 700-ft span across the White River and, a mile to the east, to construct another across Evacuation, Wash. As originally conceived the pipeline would have jumped both the White River and Evacuation, Wash., in one 1,300-ft span.

The pipeline will transport gilsonite to a coke-refiner and high-test gasoline producer, which American Gilsonite Co. is erecting just south of Grand Junction.

Engineers Ltd., have been awarded the contract for the 70-mi line.

HOW MOBILE CAT* POWER PAYS OFF FOR LAMBERT BROS., INC.

A D397 Mobile Electric Set provides crusher power on a job for Lambert Bros., Inc., near Greenback, Tennessee. The 315 KW D397, Caterpillar's biggest trailer-mounted electric set, is well within highway weight and size restrictions.

When Lambert Bros., Inc., Knoxville, Tennessee, received the contract to furnish 26,000 tons of base material for road construction near Greenback, it set up the operation pictured here. The company provided its own power with this Cat D397 Mobile Electric Set. The 315 KW unit provided the power to run the Cedarapids crusher, working 8 hours a day, 5 days a week. Output averaged about 900 tons a day. Said Lambert's Ben L. Greene: "I like the D397 because it gives us a maximum amount of operation with a minimum amount of maintenance."

For dependable electric power, *when* it's needed and *where* it's needed, you can't beat Caterpillar Electric Sets. They're available in a complete range of sizes, up to 315 KW, for use in emergency or full-time operation. Each is a complete unit, mounted on skids, semi-trailer or trailer. Easy to hook up and easy to operate, they deliver steady voltage. There's one that fits your needs and—as Mr. Greene points out—provides maximum performance with minimum maintenance.

Wherever you move these sets, you always have the plus of prompt service, right on the spot, from your nearby Caterpillar Dealer. For complete information about these versatile power plants, see him soon.

Caterpillar Tractor Co., Peoria, Illinois, U. S. A.

CATERPILLAR*

*Caterpillar and Cat are Registered Trademarks of Caterpillar Tractor Co.

MODERN, HEAVY-DUTY PORTABLE ELECTRIC POWER

"IDEAL" aggregate for Florida market

TELSMITH

designed Miami plant of IDEAL Crushed Stone Co., produces 400 tons per hr. crushed limerock and sand.

Telsmith 30" x 25' Twin Screw Sand Classifier.

•

Telsmith 5' x 12' double deck special heavy-duty Vibro-King Screen.

● With a capacity of over 400 tons per hr; 60% rock, 40% sand; this Telsmith-designed plant makes 6 sizes: ¾" to 2½" ballast; 1"-¾", ¾"-½", ½"-⅜", ⅜"-⅜6" rock; ⅜6" sand. A 4½-yd. dragline digs the raw material; self-dumping barges transport it to plant.

● Ballast goes to railroads. Aggregate qualifies for Florida State, County, and City specs; U. S. Army Engineers; ready-mix, concrete-block, and concrete pipe plants. Send for Bulletin 266.

Q-32

PLANT EQUIPMENT—Two 60" x 8' Heavy Duty Plate Feeders • 5' x 12' Special Heavy Duty Vibro-King Scalper ahead of 30" x 50" single roll primary crusher • 5' x 12' 2-deck Vibro-King Scalper ahead of reversible impactor secondary crusher • 5' x 12' 2-deck and 5' x 14' 3-deck Vibro-King Finishing Screens for rock sizing • 2' x 8' 1-deck Vibro-King Screen for fine sand • 30" x 25' Twin Screw Sand Classifier for coarse sand • 24" x 20' Single Screw Sand Classifier for fine sand • All Telsmith except crushers.

SMITH ENGINEERING WORKS

500 E. CAPITOL DRIVE **MILWAUKEE 1, WISCONSIN**

Representatives in Principal Cities in All Parts of the World • Cable Address: Sengworks, Milwaukee

Columbia Basin Pact

Federal agencies approve changes in original draft

Federal agencies have approved all provisions of the revised draft of the Columbia Basin Compact. The revisions alter priorities for water consumption to protect large federal installations in downstream states while allowing adequate supplies for upstream states.

The other major change from the original draft expands the term "major states" as commission members, and prevents the possibility of the five upstream states outvoting the two downstream states—Washington and Oregon—in matters involving water resources in the Columbia River Basin. This provision was changed at the request of Washington State.

Anderson H. Calvert, Secretary of the Compact Commission, said that "suggestions the states have been controlled by federal desires" in framing the compact are not true. "The compact commissioners have been trying to follow a practical course and avoid the possibility of Congressional objection or executive veto on the grounds of constitutionality."

Idaho, Nevada and Utah ratified the earlier draft and the commission expects these states to re-submit the pact to their 1957 legislatures. Washington, Oregon, Montana and Wyoming also must approve the draft, and then it must be ratified by Congress before taking effect.

Expensive Silt

Silting river is studied: Costly dam may be answer

A rapid silt build-up in the Snohomish River at Everett, Wash., which is threatening to curtail operations of lumber and kraft mills using the river, is under study by the Seattle District of the Corps of Engineers.

In recent years an increasing amount of water in the Snohomish River has been bypassing the main channel, going to Puget Sound through three sloughs. Engineers estimate that only 30% of the river flow actually follows the main channel at present.

With less water in the channel, the flow is slower. The slower the river flows, the more silt it drops. The greater the silt build-up, the less water will go down the main channel. Should this trend continue, the mills that are located on the lower reaches of the river will be unable to keep logs moving into their operations.

Logical solution seems to be construction of a costly dam, either across the river or across the mouth of Steamboat Slough, largest of the sloughs. The confined waters then would flow rapidly enough to move the silt into the deep waters of Puget Sound.

College Gets $50,000 Grant For Study of Traffic Safety

$50,000 grant for basic research in traffic safety has been made to Teachers College, Columbia University, by the American Automobile Association Foundation for Traffic Safety.

Columbia officials said that the studies—expected to take five years to complete—will take into consideration safety research programs that are now being conducted by other schools, so that there will be no duplication of effort.

The subject to be explored in both field and laboratory will include vehicles, roads and drivers, as well as the legal aspects of traffic safety.

Misuse of State Road Funds Is Under Probe in Kentucky

Charges that public funds have been used for construction of private roads and driveways in Harlan County, Ky., have resulted in discharge of three state highway department employees, investigation of others and preparation of legal action against private property owners who have benefited.

Some of these private roads are reported to have cost from $50,000 to $75,000.

Among examples cited were a bituminous farm road leading from State Route 217 and mine roads in the county.

Highway Commissioner Bert Kiser acknowledged that the charges—made by local newspapers—were "substantially correct."

He stated that his office has been investigating the Harlan County situation "for some time."



Silencer Building Quiets Jet Engines

Silence is golden, and community goodwill is worth plenty too, judging from Convair's outlay of nearly $1 million to muffle jet-engine noise at the firm's San Diego plant.

Under construction by Koppers Co., Baltimore, as part of Convair's F-102A interceptor program, four chambers—three for preflight engine runups (shown above), one for engine tests—will render engine roar inaudible half a mile away over other sounds in the area. Even in the immediate vicinity of buildings, noise will be damped enough to permit normal conversation.

The runup chambers will be 125 ft long, 60 ft wide and 35 ft high. Walls and sliding doors will be 12-in-thick concrete.

Fresh-air intake tunnels on each side of the section housing the plane will contain wave-shaped perforated baffles filled with glass fiber. Immediately behind the tail, exhaust gases will be diffused in water spray, then directed upward at the rear of the building through more wave-shaped baffles. The engine-test chamber will be similar in construction but will have an additional air-intake silencer.



To provide a freeway approach for the new Carquinez Bridge, earth will be moved at an ultimate rate of 40,000 to 50,000 cu yd per day from this three-mile stretch on U. S. 40, northeast of San Francisco

BIGGEST HIGHWAY CUT ever undertaken will remove 9,700,000 cu yd from this gap in the California hills.

Scrapers in Tandem Are Tools for Bigges

The biggest single earthmoving operation in highway construction history is getting in full swing on U.S. 40, northeast of San Francisco. The job—with 9,700,000 cu yd to be excavated from a single cut—will provide a freeway approach for the new Carquinez Bridge (ENR Dec. 15, 1955, p. 45). Much of the big yardage will be handled by tandem scraper units where one tractor will haul two scrapers with a total load of 40 cu yd.

The big cut will have a maximum depth of 300 ft and it will be nearly a quarter-mile across. This cut, together with two smaller ones, is wrapped up in a single $7-million contract that will provide three miles of freeway. Contractor is a joint venture of Ferry Bros., John M. Ferry, Peter L. Ferry & Son, and L. A. and R. S. Crow of Glendale, Calif.

The freeway contract is one of several totalling $30 million which will provide a new bridge crossing—together with the necessary approaches—across Carquinez Straits, an arm of San Francisco Bay. This particular stretch of U.S. 40 has in recent years become a major traffic bottleneck. But major work had been delayed due to the high cost of providing additional capacity for the three lanes carried by the existing bridge. In early 1955 the state legislature authorized a bond issue that would be financed by tolls on the existing bridge and its new parallel structure (the old bridge is now a free structure). And because the big cut makes the freeway approach more expensive than usual highway construction, it was included in the bond financing.

All of this was accomplished before recent passage of increased federal financing for the interstate highway system (this includes all of U.S. 40 in California). But even with that additional money available, the new bridge probably would have to be a toll structure.

The bridge work connects with other freeway contracts financed out of regular highway funds, which will, when completed in 1958, provide a full freeway route from the San Francisco-Oakland Bay Bridge through Richmond and Vallejo—a distance of 35 miles.

Needless to say, the California Highway Department undertook extensive investigations before adopting the route that includes the huge cut. The existing bridge fixed the location of the Carquinez Straits crossing. Several possible alignments connecting with the bridge were considered. All of them involved extensive earthwork—although none as much as the adopted route. But all the alternate routes were more circuitous, and most were more expensive. The adopted route has the advantage of direct approach to the bridge complex without requiring a sharp turn.



HOW AND WHERE the big earthmoving

Highway Dirt Job

Geology of the cut area was also thoroughly investigated. The formation is primarily sandstone, some of it relatively hard. In addition, there are some clay and silt lenses. And there is minor faulting. The highway engineers, however, decided that the unprecedented cut could pierce these formations with nominal risk.

Preconstruction explorations indicated only nominal groundwater to be expected in the big cut. Nevertheless, the specifications call for installation of horizontal drains should water be encountered. These drains would involve 2-in.-dia, asphalt-dipped metal pipe placed in 3 to 4-in.-dia drilled holes. Pipe would be supplied by the highway department. This type of drainage system has been successful on California road jobs in the past for drying perched water in cut slopes.

On the entire job there are 11,200,000 cu yd of roadway excavation—bid by Ferry-Crow at 25.6¢ a cu yd. In addition to the big cut, there are two smaller cuts—one of 800,000 cu yd located midway on the job and another of 700,000 cu yd at the south end of the job.

Not all of the excavated material goes into highway fills. Some must go into disposal or waste areas. But this is—at least in part—an advantage rather than a disadvantage. Reason is that the alignment goes through an undeveloped part of a Union Oil Co. refinery. The oil company provided free right-of-way in return for filling in part of the area to make it more suitable for refinery purposes. So something like 2,500,000 cu yd of excavation is disposed of.

The big cut is located at the extreme northern end of the job. Virtually all haul from it is to the south. Reason is that between the cut and the bridge lies the small town of Crockett. And although the new freeway will cut quite a swath through town, it will be mostly on elevated viaducts. Thus, very little fill material can be used north of the cut.

Location of the cut relative to the rest of the job together with location of the oil refinery excess fill disposal area results in extensive overhaul. Total on the job is estimated at



job will be done at one end of project where the biggest cut is located requires that virtually all fill must be hauled one way.

GRAVITY dumps the load...in

ONE second



Koehring Dumptor® *has no body hoist*

Operator drives up, trips the body-release lever — and *gravity* tilts the 6-yard body 70 degrees. One second later the load is out, and Dumptor is on its way back for the next load. It's as simple and fast as that!

There's no 15 to 25-second wait for slow-acting body hoists — no expensive hoist replacement parts, maintenance or down-time. And, you get the same one-second dumping *every time,* under heaviest loads, in all temperature extremes, because Koehring *gravity-dump* never balks — never wears out.

One-second dumping earns a substantial increase in yardage output, too. For example — take a typical 1,000-foot haul where you would normally make 16 trips an hour. By saving an average of 20 seconds dump-time on each trip, Dumptor gains 320 seconds, or 5.3 minutes more productive haul-time per hour. You get 17½ trips, instead of 16. This, alone, adds 9% to hourly production.

This saving is typical of Koehring Dumptor's basic principle — to reduce all non-productive time to a minimum — to increase work-time for more yards per day. See Koehring distributor for complete information.

KOEHRING COMPANY

MILWAUKEE
16
WISCONSIN

K640

Subsidiaries:
JOHNSON
PARSONS
KWIK-MIX

Saves 20 seconds every time it dumps — Heaviest loads are dumped instantly. Tilting Dumptor body rolls on heavy-duty rockers. Snub chains attached to big shock absorbers check the body at approximately 70-degree tilt.

Shuttles back and forth without turning — Dumptor operates with equal ease in either direction. Constant-mesh transmission gives the same 3 travel speeds forward and reverse. Every turn eliminated cuts 15 seconds off cycle time.

64 square-foot loading target — Big, square body opening permits loading over either end or sides. Top edge and bottom are box-beam constructed. Sides, ends, heavily rib-reinforced. ½"-thick kick-out pan bolts to floor for rock work.

TANDEM SCRAPERS ARE INNOVATION on earthmoving work. Attached to standard 18-cu-yd rubber-tired unit is a 22-cu-yd scraper. Because haul is all downgrade, one tractor can haul the 40 cu yd, but a pusher is useful in loading.

RIPPER ON POWERFUL TRACTOR breaks up sandstone formation for removal by means of scrapers. Contractor plans

455,000,000 station yards (bid at 2 mills).

The project was designed for a minimum of waste material without exceeding a 3½% maximum grade. And for most of the 3-mi stretch the grade is only ½%. Thus the 9,000-ft haul from the big cut to the Union Oil Co. disposal area will always be down-grade and will always be ½% or more.

The huge quantities together with the long haul led directly to the tandem scraper innovation. Actually it is not a new idea. L. A. "Babe" Crow, sponsoring partner for the Ferry-Crow joint venture, had used such a scheme on a job almost 20 years ago. But that was with smaller scrapers than those of today. Until recently, tractor units powerful enough to haul two of today's big scrapers were not available. And even with more powerful tractors, pay haul must necessarily be downhill to handle two scrapers with a total of 40 cu yd of material. And long hauls by high-speed rubber-tired tractor units must be available to make the tandem scraper units pay out.

The tandem scrapers are formed by adding to a standard 18-cu-yd tractor-scraper unit a second scraper with 22-cu-yd capacity. To convert to tandem scraper operation, a second power takeoff was mounted on the front axle of the tractor. Thus the existing power takeoff on the rear axle operates the forward scraper, and the new power takeoff on the front axle operates the rear scraper. Cables from the front of the tractor are run over A-frames on the front and rear of the forward scraper to lead to the rear scraper.

Work this year on the project will be restricted to hauling from the big cut into a 4,350,000-cu-yd fill just adjacent to it. Meanwhile, the smaller 800,000-cu-yd cut in the middle of the

HARD ROCK IN SMALLER CUT is in part a shovel and truck operation. Next year tandem scrapers will haul from big cut through this cut to disposal area—a 9,000-ft haul.

FILL IS COMPACTED with aid of tank truck and 50-ton rubber-tired roller. This



to remove all of the material from the big cut through the use of rippers and scrapers.

EARLY EXCAVATION ON BIG CUT was handled by single scraper units. Double units were not brought into use until maximum grade was less than 14% to ease tractor's job or return haul.

job will be brought down to grade. Then, by next construction season, material will be hauled from the big cut to the Union Oil Co. disposal area.

The contractor is now using four of the tandem assemblies. Next year, according to present plans, at least eight will be on the job. And, if they are as successful as is presently indicated, even more units might be made up and used.

Length of haul from the big cut this season is only about 4,000 ft. This is being done partly by tandem scraper units and partly by singles. It's about borderline from an economic standpoint for the tandem units—except of course for the benefit gained in operating experience that will be repaid next year. The double units could not even be brought into use until the return grade for empty run was cut down to something like 14%. With a 4,000-ft haul and a 14% return grade, the tandem scrapers are operating on a 13-min cycle. That includes 1½ min for loading, the rest of the time is used for hauling, dumping and returning. On the haul portion of the cycle the units reach speeds of nearly 45 mph.

In filling the double scrapers, a pusher tractor is needed as in ordinary scraper work. The rear unit is loaded first to provide additional weight for loading the forward scraper unit. The contractor has found that in loading there is some danger of jackknifing the double units. This can to some extent be prevented by having the pan on the forward scraper unit lowered just as the rear unit is filled. The slight trough thus provided guides the wheels of the rear unit to help overcome the tendency of the units to jackknife.

All excavation and drainage work on the project is adequate for eight freeway lanes. But only six lanes will

combination of equipment develops 90% relative compaction.

MAJOR FILL is pierced by 96-in.-dia corrugated culvert. Flag marks settlement platform that, together with piezometer installations, will check 150-ft-high fill's progress.

ALLIED JET SEAL

the one joint seal that . .

RESISTS JET FUEL, HEAT AND BLAST

Allied JET SEAL will not be blown from the joints by the blast and heat of jet engines even after prolonged exposure. Nor is Allied JET SEAL affected by jet fuel, oil and solvents.

GIVES LONGER LASTING TROUBLE FREE ROAD SEALING

The extreme ruggedness of Allied JET SEAL combined with its superior qualities of adhesion, cohesion, resilience and ductility at low temperatures makes it the ultimate for highway sealing. Though the initial cost of Allied JET SEAL is slightly higher it is far more economical over the long run since its expectant life is more than 250% greater than presently used materials.

HAS NO VERTICAL OR OVERHEAD FLOW ON BRIDGES

Allied JET SEAL has no cold flow tendencies even at temperatures in excess of 300°F., thereby assuring that it will remain where placed. This advanced characteristic makes it possible to seal vertical and overhead bridge joints without loss of material due to gravity flow.

Allied Materials Corporation also manufactures regular joint sealing compounds meeting Federal Specifications SS-S-164 and SS-S-159. Write for additional information.

THE PERFECT SEAL WHEREVER CONCRETE SLABS ARE JOINED

ALLIED
MATERIALS CORP.

PRODUCERS, REFINERS AND COMPOUNDERS FOR OVER 25 YEARS

GENERAL OFFICES—
Braniff Bldg., Oklahoma City, Okla., Phone RE 9-0592
PLANTS—Stroud, Okla.; Detroit, Mich.; Los Angeles, Cal.; New Market, N.J.; Brantford, Ontario (Canada)

be paved now—probably paving won't start until late in 1957. This will include two 36-ft roadways plus paved shoulders and a 12-ft center strip.

Except for part of one cut where the slopes will be steeper, all cut slopes are 1 on 2. The slopes will be broken by 30-ft benches at 60 ft intervals.

Fill slopes are likewise 1 on 2 with similar benches. Some of the higher fills are protected with wider benches —up to 100 ft. All fills are made to 90% relative compaction. This is accomplished by liberal use of water and 50-ton rubber-tired rollers. Settlement of the high fills is being carefully watched by use of settlement platforms. And piezometer installations measure fill pore pressures.

Except for the huge cut and the tandem scraper operation, the job is more or less routine. There are only two major traffic interchanges on the job. One serves an existing road that can be closed during working hours. The other serves a county road yet to be built. There are also two undercrossings in the refinery area. There is a second county road to be handled over the highway but no interchange is needed.

Because the job is financed by bond money there is a relatively stiff $7,900 a day penalty if the job is delayed. This amount is equivalent to interest on the bonds. And the contractor is specifically warned in the specifications that overtime or two-shift operations will be necessary throughout the life of the contract. At present the Ferry-Crow organization is working two 8-hour shifts. Work is under way from 6 A.M. to 9:30 P.M.

To meet the 570-working-day time limit, roadway excavation must be substantially in excess of 25,000 cu yd a day. Excavation has to be completed early enough to permit the concrete paving work. The contractor figures on raising the daily production rate to at least 40,000 cu yd a day and perhaps to 50,000 cu yd on some days.

The Carquinez Bridge and its approaches is a project of the California Division of Highways, George T. McCoy, state highway engineer. Leonard C. Hollister is project engineer coordinating all the Carquinez contracts financed by the bond issue. Construction of the approach freeway is a project of District IV, B. W. Booker, district engineer, V. O. Smith represents the District's construction department on the approach freeway and Charles P. Sweet, Jr. is resident engineer.

For the Ferry-Crow joint venture, L. A. "Babe" Crow is sponsoring partner. R. C. Philbert is project superintendent.



Here's how Liberty Mutual can help you on your highway contract bid

If you are planning to bid on a highway contract, Liberty Mutual specialists will provide you with a detailed estimate of your insurance costs with no obligation on your part whatsoever.

Liberty Mutual underwriters and engineers will work with you . . . analyze the problems you will face in the proposed job . . . help to make sure your bid contains a realistic estimate of your insurance costs. These men know the road building business, for Liberty insures hundreds of highway contractors across the country. Liberty Mutual has insured contractors on almost every major superhighway built in the United States in recent years.

If you would like Liberty Mutual to help you prepare an insurance estimate for your bid on a highway contract, write Mr. Parker M. Morrell, Liberty Mutual Insurance Company, Boston 16, Massachusetts.

For twenty straight years . . . the nation's largest writer of Workmen's Compensation Insurance.

LIBERTY MUTUAL

The Company that stands by you

Liberty Mutual Insurance Company • Liberty Mutual Fire Insurance Company • Home Office: Boston

There's EXTRA Performance in EVERY ATTACHMENT

with AUSTIN-WESTERN All-Wheel Drive and All-Wheel Steer

V-Plow With All-Wheel Drive, there is plenty of power and traction for opening rounds—and especially important when thick crusts have formed on old snow.

Snow Wing Rear Steer makes it easy to maneuver around highway signs, or other obstructions; is also used to resist the side thrust of a heavy load on the wing.

Bulldozer All-Wheel Steer provides exceptional maneuverability under all conditions, and is also used to angle the blade on work like this, to shed the material sideways.

Roller Another attachment which often takes the place of a costly, single-purpose roller. It has many uses . . . on many materials, including gravel, blacktop and soil cement.

Plainsman Used for building new roads, widening old roads or raising grade elevations, this elevating grader can be attached or detached in a matter of minutes.

Scarifier Most popular of all attachments. All teeth are used for light work; while every other tooth can be removed for deep scarifying of hard material.

All-Wheel Drive for maximum mobility and 30 percent more Power-at-the-Blade—power that is made still more effective by Torque Converter drive. All-Wheel Steer for extreme maneuverability. Put them together and you have teamwork that keeps Austin-Western Power Graders working where other graders fail. Austin-Western Works, Construction Equipment Division, Baldwin-Lima-Hamilton Corporation, Aurora, Illinois.

Power Graders • Motor Sweepers • Road Rollers • Hydraulic Cranes

BALDWIN BLH LIMA-HAMILTON

AUSTIN-WESTERN WORKS

BALDWIN-LIMA-HAMILTON

Construction Equipment Division

OTHER DIVISIONS: Eddystone • Lima • Electronics & Instrumentation • Hamilton • Loewy-Hydropress • Standard Steel Works • Madsen • Pelton

New types of tests yield . . .

New Data on How Materials Behave

At the Pacific Area National Meeting of the American Society for Testing Materials, held in Los Angeles Sept. 16 to 21, researchers described test procedures and equipment under development that are providing new information on engineering materials. Here are a few of the highlights:

Advances in Soil Mechanics

Research shows how to get better foundations, how to find out what's underground, how to improve soil testing.

During construction of the first barrel of the San Diego Aqueduct, inspection revealed that it was difficult to form in the trench bottom a cradle that would provide complete bearing. And it was almost impossible to compact the backfill thoroughly in the wedge area under the pipe. As reported by W. G. Holtz, chief, Earth Laboratory Branch, Bureau of Reclamation, Denver, a research program was initiated to study methods and materials for pipe backfill. Laboratory tests led to these conclusions:

- Free-draining cohesionless sands and gravels provide the best materials for bedding purposes.
- Such materials can be jetted to provide a uniform bedding at the sides and under the pipe, but only moderate densities can be obtained.
- An excellent backfill can be secured by saturating and vibrating sands and sandy gravels.
- Vibration must be performed with a vibrator of sufficient size and of adequate length to provide strong vibrations in the area to be compacted.
- It is advantageous to place the backfill loose to the required bedding depth after pipe joints have been completed, since its weight helps consolidate it.

Designs for the second barrel required: (1) consolidated backfill in which select free-draining soils secured from required excavation or borrow were to be placed to at least 70% relative density by saturation and vibration methods, or (2) compacted backfill in which suitable silty or clayey soils were to be placed by tamping methods to at least 92% Proctor maximum density where suitable materials for consolidation were not available, on steep slopes, at paved road and railroad crossings, or for replacing overexcavation in trench bottoms.

Several contractors carried out this project. Differences in techniques they used for consolidating the bedding backfill were minor. In one case, vibrators were mounted on a jeep that traveled on top of the pipe, and were lowered and raised by a power unit. The backfill was saturated by ponding and then easily vibrated to the required 70% relative density. In other cases, the vibrators were mounted on tractors equipped with booms.

Experience on this and other projects, Holtz reported, has demonstrated that the consolidated backfill produces a bedding much superior to compacted backfill. And the cost usually is considerably less than for placing compacted backfill.

• **Compacting cohesive soil**—F. J. Converse, California Institute of Technology, Pasadena, presented test results that lead to formulation of basic rules for compaction of cohesive soils by low-frequency vibration or resonant tamping. Sand, he said, compacts under very low unit surface loads after resonant frequency is obtained. But this is not the case for cohesive material, since it is necessary to break the bond holding the particles together before it is possible for them to shift into a denser configuration. To assure sufficient compressive force for compaction of cohesive soil, he recommends:

- Operate at or near resonant frequency of the soil oscillator mass.
- Supply a dynamic force nearly equal to the dead weight of the oscillator.
- Have the moisture content equal to or slightly higher than the optimum for maximum density as determined in the laboratory.
- Provide sufficient dead weight to give a unit dead-weight bearing pressure on the order of 10 or 12 psi.

• **Underground surveying**—On another phase of soil investigation—subsurface exploration—Maurseth & Howe, consulting foundation engineers, Los Angeles, Calif., reported that they have found the electrical resistivity method for subsurface surveys a valuable tool, though the services of a competent engineering geologist are still mandatory. The electrical device works on the principle that soil and rock of different character offer varying resistances to the flow of an electrical current. The equipment can be used for economical determination of borrow-pit sources, ground water, soundness and faulting of rock formations and depth of bedrock.

• **New soil testing devices**—A machine for making soil tests more efficiently was described by John W. Maloney, manager of technical services, Dames & Moore, Los Angeles. Called a Universal Soil Testing Machine, it can be used to make many types of tests.

Key element in the machine is a fulcrummed beam that carries a power-driven moving weight. The beam is linked to a bar that loads the sample in accordance with the position of the weight. The sample can be raised or lowered with a power-driven screwjack. Automatic switches operated by the swing of the beam control the power mechanism that drives the moving weight or the jack, depending on the type of test.

The Bureau of Yards and Docks, on the other hand, has developed a testing machine for the specific purpose of making consolidated direct shear tests. L. A. Palmer, Philip P. Brown and C. M. Yeomans reported in a paper that the bureau, not happy with conventional soil tests, such as cylindrical compression tests—both triaxial and unconfined—now favors the direct box shear test for solution of stability problems encountered in waterfront areas.

The test procedure developed provides a means for making separate evaluations of shear characteristics—cohesion and angle of internal friction—of undisturbed soil samples. The frictional portion of shear strength is dependent on the presence of an effective normal pressure acting during shear. The cohesive portion is a permanent characteristic of the soil and is dependent on the pressure to which the soil has been consolidated. Slightly lower values are obtained for shear strength with this procedure than with conventional interpretation of consolidated shear tests.

The shear box used takes a cylindrical soil sample 1⅛ in. in diameter and at least ½ in. thick after consolidation and at the time of shear. The shearing load is applied through a proving ring, at a constant rate of strain, to the bottom half of the box, which rides on ball bearings.

(*Continued on page 46*)

Tests Evaluate Buildings

Construction weaknesses show up in tests of full-size buildings, enabling designs of future structures to be improved.

In response to requests by the military services for better prefabricated buildings, the Bureau of Yards and Docks set up a program for full-scale testing. Not only has the program enabled the bureau to evaluate structures, but the facilities set up at the U. S. Naval Civil Engineering Research and Evaluation Laboratory, Port Hueneme, Calif., has led to the development of an improved 20x48-ft, vertical-wall, gable-roof building, according to J. E. Dykins.

The laboratory employs assembly-line testing methods (ENR Jan. 3, 1952, p. 30). A building undergoes three phases of testing—packaging and erection, weathering and structural. It is erected on a cart and rolled on tracks from one test station to another.

In the weather tests, buildings are observed under a simulated natural rainfall of 2 in. per hour—from an overhead sprinkler system—and a 35-mph wind-driven rain—from a portable turbine spray duster with a perforated water pipe in the air-discharge throat. In the structural tests, loads are produced with hydraulic cylinders acting against an enclosing jig constructed from Navy pontoons.

A main feature of the building developed by the laboratory, Mr. Dykin said, is that framing members are fabricated from 18-ga box-shaped columns and roof beams.

• **Tests indicate best design**—The Corps of Engineers also has been carrying out full-size tests, which has led to development of a prefabricated building. The tests are being performed at the Engineer Research and Development Laboratories, Fort Belvoir, Va.

According to Raymond F. Bartelmes, of the Buildings Branch, the laboratory prefers sand-bag loading, because this loading can be made nearly uniform, can be easily checked and can be applied at low cost. Wind loads are simulated with static loading.

Since 1953, the laboratory has been developing a prefabricated building system composed of a number of interrelated buildings with a maximum number of interchangeable parts. Contracts were let for designs based on light-gage metal box sections, nestable Z sections and open-web steel joists for framing. Bartelmes said the box-section roof beams failed to pass the structural tests. The Z-section system passed, but bolt holes in web connections had to be reinforced. This design was eliminated because of its rather complex design and difficulty of erection.

The open-web joist system also passed the structural tests but had joint failures. This system was selected because it required the least design changes and was the simplest and most rugged of the three designs.

Bartelmes recommended, to save time in the future, that novel designs, particularly in light-gage metal, should first be tested structurally as a single bent or as three braced bents with bracing.

• **Wall tests**—D. B. Dorey and W. R. Schriever, Division of Building Research, National Research Council of Canada, Ottawa, reported that the DBR has started testing full-size houses. Initially, experiments are being made on a one-story wood-frame building to study the effect of omitting sheathing from the exterior walls.

R. F. Luxford and E. C. O. Erickson, of the Forest Products Laboratory, Madison, Wis., told of experiments to evaluate the rigidity and strength of houses built of plywood "stressed-cover" panels. These panels consist of an inner structural framework with a facing glued to each side to form, in effect, a box girder. In the tests, racking loads are applied to the walls of full-size houses by turning a nut on a rod connecting diagonally opposite corners of an outside wall.

Radiation Effects

Tests of irradiated structural materials yield information of value in the construction of facilities for the rapidly growing atomic-energy industry.

In structural materials exposed to neutron bombardment, collisions occur between neutrons and the materials' atoms, sometimes displacing them, and the displaced atoms may, in turn, displace additional atoms. As a result, the properties of the irradiated materials may change. These changes may persist even after the materials are removed from the source of radiation.

Louis S. Castleman, Sylvania Electric Products Co., Inc., Bayside, N. Y., summarized the results of a survey of unclassified literature that was made to determine the effects of neutron bombardment on the mechanical properties of structural materials. He found data on modulus of elasticity meager but estimates that changes in the elastic constant will be small. He observed also that major increases occur in yield strength and lesser ones in tensile strength in annealed metals irradiated at low temperatures. Changes in these properties are considerably less if the materials are initially in the cold-worked state or if the temperature is raised. Slight increases were noted in creep strength.

Castleman reported that potentially the most serious radiation damage uncovered to date is the tendency for embrittlement to occur in steels. This conclusion was confirmed by other speakers.

D. O. Leeser, Atomic Power Development Associates, Inc., Detroit, Mich., described radiation effects on welds and notches in plain carbon and stainless steels and in nonferrous alloys. He finds that austenitic stainless steels, 18-8 types, and certain nonferrous alloys, offer the advantage of higher initial ductility and lack of entirely brittle failures. Since transition temperatures are not defined for these materials, there is not as much concern for exposed components, such as reactor vessels, made of them as there is for those made of carbon steel.

O. Sisman and C. D. Bopp, Solid State Division, Oak Ridge National Laboratory, Oak Ridge, Tenn., observed two general classes of reactions in irradiated plastics. The reactions are called cleavage, or scission, and crosslinking.

The cleavage reaction breaks down long molecules or polymers into smaller fragments. The crosslinking reaction results in the binding together of the molecules of a polymer into a network structure such as is found in a gel. The effect of crosslinking is to impede viscous flow and increase the elastic modulus, whereas that of cleavage is to reduce the yield stress for viscous flow and perhaps also the elastic modulus. Some plastics appear to be more vulnerable to one reaction than the other.

The changes that occur in the mechanical properties of irradiated plastics and elastomers depend upon the rates of crosslinking and cleavage. Since crosslinking is the more probable reaction, the researchers said, we may assume that it always takes place, and that we will only see the effects of cleavage when the cleavage reaction goes fast enough to overshadow the crosslinking.

NYU "Cultural" Studies For Engineering Students

New York University this year will put new "culture" into its engineering curricula.

After two years of study, the chairman of the philosophy department in Arts and Science, has come up with six hours of courses over four years intended to give the engineering graduate "as adequate a grasp as possible of his Western heritage and a vivid sense of the increasingly important role of his profession in perpetuating and developing this invaluable legacy."

The engineering student will devote about 22% of his time (32 class hours through a four-year period) to the humanities and social sciences.



FOUNDATION of Long Sault Dam where 700,000 yards of concrete will be poured by the contractor—Walsh, Perini, Morrison, Kiewit, Utah Companies, Massena, New York.

AGGREGATE TUNNEL CUTS COST OF VOLUME CONCRETE MIXING... ST. LAWRENCE SEAWAY PROJECT

Material handling is a major problem on projects such as the Long Sault Dam on the new St. Lawrence Seaway. Here is a job of such magnitude as to require more than 2400 cubic yards of concrete per day to keep the work rolling.

To handle the necessary aggregates, the contractor constructed, at some distance from the dam site, a tunnel within which a conveyor carries the aggregate to a batch concrete mixer. This tunnel, built right on the job with Commercial Shearing and Stamping steel liner plates, is large enough to accommodate the conveyor belt and walkway for feeder operators.

Placed at intervals in the tunnel roof are openings through which the aggregate flows by gravity from the stockpile directly overhead and which completely covers the tunnel. Feeders installed at intervals in the tunnel roof control the gravity flow of the aggregate from above.

Feeder operators working inside the tunnel control the material flow and selection of sizes to obtain the proper aggregate mixture reaching the conveyor. The belt carries the aggregate to the batch mixer for the addition of cement, water and mixing into concrete.

Commercial Shearing and Stamping liner plate was selected for this job because of its ability to withstand the most severe overhead loads, and to provide maximum protection from collapse and cave-in. In addition, the ease of constructing and disassembling Commercial liner plate tunnels make it possible to move or salvage the entire tunnel. This method of large scale aggregate handling, as done at the Long Sault Dam project, is being profitably used by contractors on other major projects.

Commercial Shearing and Stamping steel liner plate is available in a wide size and gauge range. For complete details on how Commercial can help solve your surface or sub-surface tunnel problems write to Dept. E-40, The Commercial Shearing and Stamping Company, Youngstown, Ohio.

COMMERCIAL *shearing and stamping*

YOUNGSTOWN, OHIO
CHICAGO, ILLINOIS
SALT LAKE CITY, UTAH

CONSTRUCTION of aggregate tunnel is quick and simple. Workmen install Commercial's liner plates on this concrete foundation in trench.

TUNNEL is completed. Unskilled workmen have used only 7 inside bolts to hold each plate. Note aggregate feeder openings.

AGGREGATE, stockpiled on top of tunnel, flows by gravity onto belt conveyor inside tunnel as operators open feeder gates.



CONVEYOR emerges from tunnel (foreground) and feeds aggregate into batch mixer for final processing into concrete. Trucks then haul concrete to dam site without time loss.

When bridge designs can be simplified...

Have better appearance... require less maintenance...

Yet cost less to build...

WHY don't you design all bridges and buildings for welding

IN ARKANSAS

Plate girder bridge over the Spring River, Highway 62, at Hardy, Arkansas; 1078'-2" length with a 26 foot roadway.

IN TEXAS

Three level separation of State Highway 225 and 136 in Harris County, Texas. Completed in 1953. 145 tons of steel. Both structures are on curves and both are skewed.

Cost reductions of 15% to 20% realized in welded bridge design

...with substantial savings in steel

THE accelerated trend to the use of welded steel design for highway bridges is evident from surveys of highway departments across the nation.

Savings in steel as well as cost of fabrication and erection are proving to average 15% to 20% over riveted designs.

Examples shown are typical of welded bridges reported in Texas, California, Kansas, Connecticut, Ohio, Florida, New York, Iowa, Arkansas, South Dakota and numerous other states.



"Studies in Structural Arc Welding" helpful to bridge designers are available by writing . .

THE LINCOLN ELECTRIC COMPANY

Dept. 2319 • Cleveland 17, Ohio

The World's Largest Manufacturer of Arc Welding Equipment



Pit excavation is done in wet fine sand, but without pumping, as . . .

Chemicals Dry Up Pump Pit Job

C. Martin Riedel
Chemical Soil Solidification Co.
Chicago, Ill.

Pit excavation in wet fine sand is being accomplished with a minimum of difficulty—after chemical soil solidification—as Chicago's Department of Water & Sewers modernizes its old pumping stations. As part of an $80-million program to improve water supply and pressures, one after another of the 50-mgd electrically driven centrifugal pumps at the South District's 68th Street Station near Lake Michigan, has to be replaced. At every pump, complete excavation of the old foundations, sinking of new shafts as tunnel connections and construction of new pump footings have been complex problems—further complicated by the soil conditions.

Fine sand, largely water-bearing, extends from ground level at El. 8 to El. 12. A stiff plastic clay extends from El. 12 to rock at −35.7. Pit excavation has had to go to El. 27, and it has been a most trying operation.

The City Construction Division chose to use chemical soil solidification, a method employed successfully years ago in the Chicago subway (Dearborn St. section) against a head of about 50 ft.

• **Tough drilling**—The solidification job at 68th Street Pumping Station was satisfactorily carried out within thirty working days, including drilling and injecting 92 injection holes, suitably spaced about 24 in. on centers. A majority of these holes had to be drilled through the old, uncharted brick masonry foundation and through an underlaying 3-ft-thick concrete mat of the original old steam-pump placed in 1890. To make the drilling particularly hard, this old concrete was reinforced by long 12x12-in. hardwood timber beams, latticed into the concrete. Without such obstructions, to be penetrated by the chemical injection pipes, the injection work would have been accomplished at a fraction of the actual working time.

In the process employed—based on the invention in 1925 of Hugo Joosten, Haarlem, Holland—two carefully balanced chemicals are consecutively pressure-injected into the loose soil to be treated permanently (no matter whether dry or wet): First the so-called Chem. I, a special "joostenized" silicate of soda solution, followed immediately by a strong calcium chloride solution. As both chemicals meet in the ground, a rapidly-forming silicic gel of high surface tension binds the loose sand particles together into an insoluble, sandstone-like mass of a hardness varying between 150 psi (about 11 tons per sq ft) and 900 psi (about 65 tons per sq ft), depending on the character of the loose material.

Properly solidified soil is watertight and withstands the attack of acids found in groundwater or of saltwater along the ocean shore. Hardness of the artificial sandstone increases with time. The bond to steel or iron is almost the same as that of concrete to steel. To obtain complete watertightness around the deep pit at this job, a 24-in. c-c spacing of the injection was selected, which also increased the structural strength of the treated area against the horizontal thrust of the hydraulic head, after excavation.

• **Rugged equipment**—The double-extra-

DRAFTING TRENDS

"Control" is the main factor in the trend to better prints. Nothing is left to chance in Post's exclusive controlled coating process.

Blueprints and diazo prints are getting better every year

In the 1890's, uniform, sharp reproductions were hard to get . . . and for good reason! Manufacturers of sensitized papers took ordinary paper stock and the best paint brush they could buy, then *painted on* emulsions! Color of developed blueprints often varied greatly from one end of the sheet to the other.

Through the years, better blueprint and diazo papers resulted from technological advances in three fields. In the *paper industry*, mills perfected higher quality stock to accept improved emulsions. Improvements in emulsion resulted, in turn, from production of purer *chemicals*. Then, to transform superior emulsion and stock into better sensitized paper, Post designed and built their own *controlled coating* machines. Each machine rigidly controls every phase of blueprint and diazo paper production for absolute uniformity from roll to roll.

"Control" opens new era

Back in the 1890's, paper stock was not uniform . . . coating patterns varied with the skill of the brusher . . . color was pure guesswork. During the past 60 years, production of blueprint and diazo paper left the age of chance and entered an era of scientific control.

Today, sensitized emulsions and coating techniques are rigidly controlled to assure sharp line images, intense color and clear background. Base paper is carefully selected and thoroughly tested for durability, ease of trimming, and ability to take repeated creasing. Even temperature and humidity are held to close tolerances to prevent variations in print quality.

What was considered good paper and reproduction quality just a few years ago now fails to meet minimum standards. At Post laboratories new developments in paper composition, chemical production and reproduction techniques are being translated daily into still better prints.

New brochure on better prints now available

Now is the time to investigate rapid advancements in print quality. If your firm has reproduction equipment to make its own prints, write today for Post's brochure on how to get better, sharper prints through *controlled coating*.

Write to the Reader Service Division, Frederick Post Company, 3668 N. Avondale, Chicago 18, Illinois.

POST

SENSITIZED PAPERS & CLOTHS • TRACING & DRAWING MEDIUMS • DRAWING INSTRUMENTS & SLIDE RULES
ENGINEERING EQUIPMENT & DRAFTING SUPPLIES • FIELD EQUIPMENT & DRAFTING FURNITURE

strong, injection pipes normally used in such work are less than 2 in. in diameter, fitted with points varying in shape and length for the different soils encountered in foundation work. Our own developments are the special driveheads and valve-heads on top of the pipes, to allow injection of the chemicals while the pipes are either being driven or withdrawn by hydraulic double-jacks capable of pulling even 100-ft-long pipes embedded in freshly solidified soil. Pumps used are of the double-acting piston type, of size and pressure to fit the job. Average pressure developed is between 80 and 150 psi.

• **Work progress**—At this job the preparation of the injection holes through the unpredictable area above the solidification area required more care and time than on many difficult jobs carried out before. However, the excavation work for the deep pit could start immediately after the last pipes were withdrawn from the solidified and watertight contract area around the proposed pit and its bottom. The excavation was carried down with free-standing, vertical sidewalls.

Afterward, lightweight sheetpiling was driven by hand-operated air hammers. This was done as an added safety precaution due to the steady vibration from existing pumps operating in the area.

No water trouble or running sand occurred while excavating and removing old concrete, masonry and the heavy hardwood timber lattice down to the clay and the final new elevation-bottom of the new foundation. Only a small, immaterial trickle appeared through old brickwork; origin of flow could not be traced. The little runoff could be handled easily by pumping in the morning before starting work.

• **Part of a big reconstruction program**—The extensive program for service improvement of Chicago's water supply is a cooperative effort of the department of Public Works, George L. DeMent, commissioner, and the Department of Water & Sewers, James W. Jardine, commissioner. Ernst Stromback, engineer of waterworks construction, with an excellent background of experience in tough tunneling and other construction problems, is in direct charge of the tunnel extensions and pumping station reconstruction work throughout the city. Phil H. Jordan is his resident engineer, on this pumping station work.

The design layout for the solidification work was made by the writer and his partner in the Chemical Soil Solidification Company, Lawrence Scully, who directed the field work with the company's superintendent, Leo G. Oler.

See Rust-Oleum *penetrate rust* to bare metal through the "Eyes" of Radioactivity!



Curved line illustrates Rust-Oleum penetration through rust at each mil level as recorded by Geiger Counter.

Rust-Oleum dries to a firm, decorative coating that resists salt water, sun, fumes, heat, humidity, and weathering.

Geiger Counter traces Rust-Oleum penetration to bare metal! In nearly three years of radioactive research, Rust-Oleum's *specially-processed* fish oil vehicle was radio-activated and formulated into Rust-Oleum 769 Damp-Proof Red Primer — then applied to rusted test panels. Rust-Oleum's specially-processed fish oil vehicle was then traced through the rust to bare metal by Geiger Counter.

This penetration means rust-stopping power, because the fish oil vehicle works its way into the tiny pits in the metal where it drives out air and moisture that cause rust. Important savings are yours, because Rust-Oleum can be applied directly over sound rusted surfaces — usually eliminating costly surface preparations. Attach coupon to your business letterhead for your copy of the thirty-page report entitled, "The Development of a Method To Determine The Degree of Penetration of a Rust-Oleum Fish-Oil-Based Coating Into Rust On Steel Specimens," prepared by Battelle Memorial Institute technologists. Prompt delivery of Rust-Oleum is assured from your nearby industrial distributor.

There is only one Rust-Oleum. It is distinctive as your own fingerprint.

RUST-OLEUM®



STOPS RUST!

Rust-Oleum is available in practically all colors, including aluminum and white. See our complete catalog in Sweets, or write for information.

ATTACH TO YOUR LETTERHEAD—MAIL TODAY!

Rust-Oleum Corporation
2700 Oakton Street
Evanston, Ill.

- ☐ Complete literature with color charts.
- ☐ Thirty-page report on Rust-Oleum penetration.
- ☐ Nearest source of supply.

University of Wichita field house
features unique 267-foot diameter

THE ALL-WELDED, EXPOSED STRUCTURAL STEEL framework actually enhances the attractive interior of the building. The soffits of all trusses are painted a brilliant red which contrasts with the gray lead of the rest of the steel, emphasizing the diamond pattern.



UNIVERSITY OF WICHITA FIELD HOUSE. Architects: Lorentz, Schmidt, McVay, and Peddle, Wichita, Kansas. **Steel Fabricator:** Watkins Inc., Wichita. **General Contractor:** Dondlinger and Sons Construction Company, Wichita. **Designer and Engineer of Lamella Roof Structure:** Roof Structure Inc., Webster Grove, Missouri.

THE ROOF STRUCTURE is supported by 36 10WF39 columns. A trussed ring girder, 39 inches deep, rests on top of the columns and runs the entire perimeter of the building. Into this ring girder are framed 12 radial trusses which span to the compression ring at the apex of the roof. Also springing from the ring girder at intermediate points are curved roof trusses which intersect the radial trusses, resulting in the characteristic diamond-shaped lamella pattern.

lamella dome of Structural Steel

432 tons of steel erected in only 14 days

The unique lamella dome of Structural Steel which crowns the University of Wichita's new field house is the *first* such dome ever to be constructed. It was designed, developed and put to use for two practical reasons—economy and speed of erection.

Spanning 65,000 square feet, the 432 tons of Structural Steel were erected by two crews in the spectacular time of just 14 days! Starting on opposite sides of the building, the two crews worked around in one direction until closure was effected. The only falsework required was a central tower supporting the compression ring, or "lantern," at the apex of the dome. All connections were bolted during erection, then field-welded.

Built at a total cost of $1,405,700, the ultra-efficient structure includes such features as a complete heating and ventilating system (with radiant heating in the locker rooms), and color-corrected vapor lighting for the arena. And, with peripheral seating, not one of the 10,235 seats is more than 86 feet from the playing surface.

Where economy, speed of erection, and dramatic design are the keywords of construction, that's where you'll find versatile Structural Steel. Moneywise, Structural Steel is the most economical of load-carrying materials. And, it's the strongest. It will withstand more abuse than other structural materials, effectively resisting tension, torsion, compression and shear. Once enclosed in buildings, it lasts indefinitely, requiring no maintenance.

USS STRUCTURAL STEEL

6-2289-A

UNITED STATES STEEL

Structural Steel may be riveted, bolted or welded, and may be erected in any weather. Since steel members are fabricated indoors, weather can have no effect on the quality of workmanship. Want more information? Return the attached coupon.

UNITED STATES STEEL CORPORATION, PITTSBURGH
COLUMBIA-GENEVA STEEL DIVISION, SAN FRANCISCO
TENNESSEE COAL & IRON DIVISION, FAIRFIELD, ALA.
UNITED STATES STEEL SUPPLY DIVISION, WAREHOUSE DISTRIBUTORS
UNITED STATES STEEL EXPORT COMPANY, NEW YORK

USS

SEND FOR THIS INFORMATIVE BOOK NOW!



United States Steel Corporation
525 William Penn Place, Room 5476
Pittsburgh 30, Pennsylvania

Please send me a free copy of HOT ROLLED CARBON STEEL SHAPES AND PLATES.

Name .....

Company .....

Address .....

City ..... **State**.....



H. Amengual, engineer, Jamaica Rock Crushers, Inc., Cuba

"UNOBA...finest grease obtainable"

"Union Oil products protect our crusher against dust and climatic conditions which can be unbelievably bad here in Cuba.

"Sometimes our plant is deluged by tropical downpours...other times the dust gets so thick it looks like we'd had a snow storm. However, since we went into production over a year ago we've lubricated all bearings with UNOBA, and even during this rough 'shakedown' period we haven't lost a single one in the Rogers Iron Works crushers, conveyor rolls, shaker screens or anything else. In my opinion UNOBA is the finest grease obtainable for tropical operations like ours."

In spite of drenching rains and high temperatures UNOBA *stays in bearings to keep dust out*...it's truly a *multipurpose* grease. Immediately available from your nearby Union Oil representative.

UNION OIL COMPANY 76
OF CALIFORNIA

Los Angeles: *Union Oil Bldg.* • ***New York:*** *45 Rockefeller Plaza* • ***Chicago:*** *1612 Bankers Bldg.* • ***Philadelphia:*** *Eastwick Ave. & Edgewood St.*
Dallas: *313 Fidelity Union Life Bldg.* • ***Kansas City, Mo.:*** *612 47th St.* • ***New Orleans:*** *644 Nat'l Bank of Commerce Bldg.* • ***Boston:*** *214 Harvard Ave.*

UP was the only direction offering the needed space, so . . .

Grandstand Tops a 5-Story Clubhouse

CANTILEVER FRAMES of reinforced concrete overhang adjacent property 26 ft. Space-gaining encroachment, 85 ft in the air, would not have been allowed lower down.

To support the roof canopy and upper deck of Copenhagen's new $1-million grandstand, 26 reinforced-concrete frames perch atop a 5-story clubhouse, looking very much like the open mouth of a bird.

Upper arms of the frames cantilever 70 ft, carrying a 2½-in. thin-shell concrete roof over more than half the 13,000 grandstand seats. The lower arms rest on two rows of clubhouse columns and support the top bank of seats. Lower decks slope downward from fifth and third-floor levels, and additional seating is provided in bleacher quadrants at either end of the grandstand.

Sharply limited as to grandstand depth by the 118-ft distance from playing-field boundary to building line, the designers had to gain space by adding height. The depth restriction eased somewhat at the height attained, however (the top tier of seats is 85 ft above the field), and the frames were allowed to overhang the building line 26 ft, encroaching on adjacent park property.

Length of the grandstand and clubhouse is 391 ft—twenty-three 17-ft bays. Expansion joints, with twin frames, occur near the third points.

Clubhouse construction is reinforced-concrete frame, designed to resist lateral loads by frame rigidity,

since end-to-end corridors at several levels made it impracticable to use transverse shear walls. Before the final design was completed, wind tests on an eight-bay model were carried out at the Technical University at Denmark.

The V-frames were cast in place in three stages, corresponding to the sections marked off by expansion joints. Trolley-mounted formwork long enough for one section was used three times. The concrete was placed by a crane that was equipped with a ½ cu yd bucket.

Frames and roof shells were not cast monolithically. Instead, the frames were cast first, with grooves along the sides at shell level and with splicing bars left protruding. Then the shell sections were cast, reinforced with 0.275-in. bars in an 8x8-in. mesh placed at mid depth.

For cast-in-place members (all struc-

Volta River Bridge Nears Completion

The midspan meeting last month of two 500-ton steel-arch segments ended a major phase in construction of the first bridge across the Gold Coast colony's Volta River. The segments jut from 200-ton concrete abutments on either bank and during construction were tied back by steel cables anchored in rock.

Two hours after jacks began letting off on the cables, the two halves closed a 10-in. gap 200 ft above the river and the 805-ft arch (ENR Aug. 16, p. 72) became self-supporting. Dorman, Long & Co., Ltd., the contractor, then started work on the deck structure. It will be suspended from the arch by cables. With approach roadways already completed, the bridge is expected to be opened for traffic before the end of this year.

Located at Adomi, 70 mi from the river mouth, the bridge will replace an overworked ferry that sometimes delays travelers as much as 24 hours on journeys between the Gold Coast and neighboring Togoland.

Consulting engineers on the project are two British firms, Sir William Halcrow & Partners and Freeman Fox & Partners.

it's that simple!

Draftsmen want to use STANPAT in place of the old-fashioned time-consuming method of re-drawing and re-lettering specification and revision boxes, standard symbols, sub-assemblies, components, and cross sections.

STANPAT reprints your standard drawing details on acetate sheets with adhesive on front or back. Guaranteed not to dry out, come off, or wrinkle. Reproductions come crisp and clear. Save drafting time and money; use STANPAT whenever drawing details re-appear on your tracings.

Prove to yourself how STANPAT saves time, effort, money. Send us your drawing details now for quotation without obligation.

STANPAT

STANPAT CO., Whitestone 57, N. Y., U.S.A.

STANPAT CO., Whitestone 57, N.Y., U.S.A.
Phone: FLushing 9-1603 — 1611 ER-10
☐ Please quote on enclosed samples
☐ Kindly send me STANPAT literature and samples.

NAME _____

TITLE _____

COMPANY _____

ADDRESS _____

GREAT NEW IDEA in tractors and attachments

52 hp

Work Bull Model 404 with ⅛-yd. loader and hydraulic-controlled back hoe works and travels on or off the hard surface. Gasoline or diesel engines.

42 hp

Model 303 with angle dozer and back hoe. Hoe buckets available in 5 sizes — 12 to 36 in. Mounting or dismounting of any attachment takes only 5 to 15 minutes. Gas or diesel engines.

34 hp

Model 202 with grader makes an ideal utility and cleanup tool . . . frees big rigs for more profitable assignments. Features dual range 6-speed transmission . . . high speed reverse.

M-H-F

WORK BULLS

Now from one source . . . a package of 5 versatile, low-cost tractors with 20 power-matching attachments

Measure your profit problem against the bright, new versatility of M-H-F Work Bulls. Never before so much pay-off workability at such low cost!

Tough manhandling projects become a breeze with a Work Bull—34 to 52 hp—digging, dozing, lifting, loading, hauling, mowing, handling scores of jobs on all projects.

And when the job is too small for a large machine, it's just right for a Work Bull. Attachments quick-change in 5 to 15 minutes with no special gear.

Maintenance costs little, too — Work Bulls are built to "construction standards" . . . always ready for rugged duty. And when you think of maintenance, remember this. You'll be dealing with a single retail distributor for sales and service on both tractors and attachments. One source, one responsibility — a definite advantage for you.

Write today for your retail distributor's name and free, 24-page illustrated catalog.

FORK LIFT

Model 202 works on or off hard surface. With standard 10-ft mast, it handles loads to 4000 lbs. With optional triple mast extension, shown, it lifts lighter loads to 21 ft.

Work Bulls pay off as primary equipment . . . as backup machines . . . as utility or cleanup tools

M·H·F WORK BULLS

Division of Massey-Harris-Ferguson, Inc.

13-J Quality Avenue • Racine, Wisconsin

when you specify and use SERVICISED hot-poured PARA-PLASTIC®

★ Keeps joints sealed under severest conditions of Traffic and Temperature

★ Pumped directly into joint from melting kettle

Hot poured Para-Plastic is the *original* hot poured rubberized asphalt joint sealing compound. It forms a resilient, adhesive and effective plastic which maintains bond at sub-zero temperatures. Superior characteristics of adhesion and cohesion, together with its stability under extremes of temperature make hot poured Para-Plastic the most effective, joint sealing material available.

JET FUEL RESISTANT TYPE

Servicised hot poured Para-Plastic JF is a specially compounded material with all the stability, plasticity and sealing characteristics of regular Para-Plastic, and in addition is unaffected by jet fuel and solvents. It is used for sealing pavement joints on airport runways, taxi strips and aircraft parking aprons.

PARA-PLASTIC SEALING STRIPS

molded Para-Plastic

For sealing keyed construction or contraction joints in vertical walls. Maintains bond with concrete at temperatures to sub-zero. Simple installation insures a moisture-tight seal of the joint.

Keyed construction joints in vertical walls and horizontal slabs.

Molded Para-Plastic sealing at a footing.

Para-Lateral Strip

Designed for sealing against seepage in vertical construction and contraction joints in foundation walls, retaining walls, tunnels, abutments, wing walls where back filling against one side of the structure is required.

Get complete information on Servicised Para-Plastic sealing compounds. Write for the Servicised Catalog.

SERVICISED PRODUCTS CORPORATION

6051 WEST 65th STREET • CHICAGO 38, ILLINOIS

tural framing), high-early-strength concrete was used. Precast steps were used as the grandstand decks. Hauled to the site as needed, they were erected directly from trucks.

Anticipating that the cantilever ends of the frames would drop 3 to 3¼ in. elastically on removal of the falsework, the designers called for 10 in. of superelevation at the tips, this amount being intended also to compensate for creep deformation. The observed elastic deflections were 6 to 7 in.—twice as much as expected—and they also differed from section to section but not enough to cause concern.

Christiani & Nielsen, Ltd., designed and built the grandstand, consulting on the design with Gunnar Krohn and Hartvig Rasmussen, architects, and A. J. Moe, civil engineer.

Rubble Dam

Indian board picks rubble, local labor for big dam

Sacrificing two years construction time for economic advantages, India's Nagarjuna Sagar Control Board has decided to build the dam of a $157.5-million multi-purpose project of mortared rubble masonry. By its decision, the board—which consists of the Indian Government's Central Water & Power Commission and members of the two beneficiary states, Andhra and Hyderabad—overruled the recommendation of U. S. dambuilder Harvey Slocum (ENR, Feb. 9, p. 26), superintendent of the Bhakra-Nangal project, who favored an all-concrete structure.

In backing construction of a concrete dam, Slocum proposed complete mechanization, with the import of 1,200 skilled workers from the U. S. and promised completion within eight years. While the construction of a rubble masonry structure, using methods not so modern, would take longer, the board saw in it a chance to reduce costs by $10 million, put less of a pinch on already-short cement supplies and more important, provide steady employment over a ten-year period for 37,000 local masons.

In the construction scheme now planned, cement mortar with a 1:4 ratio will serve as the binding agent where principal compressive stress does not exceed 15 tons per sq ft. On the dam's upstream face, a richer mixture—about 1:3 to insure water-tightness—will be applied even though the stress be less than 15 tons per sq ft. Where stress is between 15 and 20 tons per sq ft, rubble masonry with a 1:3 mortar will be employed; stresses over 20 tons will

3 more contractors get profitable performance from

International®-Powered motor graders

Arizona owner uses Model 118 Galion Motor Grader to construct irrigation ditches. Grader is dependably powered for low-cost operation, long life with International UD-525 diesel engine.

Paving contractor in Pennsylvania backfills bridge abutment with Austin-Western 99-H four-wheel drive grader driven by an International UD-14A Diesel.



Ohio contractor cuts ditches on a new highway with Model T-600 Galion Grade-O-Matic Grader equipped with International 140D diesel engine.

Here are three more contractors who have proven the long life, dependability, and profit-making performance of International-powered motor graders. Altogether nearly 50,000 International engines have powered motor graders, alone. It's proof that International power units give contractors the profitable kind of power they need and want.

Some of the many reasons for this in IH diesels are: exclusive injection and combustion systems for clear exhaust, full measure of power...over 15 to 1 compression ratio with full working expansion of hot gases behind the pistons, better fuel economy...heavy, counter-balanced crankshaft or vibration-dampeners for smooth operation (new gear-driven balancers on UD-350 and UD-14A)...and exclusive IH in-built gasoline conversion starting system which turns the engine 3 times faster than ordinary systems for fast, easy diesel starts in any weather.

It follows, that if so many contractors choose International engines for new equipment...they must be good for replacement, too. See the complete line of International diesel and carbureted engines at your International Power Unit Distributor or Dealer, soon.

CHOOSE FROM 17 HEAVY-DUTY INTERNATIONAL DIESEL AND CARBURETED ENGINES—FROM 17 TO 214 HP.

See you at the **ROAD SHOW CHICAGO** Jan. 28-Feb. 2, 1957

INTERNATIONAL® CONSTRUCTION EQUIPMENT

International Harvester Company
180 North Michigan Avenue, Chicago 1, Illinois

A COMPLETE POWER PACKAGE INCLUDING: Crawler, Wheel, and Pipe-Boom Tractors... Self-Propelled Scrapers and Bottom-Dumps... Tractors and Rubber-Tired Loaders... Off-Highway Trucks... Diesel and Carbureted Engines... Motor Trucks.

require the use of monolithic concrete construction to insure adequate safety factor.

The design staff of the Central Water & Power Commission has yet to establish the thickness of the high abrasion concrete to be placed on the face of the dam's spillway. Mechanical equipment will be used for batching, mixing and transporting the concrete, which will contain an air-entraining agent to reduce water content.

The overall Nagarjuna Sagar picture —involving 410 miles of canals and powerhouse works—will have an estimated ultimate completion cost of $244 million. When finished, about 1965, its 9.3-million-acre-ft reservoir will help irrigate 3.2 million arid acres.

Venezuela to "Freeze" Lands For Giant Irrigation Project

Venezuela plans a giant irrigation project to water 740,000 acres of land on the plains of the southwest state of Barinas, President Marcos Perez Jimenez recently announced.

Dams on the Bocono and Maparro rivers will store 2.5 million acre-ft of water and provide 50,000 kw of power. A decree "freezing" lands covered by the project will be issued in the near future as a preliminary step in the program. No cost estimate has been given.

Venezuela is now spending $75 million on a similar project, the Guarico Dam, which will irrigate 270,000 acres (ENR Sept. 27, p. 51).

Several other irrigation systems are on the boards. A $9-million dam at Agua Viva in the western state of Trujillo will water 125,000 acres. Irrigation and flood control dams on the Palmar and Apon rivers will irrigate 125,000 acres west of Lake Maracaibo.

International Roads Group Awards Foreign Scholarships

Forty-two engineers from 28 countries will study highway engineering during the school year 1956-57 under sponsorship of the International Road Federation.

Except for two who will study at Durham University England, all will attend graduate school at Purdue, Ohio State, Yale or Northwestern.

In addition to representatives from Europe, Canada, Mexico and South America, the group comprises highway officials from such places as Korea, Indonesia, Japan, Australia, Philippines, Egypt, Iraq and South Africa.

The Federation's fellowship program, started in 1949, now has trained engineers from 44 countries.

IN SOUTH AFRICA

AROUND THE CLOCK

A TANK CAR AN HOUR OF H_2SO_4



This FluoSolids System at West Rand Consolidated Gold Mines, Ltd. on South Africa's fabulous Witwatersrand was started up early in 1952. The first of several to go into operation on the Rand, it was also the first in the world to combine FluoSolids roasting of pyrite with a contact acid plant.

Over 1650 tons of H_2SO_4 — enough to fill twenty-four tank cars — are being produced every day for uranium leaching at seven South African mills.

An important part of each of these installations is a Dorrco FluoSolids System. Cumulatively the Systems include nineteen Reactors, of which sixteen were on original order and three on repeat orders, plus additional Dorr-Oliver and auxiliary equipment to produce a high strength SO_2 gas for acid manufacture by conventional contact acid plants.

Total feed to the Systems is 1450 tons per day of pyritic gold mill tailings — averaging 35 to 45% total sulfur, gas production is 75,000 to 82,000 SCFM. Gas strength averages 12 to 13% SO_2 . . . sulfur recovery approximately 90%.

The efficiency and economics of the Dorrco FluoSolids System is in evidence in these facts. Additional representative proof that the FluoSolids process can produce an SO_2 gas at lower investment and operating costs than other roasters.

If there's a step in your flowsheet where intimate contact between solids and gases is essential, fluidization should be investigated. Just drop a line to Dorr-Oliver Incorporated, Stamford, Connecticut.

FluoSolids is a Trade Mark of Dorr-Oliver Incorporated, Reg. U. S. Pat. Off.

DORR-OLIVER
INCORPORATED
WORLD-WIDE RESEARCH • ENGINEERING • EQUIPMENT
STAMFORD • CONNECTICUT • U.S.A.

SO FAST... YOU'D THINK IT WAS ON WHEELS...

the all new Rear-engine 1¾ yd. International® Payloader®



NEW PRY-OUT FORCE
International-built 77 net hp diesel engine, short-coupled power train, positive hydraulic action and 40° tip-back bucket on ground break-out pads combine to give tremendous pry-out force.

	1st	2nd	3rd
Forward	0-1.6	0-4.5	0-10.1
Reverse	0-2.1	0-5.7	0-13.1

NEW HIGH SPEEDS
The Payloader's top speed of 10 mph forward is nearly three times faster than most other competitive units. Top reverse speed of 13 mph is four times faster.



NEW VISIBILITY
Operator is always "on top of his work" because of rear-engine design. He works faster with less effort. To shift or steer, he pulls a hydraulic lever. There is no master clutch or steering pedals.



NEW SERVICIBILITY
Only tractor-shovel with tilting body, the Payloader permits mechanic to get at all four sides of engine easily and quickly. Tilting body for servicing takes only a few minutes.

Here's the new tractor-shovel that surpasses all competitive models for speed...gives you fastest loading cycles ...yet offers you crawler traction and stability for greater production and more profitable work in any terrain...in any weather. It's the all new, rear-engine, 1¾-yard International Model 12 Payloader...with new, high speeds, unmatched in crawler history...with new pry-out force necessary in rock and other tough materials...with new visibility, a result of rear-engine design...and new serviceability obtained by tilting the body to reveal engine and other components. See all these and many other International Payloader features at your International Construction Equipment Distributor, soon. Then try it! It's so fast...you'll think it's on wheels.

INTERNATIONAL® CONSTRUCTION EQUIPMENT

International Harvester Company
180 North Michigan Avenue, Chicago 1, Illinois

A COMPLETE POWER PACKAGE INCLUDING: Crawler, Wheel, and Pipe-Boom Tractors . . . Self-Propelled Scrapers and Bottom-Dumps . . . Crawler and Rubber-Tired Loaders . . . Off-Highway Trucks . . . Diesel and Carbureted Engines . . . Motor Trucks.

"Years of lowest downtime"

back preference for schedule-beating International® Equipment . .



Foreman Milton D. Peterson and Supt. H. L. Radandt beside one of Radandt's new Payscrapers.

It's a $394,000 relocation and regrading job of Wisconsin 27, between Ojibwa and Ladysmith—involving clearing, grading, culverts, and sand gravel fill up to base course. Approximately ½ million cu. yds. of excavation and borrow to do.

Cuts as deep as 21 feet are required—and one 32-foot fill is necessary, because of a 22-foot deep marsh excavation, to base new road on firm footing.

A 12-unit International prime mover fleet—pushers, dozers, rubber-tired Payscrapers®, and crawler-scraper team—is what Contractor H. F. Radandt, Inc., banks on to "wind 'er up," ahead of the Wisconsin winter, with a profit!

"Have been using International crawlers since 1946," states Supt. H. L. Radandt, for the contracting firm. "Presently we have nine International crawlers and three Payscrapers in the fleet. Years of actual operation have proven International equipment had given us good service with lowest downtime. We do all our own repair work, and International design is simple to work on."

Prove how exclusive Planet Power steering with full-time live power on both tracks, plus finger-tip operating ease, give the International TD-24 exclusive production-boosting advantages! Compare capacity of new bonus-powered International equipment to anything else on tracks or wheels. Find out what International unit assembly construction means for overhaul speed and simplicity—for reduced downtime—for new upkeep economy. See your nearby International Construction Equipment Distributor for a demonstration!

"**The new design 75 Payscraper** bowl loads and unloads, fast and easy," declares Supt. Radandt. "Estimated average load: 18 pay yards." Here, loading time with TD-24 as pusher, the 75 heap-loads in 45-60 seconds, in silt-sand-gravel mixture!

—by H. F. Radandt, Inc.,

Eau Claire, Wisconsin

See you at
the ROAD SHOW—CHICAGO
Jan. 27 to Feb. 4, 1957

Dumping of the new 75 Payscraper takes only 10 seconds. Higher apron lift, and bigger apron opening assure new dumping speed and positive clean-out ability. The new Payscraper's high horsepower - to - capacity ratio permits rapid acceleration to 24 mph top speed — a big yardage-booster!

The three Payscrapers in the Radandt fleet average 2200 cu. yds. per 10 hours—on a 6300 lineal-foot round trip. "The new '75' has matched engine power to deliver the payload fast, and flotation to take roughest pit or haul-road conditions," adds Mr. Radandt.

This torque-converter TD-24 is one of three International crawlers towing scrapers on the job—hauling up to 1000 lineal feet one way. With 200 net engine hp and full-time traction power on both tracks with Planet Power steering, this outfit hauls fill dirt into one of the 22-ft. deep cuts.

Another TD-24—a veteran in the Radandt fleet—spreads and compacts fill dirt on one of the marsh-excavated spots. TD-24 Planet Power steering is particularly productive on all blade work. Full-time live power on both tracks results in faster cycles, bigger loads.

INTERNATIONAL HARVESTER

INTERNATIONAL® Construction Equipment

International Harvester Company, 180 N. Michigan Avenue, Chicago 1, Illinois

A COMPLETE POWER PACKAGE INCLUDING: Crawler, Wheel, and Pipe-Boom Tractors . . . Self-Propelled Scrapers and Bottom-Dumps . . . Crawler and Rubber-Tired Loaders . . . Off-Highway Trucks . . . Diesel and Carbureted Engines . . . Motor Trucks



Kodagraph Autopositive intermediates have dense black photographic lines on a translucent paper base.

To show alternate floor plans and elevations

Instead of retracing basic plans over and over, you reproduce them on Kodagraph Autopositive Paper.

This revolutionary paper gives you positive photographic intermediates *without a negative step.*

You, or your blueprinter, can turn them out under full roomlight with present equipment. Expose in a blueprint or direct-process machine . . . or vacuum frame; process in standard photographic solutions.

Result: Sparkling intermediates made at a fraction of the retracing cost! Just add the new design . . . and you have printmaking masters which will give you top-quality blueprints and direct-process prints.

This is another example of the way Kodagraph Reproduction Materials save time, cut costs in thousands of drafting rooms and reproduction departments.

EASTMAN KODAK COMPANY
Graphic Reproduction Division, Rochester 4, N. Y.

New booklet is jam-packed with valuable tips on saving drafting time, protecting drawings, getting better prints.

Kodagraph Reproduction Materials

MAIL COUPON FOR FREE BOOKLET

EASTMAN KODAK COMPANY
Graphic Reproduction Division, Rochester 4, N. Y.

Gentlemen: Please send free booklet describing Kodagraph Reproduction Materials. 67-10

Name_____

Company_____ Position_____

Street_____ City_____ State____

Kodak



TEST HYPERBOLIC-PARABOLOID SHELL, 40 x 40 ft, is supported on 2-ft-sq column.



FOUR REINFORCING SCHEMES were tried—¾-in. rods 16 in. c-c (1); ¾-in. rods 12 in. c-c (2); ¾-in. rods laid diagonally 12 in. c-c (3); 6x6 by no. 4 mesh (4).



FOUR SIZES OF FORM PANEL were tested—one on each quarter of the test roof. The warped shell is formed with straight panels despite the double curvature.

Pilot Project Probes Paraboloid

The hyperbolic-paraboloidal roof shape, which has been built in metal and thin-shell concrete in Europe, Latin America—and in a few instances, in the U.S.—has successfully passed tests conducted by A. A. & E. B. Jones Construction Co., Denver, Colo. The firm built a 40x40-ft section in thin-shell concrete for the purpose of testing different methods of forming and reinforcing. The Jones Co. will manufacture the selected form system for Great Southwest Corp., Dallas, Texas, for a 5,000 acre industrial district.

The test section in its entirety does not have the familiar saddle shape of a hyperbolic paraboloid. Instead, its configuration is that of portions of such a surface, rearranged so that all four edges of the roof lie in the same horizontal plane. This feature will facilitate the joining of a number of the sections in multi-bay buildings.

There are certain inherent advantages in the hyperbolic-paraboloid shell. It is highly efficient at carrying loads, thus saving on concrete and reinforcing. It is also lightweight. Some of the roofs built abroad of this type have been only 1-in. thick, although Jones Construction Co. will use a 3-in. slab. An important advantage is that the warped-shaped surface can be formed with straight forms, since a section taken parallel to its edges will yield a straight-line profile. Relatively long column spacings are also achieved.

Jones' forming system was developed in 1953 for concrete slabs. The form panels are plywood on aluminum frames. Panels are fastened together with pins, with all the fastenings at-

tached to parts of the form. The only bolts required are on the bracing members. For the test slab Jones used shores and beam clamps manufactured by Acrow, Inc., Carlstadt, N. J.

Four different sizes of form panel were used in forming the test shell—one on each quarter section. Form panels 40 in. wide and 10 ft long proved to be the most satisfactory. Other sizes tried were 20 in. by 10 ft, 20 in. by 20 ft and 40 in. by 20 ft. Panels consisted of ¾-in. plywood mounted in standard aluminum frames.

Similarly, four types of reinforcing were tested—one type in each quarter of the shell. That quarter of the roof in which ¾-in. rods on 16-in. centers were used was most satisfactory for placing concrete. Tried in other sections were ¾-in. rods on 12-in. centers, a 6-6-4 mesh, and ¾-in. rods on 12-in. centers set diagonally.

Perpendicular to the roof edge, along the line of demarcation between quarter sections, was a more heavily reinforced region, or so-called beam section. Each of these areas was reinforced with three ¾-in. bars that extended from the center column to the edge of the roof and two other ¾-in. bars extending midway between the edge and the center column.

The center-supporting concrete column is 2 ft sq, hollow in the center for drainage. Reinforcing consists of twenty 1⅛-in. bars. The column, in turn, rests on a footing 9 ft sq, 2 ft thick, with two steel mats. In multi-bay structures, a footing only half this size would be needed.

The test structure also marked the first major use of "Idealite," a new lightweight aggregate. The aggregate was produced by Great Western Aggregates, Inc., Denver, Colo., and shipped from Great Western's plant at Laramie, Wyo., to Walt Flanagan Co. of Denver. This firm mixed and placed the concrete.

The new aggregate was reported to be stronger and less water-absorbent than most lightweight aggregates. Heat insulating and sound absorption qualities are also claimed for it. The concrete mix used weighed 93 lb per cu ft.

Forms were removed 44 hours after placing, when the concrete had attained a strength of 2,080 psi. The mix contained 5.9 bags of cement per cu yd. Tested after 72 hours, the concrete showed a strength of 2,610 psi.

The shell-roof structure was built for less than $2 psf. This cost included labor but not the forms. E. B. Jones estimated that the forms would have to be used 20 to 30 times to write off the original investment. He said, "The aluminum frames last indefinitely, but the plywood has to be replaced after seven or eight uses."

According to Jones, this type of roof construction has been slow to develop in the U. S. because of high labor costs here. He said that in Mexico the forms are built, used once and discarded because a Mexican workman works about two days to earn what an American construction worker makes in one hour.

A. A. & E. B. Jones Construction Co., Denver, Colo., will manufacture the forms for the first U. S. application of the roof—the 5,000-acre industrial district between Dallas and Fort Worth. Associated Architects and Planners, Dallas, Texas have been working with the builder, Great Southwest Corp., also of Dallas, on the industrial designs for the development. Architects O'Neil Ford and Richard Colley of Associated Architects and Planners worked with the Jones brothers in developing the forming system. Mexico City architect, Felix Candela, is a consultant for Associated Architects and Planners.

The Denver test was part of a general research project by Great Southwest to develop better and more economically constructed industrial buildings.

Oil Tank Fires

Preventing lightning fires in floating-top oil tanks

A method has been developed to protect floating-roof oil tanks from lightning-caused fires. Prof. E. R. Whitehead, director of the department of electrical engineering, Illinois Institute of Technology, together with engineers of the Chicago Bridge & Iron Co., Chicago, Ill., appears to have eliminated a hazard that has plagued this type of tank since its production. There have been about forty such fires since the first floating roof was installed on an oil storage tank in the early 1920's. Yet, these tanks have become increasingly popular because of their efficiency in reducing evaporation losses.

• **How fires start**—During a storm, an electric charge is induced on the floating roof of the tank by the electric field of a thunder cloud. Discharge of the cloud by lightning—on the roof, tank shell, or ground nearby—suddenly removes this field. The charge on the roof then is rapidly released and in passing to the ground travels through the rim vapor space around the roof



Photo taken right after stripping forms proves that you get the...

FINEST SURFACE with PLYGLAZE® CONCRETE FORM PANELS

READ "finest" both ways: PlyGlaze *itself* has the finest, smoothest surface of any form material; PlyGlaze-formed *concrete* surfaces are the finest—smooth, even-textured, with no trace of grain pattern. Savings on finishing costs alone frequently offset slightly higher cost of this premium material. See Sweet's File or use coupon for more information.


TREE LIFE FOREST PRODUCTS
Another member of the famous Tree Life Family of Forest Products
Hard, glossy-smooth wear resistant fused resin-fiber surfaces.
Top-quality Exterior plywood (EXT-DFPA). Standard panel sizes.
PLYGLAZE EXT-DFPA

ST. PAUL & TACOMA LUMBER CO.
Dept. ENR, Tacoma 2, Wash.
Please send free PlyGlaze literature.

Name _____

Address _____

City _____ Zone _____ State _____

James F. Byrnes High School, Duncan, South Carolina.
Architect: Lockwood Greene, Spartanburg, S. C.; *General Contractor,* Fiske-Carter Construction Company, Spartanburg; *Roof Deck Contractor:* Bonitz Insulation Company of South Carolina, Columbia, S. C.

THE 70,000 square feet of roof area on the James F. Byrnes High School is protected from fire with economical Gold Bond "Firefighter" Roof Deck. This also includes the walkways which extend from building to building. Wherever you go, you are protected by a roof deck that is naturally fireproof. The poured gypsum concrete deck *can't* burn!

Econacoustic Formboard, which was used on this school, insulates and sound-conditions the classrooms, gym and auditorium. And there are other Gold Bond Formboards available that can be varied according to specifications: Gypsum Formboard specially treated to resist mildew; Insulation Formboard that resists fungus and termites; Asbestos-Cement Formboard for additional fire-resistance.

Gold Bond "Firefighter" Roof Decks are adaptable to the barrelled and flat roofs on the Byrnes High School as well as being a practical covering for pitched roof designs. *Up to 30,000 sq. ft. may be poured in just one day...* and full load roof capacity is possible within an hour! Low dead load permits lighter supporting structures to be specified and saves on actual construction costs.

See how Gold Bond "Firefighter" Roof Deck can add safety and economy to your building designs. Send in the coupon below for full details. National Gypsum Company, Buffalo 2, New York.

Gold Bond
BUILDING PRODUCTS

"FIREFIGHTER"
GYPSUM ROOF DECK

NATIONAL GYPSUM COMPANY

NATIONAL GYPSUM COMPANY, Dept. EN-106
Gentlemen: Send me Technical Bulletin No. 502 with complete details on "Firefighter" Roof Decks.

Name *Address*

City *County* *Zone* *State*

"INFERNO"

"Standard of Quality"

STEAM HOSE

Famous for Durability and Safety!

Contractors know that when they put "Inferno" on the pile-driving rig, the job will keep going at a steady, profitable pace, with no question of bursting and its costly consequences. Record speeds and depths of drive have been made many times with this extra-strong, extra-durable steam hose . . . easily identified by the Goodall "Cloverleaf", and a black spiral stripe on the familiar red cover.

"INFERNO" STEAM HOSE specifications include high-temperature tube; multiple-layer, braided steel wire carcass; wear-and weather-resistant "synplastic"® cover. Sizes ½" to 3", inclusive, in maximum lengths of 50 feet.

"If it's GOODALL, it MUST be Good!"

Contact Our Nearest Branch for Details and Prices

Standard of Quality—Since 1870

HOSE · BELTING · FOOTWEAR · CLOTHING AND OTHER INDUSTRIAL RUBBER PRODUCTS

GOODALL *Rubber Company*

GENERAL OFFICES, MILLS and EXPORT DIVISION, TRENTON, N. J.

Branches and Distributors Throughout the United States and in Canada



through pantograph metal supports. Fire is caused if the vapor is ignited by sparks generated at points of imperfect electrical contact.

• **Solution**—The method devised to eliminate the hazard provides a safe path for the charge to flow to ground. Stainless steel shunts on the outside of the vapor space, placed around the periphery of the roof, do this. At the same time, supports and pantograph hangers within the vapor area are insulated to prevent any lightning-induced currents from passing through.

It was specified that pantograph hangers had to be able to hold the floating roof in place even during a fire. After investigation, an insulating material was found that could both pass a surge-current test and meet this fire-exposure requirement.

A full-scale model of the pantograph hanger was built for surge-current testing. To reproduce currents equivalent to lightning, a 400,000-volt surge-current generator was used. Then, to prove that sparking would occur under lightning conditions, a non-insulated hanger was tested. Tests were continued to determine the amount and type of insulation and shunting required.

Improvement of Clay Pipe

A contract to inaugurate a research program for improvement of clay sewer pipe was recently awarded to a Cleveland research firm, Horizons Incorporated, by the National Clay Pipe Research Corp., of Willard, Ohio.

The program will be under the direction of Cameron G. Harman, head of the ceramics department. According to Harman, the research program is directed at using modern technology and methods to produce a greater strength in clay piping while reducing its size and weight.



Project: Underpinning Main U. S. Post Office, Chicago, Ill. — *Contractor:* S. A. Healy Co., Chicago, Ill.

DEEP PRETEST PILES UNDERPIN CAISSONS BLOCKING CHICAGO'S SUBWAY TUNNEL

While digging under the city's main post office, the contractor for Chicago's new subway ran into his biggest headache. Instead of caissons extending to rock, he found belled caissons blocking further progress.

At that stage Spencer, White & Prentis were awarded a contract to underpin 16 of these caissons. The drawing shows our completed Pretest piles carrying the caisson loads (some up to 2,400 tons) to hardpan. Perhaps you would like us to explain how the Pretest method, pioneered by this company, transfers loads safely and dependably, and precludes danger of future settlement.

CATALOGUE ON REQUEST

FOUNDATIONS
PILING
UNDERPINNING
SHORING
COFFERDAMS
SPECIAL SERVICES

Spencer, White & Prentis

INC.

10 EAST 40th STREET, NEW YORK 16, N. Y.

DETROIT: 2933 PARK AVE. • CHICAGO: 228 NORTH LaSALLE ST. • WASHINGTON, D. C.: TOWER BLDG.
OF CANADA: 700 BAY ST., TORONTO • 2050 ST. CATHERINE ST. WEST, MONTREAL

Immaculate Heart of Mary Church School
Youngstown, Ohio
P. Arthur D'Orazio, architect;
Charles Shutrump and Sons, Co., contractor.



TRUSCON® "O-T"® Open Truss Steel Joists, Ferrobord® Steeldeck and Projected Steel Windows Help Create This Exciting

Daylighted outdoor corridor

This interesting outdoor corridor has been designed into the new Immaculate Heart of Mary Church School in Youngstown, Ohio. Almost monastic in appearance, the second floor corridor has been roofed by extending Truscon "O-T" Steel Joists and structurals across its full width. Truscon Ferrobord Steeldeck completes the roof except for a run of clerestory windows which bring daylight directly into the Truscon Architectural Projected Windows of second floor classrooms.

Truscon "O-T" Steel Joists are light, strong, fire-resistant floor and roof supports. Lightweight and easy to handle, they lessen time and labor costs, save material in supporting framework and foundations.

Ferrobord Steeldeck is clipped or welded directly to the steel joists. It comes in long lengths to span three or more purlins. Easy to handle, easy to place, it roofs large areas quickly—flat, pitched or curved. Erection is from above, no scaffolding needed. Full length interlocking adds extra strength.

Truscon Steel Projected Windows provide superior ventilation plus minimum air infiltration. Integral baffles of Truscon's own special steel section provide casement-type full weathering contact—a Truscon exclusive feature in windows of this classification.

For more information and specifications on these quality Truscon building products, see Sweet's File or send coupon below.

REPUBLIC

REPUBLIC STEEL

World's Widest Range of Standard Steels



SCHOOL MADE FIRE-RESISTANT WITH TRUSCON METAL LATH AND PLASTER

Membrane fireproofing is a system of fire protection using metal lath and lightweight aggregates. Used in ceilings, partitions and for shrouding structurals, membrane fireproofing makes possible buildings of lighter weight, greater useful space and lower cost. Truscon Metal Lath and plaster make a safer school.

SCHOOL CONCRETE PROTECTED WITH TRUSCON WELDED WIRE FABRIC

Pennies buy you "concrete plus." Truscon Welded Wire Fabric reduces the rate of cracking. High strength steel wires keep cracks tiny and practically invisible. Concreted areas get lifelong protection. Specify concrete PLUS Truscon Welded Wire Fabric for longer-lasting, expense-free concrete slabs.



STEEL

and Steel Products

REPUBLIC STEEL CORPORATION
3114 E. 45th St., Cleveland 27, Ohio

Please send me more information on these Truscon Steel Division building products:

☐ Truscon "O-T" Steel Joists ☐ Truscon Welded Wire Fabric
☐ Truscon Steel Windows ☐ Truscon Ferrobord Steeldeck
☐ Truscon Metal Lath and Accessories

Name_____ Title_____

Firm_____

Address_____

City_____ Zone____ State_____

K-1648

EFFICIENT WORK BARGE SET-UP consisted of revolving derrick with 130′ boom and 4-way pile driver.

Prestressed wharf piles resist side loads and salt water

FOR ESSO STANDARD OIL'S new bulk oil terminal at Newport News, Va., Tidewater Construction Corp. has erected a wharf on concrete piling of interesting design. The piles, (72′ to 77′ long and 18″x18″ in cross section with 8″ dia. hollow core) were cast at the site and prestressed with sixteen ⅜″ cables pretensioned under a total load of 112 tons. This prestressing stiffens the piles against side loads created by the thrust and pull of loaded tankers and barges. It also holds closed any cracks which develop in the concrete, so as to prevent exposure of the steel reinforcing to salt water.

The high early strength concrete needed for this construction was supplied by an 8½ bag mix properly processed in truck mixers of certified design, capacity, mixing speed and water control accuracy. It tested 4000 psi after 72 hours.

21 PILES AT A TIME were cast and prestressed in 7 lines of 3 piles each. Forms were reused 12 times.

CONCRETE was placed and vibrated around fibre Sonovoid tube, centered in form to create a weight-saving, cost-saving hollow core.



You have a right to insist on this Rating Plate. It certifies compliance with the high industry standards maintained for your protection by the Truck Mixer Manufacturers Bureau.

BLAW-KNOX CONSTRUCTION EQUIPMENT DIV.
Mattoon, Ill.
CHAIN BELT COMPANY
Milwaukee, Wis.
CHALLENGE MANUFACTURING CO.
Los Angeles, Calif.
CONCRETE TRANSPORT MIXER CO.
St. Louis, Mo.
CONSTRUCTION MACHINERY CO.
Waterloo, Iowa
THE JAEGER MACHINE COMPANY
Columbus, Ohio
THE T. L. SMITH COMPANY
Milwaukee, Wis.
WILLARD CONCRETE MACHINERY CO., LTD.
Lynwood, Calif.
WORTHINGTON CORPORATION
Plainfield, N. J.



Rotary Drill Makes 7⅜-Inch Hole in Rock

A new dry type, low-cost rotary drill—the invention of a mining company that saw its profits dropping because of high drilling-and-blasting costs—has been so successful in their opinion that a separate corporation has been set up to manufacture and market the machine as a tractor-mounted rotary drill.

The drill was developed for drilling blast holes in overburden of coal seams, by the Robbins Coal Co. of Oneonta, Ala., which has set up a separate corporation—the Robbins Machine & Manufacturing Co., Inc.

Among advantages claimed for the drill is that the rotary with a 7⅜-in. bit drills a larger blast hole than possible with wagon drills, and permits blasting on a larger pattern. The drill permits a maximum drilling depth of 65 ft, which offers the advantage of being able to drill to the full depth of the cut instead of in 12- or 15-ft lifts. Experience with test models in Alabama has seen the drill used in all types of rock excepting hard granite.

Drill speed of the rotary has varied from 1 ft per min in hard blue sandstone to as high as 6 ft per min in softer foundations. The drill features a mechanical drive as opposed to pneumatic drive in most rotaries. First models were adapted for mounting on Caterpillar D6 tractors, but adapters are now provided for mounting the drill on non-Caterpillar crawler machines. Power to drive the rotary comes from the rear power takeoff of the tractor through a Fuller K8 or K11 transmission, with four speeds forward and one reverse.

Through a chain drive the transmission powers a right angle connection to a square shaft running the height of the drill unit. This shaft powers a sliding gear box which rotates the drill steel at speeds between 25 and 120 rpm.

Down pressures as high as 30 tons on the drill bit are obtained by two 8-in. hydraulic cylinders operating off a 70-gpm hydraulic two-stage pump also driven from the power takeoff of the tractor. These pistons operate a rack-and-pinion which raises and lowers the drill pipe by two chain sprockets, providing the necessary down pressure on the bit. A 600-cfm air compressor forces air into the drill pipe to blow chips and dust away from the bit, the compressor being used either as a separate unit or mounted on the tractor. The drill can handle bit sizes from 5 to 12 in.

The drill mast is hinged and can be quickly broken over, making the entire unit portable in a matter of minutes. Supporting braces on the latest models are swiveled so they need not be removed for the breakover. A splined coupling on the square shaft eliminates capscrews which would otherwise have to be removed. Total weight of the drill unit is about 24 tons, including ballast and oil, but excluding tractor. Robbins Machine & Mfg. Co., Inc., Oneonta, Ala.

(*New Products continued on page 74*)

Air-Operated Sump Pump

A new air-operated sump pump, rated at 340 gal per min against a 10-ft head, comes in either steel or bronze. The pump operates with a maximum head of 95 ft and is designed for removing water or other liquids from tanks, sumps, ditches, manholes and traps. It requires no priming.

The pump has an 8-in. base diameter, is 23 in. high. Air inlet is ¾ in. in diameter and discharge outlet 2½-in. Low air consumption, governor-controlled motor and built-in lubrication system are featured along with lightweight construction—steel model is 56 lb, bronze 75 lb. Le Roi Div., Westinghouse Air Brake Co., Milwaukee 1, Wis.

IN MASONRY BITS — the TIP'S the THING!



That's Why Most Experienced Bit Users are Switching to

New England
CARBIDE-TIPPED
MASONRY BITS

THE WORLD'S ONLY COMPLETE LINE OF Carbide-Tipped MASONRY BITS

YOU NEED THE RIGHT Carbide-Tipped BIT FOR EACH DRILLING JOB!

Don't try to use an ordinary bit to do the tough drilling jobs that only New England Carbide-Tipped MASONRY BITS can handle. And — don't use the wrong type when only the right type will do. Equip with the complete New England line — and eliminate wasted labor — slow, costly work — bit breakage — and disappearing profits. Start using the line made of heat-treated alloy steel, with the super-sharp carbide tips and tip-to-shank flutes that assure positive dust removal.

Cyclo-twist®
ROTARY BITS
For ROTARY DRILLING of Medium Masonry — Sizes 7/64" to 1½".

Cyclo-Core®
ROTARY BITS
For ROTARY DRILLING of Hard Masonry, including Hard Concrete and Vitreous Tile — Sizes ¼" to 6".

Thunder-twist®
HAMMER BITS
For One-Man HAMMER DRILLING of all Hard Masonry and Granite — Sizes 3/16" to 1¼"

FOR THE ANSWER TO THE QUESTION — "What Masonry Bit Should I Use?" — WRITE for our "WHAT and HOW" MANUAL. It's FREE, and very helpful.

New England
Carbide Tool Co., Inc.
55 W. Commercial St.,
Medford, Mass.

Please send me FREE "WHAT and HOW" MANUAL

NAME_____

ADDRESS_____

CITY_____ ZONE___ STATE_____

Scaffolding Hangs Easily With Hook or Scissor Hanger

Versatility is offered in a scaffolding that can be suspended from structural beams, angles, junior beams and open-web joists. Called Swing-Lo Suspended Scaffolding, the new product is lightweight and can be adjusted for working height.

The scaffolding comes either with a hook for suspension from junior beams, open-web joists and angles, or with a scissors-type hanger for larger beams. Used in sets of four or more, the suspenders carry wood beams, which, in turn, carry the working platform. A forged pigtail on individual hangers permits a variety of interchangeable hangers to be used. The smallest hanger will carry a single 4 x 4-in. beam, while the largest can take two 8 x 12-in. timbers.

When equipped with the scissors-type hanger, the suspension system can actually be rolled along the flange of the beam that supports it. Scissors come in two sizes—one for 6 to 10-in. flange widths, the other for 10 to 20-in. flange widths. Swing-Lo Suspended Scaffold Co., Covert, Mich.

Melting Compound Marketed Free of Chloride and Calcium

A new chloride-free ice-and-snow melting material in prismoid form, said to be harmless to pavements, metals and vegetation has been announced by Speco. Known as Ice Rem-CF, the material is said to be 99.99% chemically active and contain neither calcium nor chloride. For this reason, the manufacturer says that the material does not produce a heat effect as part of its melting process, and that it will not corrode aluminum or other metals. Since the material also produces a combined melting and abrasive action, it has been recommended for use in street car, bus and truck sand boxes and under spinning automobile wheels.

Because its molecular structure has a greater depressing point on ice than salt, Ice Rem-CF is said to have substantially more thawing capacity at lower temperatures and in the sub-zero range, leaving no messy residue and not being hygroscopic. Consequently, it is cleaner to use and simpler to store than similar products. Speco, Inc., Cleveland, Ohio.



Leveling Plane Tested on Colorado Road Project

A new-type plane for leveling sub-base and base courses on roads has been tested with excellent results on a Colorado road-building project, according to the manufacturer.

The machine, towed by a conventional tractor, is said to incorporate new designs to afford an effective leveling length of 50 ft. A hydraulic system automatically maintains a straight line of plane and is said to enable the blade to shave off humps and fill dips effectively. The attachment is transportable, with the rear boom and gage wheel folded to reduce overall length to 35 ft for transport and storage. Gurries Mfg. Co., 1720 S. First Street, San Jose, Calif.

Plastic Material Repairs And Waterproofs Concrete

Severe spalling and cracks in concrete can be permanently and effectively repaired with Permagile, according to its manufacturers. Among other claims made for the epoxy-based plastic: It joins bricks, tile, concrete blocks and other masonry items with a bond stronger than the joined materials; it is hard, tough, elastic and waterproof; it won't shrink or expand; it is immune to the ravages of time and weather; alkalis and most acids and chemicals don't affect it; average strength is 35,000 psi in compression, 8,000 to 10,000 psi in tension. Applications include waterproofing and repair of tanks, sewers, floors, walls and basements; also tile-setting and roadway surfacing. PERMAGILE CORP. OF AMERICA, 37-23 33D ST., LONG ISLAND CITY 1, N. Y.

Tool Clinch-Fastens Panels Eliminates Spot-Welding Time

A manufacturer of aluminum and steel building panels has developed a tool for fastening the panels by clinching the metal. The new tool speeds construction by eliminating time required to spot weld panels together.

Called a "Riv-Clinch" tool, the device can be operated by one person. It comes in two models—one for use with Fenestra's type "D" long-span cellular steel panels, and a lighter model for use on type "FA" field-assembled and type "F" panels.

The "D" tool can be used on 14-ga



DROP-TIGHT SHUTOFF R-S Rubber-Seated Butterfly Valves give drop-tight closure to 125 psig through wedge-type action of the disc within a one-piece rubber seat. 65 of these valves, installed as shown for service in the San Jacinto River project near Houston, gave a substantial space reduction and direct, in-place cash savings of $124,000.





FOR HIGH-PRESSURE SERVICE SMS Babbit-Seated Butterfly Valves are built to give tight shutoff and meet the rugged demands of high-pressure service. They are available for shutoff pressures up to 200 psig, and for a wide range of velocities, including open-end free discharge.

BUTTERFLY VALVES

GET POSITIVE SHUTOFF, CUT CONSTRUCTION COSTS

For high or low-pressure water service, SMS has the Butterfly Valve to give you tight shutoff and help reduce construction costs. Using SMS or R-S Butterfly Valves in place of conventional gate valves permits a much more compact piping layout, means substantial savings in the initial building costs. For full information on the complete SMS valve line — Butterfly Valves, Ball Valves and Rotovalves —see our local representative or write S. Morgan Smith Co., York, Pa.

HYDRAULIC TURBINES · GATES & HOISTS · TRASH RAKES · PUMPS · ACCESSORIES

HYDRODYNAMICS

ROTOVALVES · FREE-DISCHARGE VALVES · BALL VALVES · CONTROLLABLE-PITCH SHIP PROPELLERS · BUTTERFLY VALVES

S. MORGAN SMITH

AFFILIATE: S. MORGAN SMITH, CANADA, LIMITED • TORONTO

Whether you have many employees . . .

or just a few . . .

Give them the protection of Hartford Group Insurance!

Once only "big" employers could have Group Insurance plans for their workers.

That time is past. Hartford now writes Group coverages for companies with *as few as 10* employees (except in Florida, where the minimum is 15).

For groups of ten to twenty-four people, Hartford offers convenient package plans. For larger groups, Hartford can "custom tailor" Group coverage to meet exact needs—or to fit a budget.

These plans can include coverages for:

- **Accidental Death and Dismemberment**
- **Weekly Disability Expenses**
- **Laboratory and X-ray Expenses**
- **Poliomyelitis Expenses**
- **Major Medical Expenses** (For groups of 25 or more)

Group Insurance by *Hartford* offers you these worthwhile special advantages:

1. **Fast, expert claim service** through a nation-wide network of nearly 200 claim offices relieves you of practically all details and responsibility on claim matters. These facilities are particularly valuable to your branch offices and traveling employees.
2. **Streamlined premium payment procedures** and simplified policy forms reduce your work and lower your Group Insurance administration expense.
3. **Low cost** for you and your workers through efficient procedures and loss engineering activities that prevent abnormal loss experience.

You should certainly look into what Hartford has to offer. *Both you and your employees stand to benefit!* Call your Hartford Accident and Indemnity Company Agent or your insurance broker for details.

Year in and year out you'll do well with the

Hartford

Hartford Fire Insurance Company
Hartford Accident and Indemnity Company
Hartford Live Stock Insurance Company
Citizens Insurance Company of New Jersey . . . *Hartford 15, Connecticut*
New York Underwriters Insurance Company . . . *New York 38, New York*
Northwestern Fire & Marine Insurance Company
Twin City Fire Insurance Company . . . *Minneapolis 2, Minnesota*

steel or lighter. Clinches are specified 3 ft c-c.

According to the manufacturer, tests at Cornell University led to developing this type of fastening until it could take shears and carry loads of a comparable welded construction system. FENESTRA, INC., 2250 E. GRAND BLVD., DETROIT 11, MICH.

Drill's Integral Pusher Leg Is Automatically Retracted

A new model rock drill equipped with automatic retraction of its integral pusher leg and with all controls concentrated for single-hand drilling operation is now available.

Up to 30% increases in drill footage per hour claimed as a result of these design advances. Machine downtime for new positions and steel changes are said to be held to a minimum by the automatic leg retraction feature, which is controlled by a handle grip and operated without shutting off the drill. In operation the driller exerts moderate pressure on the hand grip to release the feed pressure, and further depresses the control to retract the "stinger" in the leg. Releasing hand pressure automatically stops retraction and restores full feed pressure. To round out the full-hand drill control, a pair of levers on the backhead provide an adjustable feed pressure and extra-strong blowing. ATLAS COPCO PACIFIC INC., 930 BRITTAN AVE., SAN CARLOS, CALIF.

Water and Compressed Air Charge Fire Extinguisher

A fire extinguisher introduced by Ansul Chemical Co. can be charged at the nearest water faucet and compressed air outlets. To fight fires, the operator squeezes the carrying handle, and air at 100 psi squirts a stream of

The One Best Way to

CURE & PROTECT CONCRETE

New concrete must dry slowly for maximum strength. It also needs protection against marring and staining. Sisalkraft provides both . . . *and at low cost!* No kid glove handling with tough Sisalkraft . . . you can apply it *fast* and can even use it over again. Write us at Attleboro, Mass. for free booklet, "Curing & Protection for Better Concrete".



Other Quality Products of the SISALKRAFT Line include:

COPPER ARMORED SISALKRAFT
Pure copper bonded to reenforced paper. For all concealed flashing and waterproofing.

SISALKRAFT MOISTOP
Permanent vapor barrier.

SISALATION
Reflective insulation and vapor barrier.

SISALKRAFT VAPORSTOP
Rot-resistant vapor barrier

SISALITE
Pure polyethylene film

AMERICAN SISALKRAFT CORPORATION
DEPT. ENR-10, ATTLEBORO, MASS.
Chicago 6, New York 17, San Francisco

Doors open straight upward--no space is wasted anywhere

Maximum protection against theft, riot intrusion, vandalism

Every door is REGISTERED[1] for your protection

Extra-heavy zinc coating, for lasting weather resistance[2]



Kinnear Rolling Doors

You get *more* protection plus *more* efficiency in Kinnear Rolling Doors. Coiling above the doorway, they open out of the way! They never block light from close-by windows or fixtures. No floor, wall, or ceiling space is sacrificed. Hoists, conveyors, high-lift fork trucks and similar equipment can be used to maximum advantage.

1. Details on every Kinnear door are REGISTERED—kept in fire-safe vaults. Damaged or worn parts are *permanently* replaceable. Your Kinnear Door is never "orphaned."

2. Kinnear's rugged interlocking-slat curtain is heavily galvanized (1.25 ounces of pure zinc per sq. ft., A.S.T.M. Standards). In addition, the special Kinnear Paint Bond assures immediate, thorough coverage and adhesion of field-applied paint.



Kinnear Rolling Doors are engineered to fit any need, with manual-lift, crank, chain or electrical operation. Controls for motorized doors can be placed at any number of convenient spots. For long, low-cost service, insist on Kinnear Rolling Doors! *Write for catalog.*

The KINNEAR Mfg. Co.
FACTORIES
1620-40 Fields Ave., Columbus 16, Ohio
1742 Yosemite Ave., San Francisco 24, Calif.

KINNEAR
ROLLING DOORS
Saving Ways in Doorways

. . . New Products

water 35 to 40 ft. A gage on top of the tank shows whether or not air pressure is high enough.

Underwriters' Laboratories classify the extinguisher 2-A. Water capacity is 2½ gal. Antifreeze will assure operation at temperatures as low as —40F. Single-unit prices are $47.00, with stainless steel tank; $56.50, brass; $64.60, chromium-plated brass. Ansul Chemical Co., Marinette, Wis.

Powder Forms Weak Acid That Cleans Mortar From Masonry

Lime and mortar can now be removed from brick and other masonry work by a solution claimed to combine the cleaning qualities of strong liquid acids with the advantages of an extremely low corrosion rate. According to the manufacturer, the solution, with a pH of 5.2 (7 is neutral), can be a substitute for muriatic acid, yet does not harm or discolor stainless steel or aluminum doors and windows, nor copper, chrome or nickel trim.

Cleaning time for the solution is comparable to muriatic acid. It is brushed on, then washed off with water. It is cited as causing no noticeable discoloration nor other harmful effect on sandstone, limestone, glazed brick, common brick, quarry tile, prepared mortar, or lime-cement mortar.

In its powder form, the substance is described as non-irritable to skin. Other advantages include lower cost than acid and elimination of carboy breakage.

Suggested mix is 1 lb of powder to 5 gal of water. Berman Chemical Co., 841 Superior St., Toledo 4, Ohio.

Gooseneck Crane Fitted For Low Clearance Jobs

A new 15-ft gooseneck crane attachment, featuring low clearance for in-plant and yard materials handling, is announced by Schield.

Company engineers say that the new attachment has a minimum working clearance height of 10 ft 5 in., when mounted on the self-propelled model CR-35 Bantam, for which it was designed. Working radius at this clearance height is 17 ft 6 in. and travel-with-load crane capacity is listed as 4,675 lb.

The new attachment is a specially constructed 15-ft box boom, with the centerline of the top section offset 25 deg by the insertaion of a wedge with an angle of 25 deg. The wedge is held in place by heat-treated capscrews and is easily removed to convert to a straight-boom operation. Schield Bantam Co., Waverly, Iowa.

(*New Products continued on page 80*)



Two Manitowoc Cranes team up to unload intricate pump assembly at Tidewater Delaware Flying A Refinery construction site.

24 Manitowoc Cranes Help Raise Giant Tidewater Oil Refinery

A total of 24 Manitowoc Cranes is working on the erection of the huge new Tidewater Oil Company Delaware Flying A Refinery near Delaware City, Del. Covering 5000 acres, the ultra-modern refinery will be the biggest built at one time as a single unit, with an expected throughput of 130,000 barrels of oil per day.

C. F. Braun and Co., Alhambra, Calif., designers and engineers for the project, is also handling actual construction of the refinery. The Braun Co. is using 22 Manitowoc crawler cranes, and two Manitowoc Mobile Cranes, units ranging in capacity from 40 to 80 tons, with booms 60 to 120 feet long.

A tremendous variety of jobs are handled by the Manitowocs. Some of the work includes: unloading freight cars, stacking incoming materials, transporting machinery to the construction site, pouring concrete, erecting scaffolding and rigging poles, setting steel; erecting 250 miles of elevated pipeline, laying underground conduits and setting high velocity water pumps on foundations.

Machine downtime on the Tidewater project has been negligible, with no holdup of work due to breakdowns . . . a real testimonial to the ruggedness and solid engineering for which Manitowoc cranes are famous!

Your Manitowoc Distributor will be glad to supply all the details on Manitowoc's versatile line of cranes and excavators — call him today!

MANITOWOC ENGINEERING CORP.,
MANITOWOC, WIS.

What the Men on the Job Think of Their Manitowocs!

"For steel erection you can't beat Manitowoc. One of the finest machines on the market."
Don Rossillo, Crane Operator

"The 2800 is the best motor crane on rubber that was ever made. It will pick up 20 tons without an outrigger and walk away with it."
Jack Streets, Ironworker's Foreman

"For hooking rigs, setting steel, or pouring concrete, Manitowocs can't be beat. And they stand up very well. Been working here an 8 hour day, 5 day week for about ten months and have never been down a minute for repairs."
R. L. Slater, Operator

"This mobile model 2800 is one of the best cranes for all-purpose work. They are strong and smooth running, both on the hoisting and the travelling on the road. Best machine I ever ran, truck or cat."
Prince A. Congleton, Operator

"Sturdiest truck crane on the market, and I've run them all."
Harry Racine, Operator

MANITOWOC
SHOVELS 1-5½ YD. Speed-Crane CRANES 20-100 TON

THE NEW BARCO VIBRA-TAMP*

* Companion Tool to the Barco Rammer, famous for Deep, Penetrating Soil Compaction!

A Versatile Tool for MAXIMUM COMPACTION of

1. Granular Base Materials

2. Bituminous Surfacing

EFFICIENT—one man does the work of many with VIBRA-TAMP. Operates in any weather. Works flush against curbs, foundations, and walls.

ECONOMICAL—to buy, operate, and maintain! No special tools required. Saves your bigger, costlier equipment. Tamp up to 750 sq. yds. per hour.

SAFE—moving parts fully enclosed. Special vibration dampers reduce operator fatigue. Simple controls. Handle adjustable to comfortable height.

DURABLE—simple design and quality construction keep VIBRA-TAMP on the job day in and day out. Carburetor unaffected by vibration.

VERSATILE—use VIBRA-TAMP for all kinds of work—wherever low cost is a prime consideration. Take VIBRA-TAMP on the big jobs for hard-to-reach areas. Use it for patching streets, driveways, and roads. VIBRA-TAMP has no economy equal—a real work-horse on sand, gravel, soil, chippings! *Ask for new catalog No. 630.*

Worldwide Sales and Service

BARCO *Serving Industry Since 1908*
MANUFACTURING COMPANY, 518V Hough St., Barrington, Ill.



Ditcher Digs in Own Tracks With Three-Position Wheel

Develo
dig to wi
of either
announce
Known
308TP, t
er's diggi
three sep
right of t
the mai
claims tha
of the ex
heretofor
ventional
as buildi
features
draulic co
wheel ho
split-shaft
fied grou
Wood
Mich.

MISSING IN NUM

Continuous Smoke Sampler Aids Air Pollution Fight

As an aid to the battle against air pollution, Research Appliance Co. offers the AISI Smoke Sampler. It can be used to (1) make records of smoke concentrations over a long period of time, (2) trace sources of smoke and particles in the air.

The sampler, according to the company, records smoke and other air pollutants by pumping air samples through a filter-paper tape reeling off at half-hour, hour or two-hour intervals. An electric light shines through the polluted tape and the reduction of light transmission is measured by a light-sensitive cell and millivolt meter.

(*Continued on page 85*)



It is pointed out that the low cost (…) it possible …trial firms …ver a wide …et of sam… …ne of the William… …incinnati, …ew York, American …sored the … Smoke …ICE Co., …

N NUMBER ONLY.

…ipes …ng

…cate are …n, a new …tempera… …l in 3-ft… …for pipes up to 33 in. in diameter. Wall thicknesses range from 1 in. to 4 in. Metal bands hold the half-cylinders in place around a pipe.

Even the largest sizes are said to be lightweight and easy to handle. The manufacturer describes the material also as flame-resistant, chemically inert, insoluble in water, dimensionally stable, wear-resistant, easily workable with ordinary tools and strong enough to be fastened over irregular shapes without fear of breakage. KEASBEY & MATTISON CO., AMBLER, PA.



Emergency Warning Flasher Is Visible for One Mile

A new powerful red flashing emergency warning light is offered to mark obstructions, repair or danger areas.

Said to be visible for one mile, the unit includes a new power pack 4" by 5", consisting of two 6-v lantern batteries wired in parallel to yield, what the manufacturer claims, is the most powerful dry battery unit of its type ever developed. Laboratory tests indicate useful life of more than 50 hours of continuous flashing.

To set up, the light-head is merely placed on the battery terminals and two screw caps tightened. BURGESS BATTERY CO., FREEPORT, ILL.

Valve-in-Head Engine for Construction Applications

A new valve-in-head compact four-cylinder V-type engine designed for general application in the construction field has been announced by Avco.

Designated as Model CV4-180, the engine delivers 70 hp at 3000 rpm, and is air cooled.

The engine weighs about 463 lb, less electric starter, generator and flywheel housing which are offered as optional equipment. LYCOMING DIV., AVCO MFG. CORP., STRATFORD, CONN.

Midget 4-Blade Power Trowel Floats and Trowels Non-Stop

A new small model 4-blade cement finishing machine—smallest in a line of three power trowels—has been announced by Superior. The "midget" weighs only 75 lb, its light weight making it suitable for equipment rental firms, smaller contractors. The machine is small enough to pass through narrow doorways and light enough for one man to carry up or down stairs.

A crank adjustment permits the operator to switch blade pitch when the unit is in motion, thereby floating and troweling concrete in one non-stop operation. The crank may be used to change blade pitch up to 30 deg for polishing purposes. The machine is powered by a 1.5-hp gasoline motor and has a blade sweep diameter of 23 in. SUPERIOR CEMENT TOOL CORP., 11616 WRIGHT RD., LYNWOOD, CALIF.



BY CONSTRUCTION EQUIPMENT MEN

Sales records prove that Service-Master is used by more service men than any other body. Service-Master makes work easier . . . saves more time . . . *builds greater profits!*

EXTRA FEATURES!

"Freeze-free" hinges that can't bind • Concealed fenders to protect compartment walls • "Hi-Lo" floor for easier loading • "No-Bounce" bins to keep parts in place • "Puddle-Proof" cargo area . . . and many other "extras".

OUTLASTS SEVERAL CHASSIS Carried in stock in all 48 states by LOCAL Distributors!

FIND OUT FOR YOURSELF Prove to yourself that Service-Master gives you more for your money. Mail this coupon for complete details and price information today.

McCABE-POWERS AUTO BODY CO.
5900 N. BROADWAY • ST. LOUIS 15, MO.
625 CEDAR ST. • BERKELEY 10, CALIF.

Please send me complete details on SERVICE-MASTER

Name_____

Company_____

Address_____

City & State_____

TZS

THE NEW BARCO VIBRA-TAMP*

* Companion Tool to the Barco Rammer, Famous for Deep, Penetrating Soil Compaction!

A Versatile Tool for MAXIMUM COMPACTION of

1. Granular Base Materials

2. Bituminous Surfacing

EFFICIENT—one man does the work of many with VIBRA-TAMP. Operates in any weather. Works flush against curbs, foundations, and walls.

ECONOMICAL—to buy, operate, and maintain! No special tools required. Saves your bigger, costlier equipment. Tamp up to 750 sq. yds. per hour.

SAFE—moving parts fully enclosed. Special vibration dampers reduce operator fatigue. Simple controls. Handle adjustable to comfortable height.

DURABLE—simple design and quality construction keep VIBRA-TAMP on the job day in and day out. Carburetor unaffected by vibration.

VERSATILE—use VIBRA-TAMP for all kinds of work—wherever low cost is a prime consideration. Take VIBRA-TAMP on the big jobs for hard-to-reach areas. Use it for patching streets, driveways, and roads. VIBRA-TAMP has no economy equal—a real work-horse on sand, gravel, soil, chippings! *Ask for new catalog No. 630.*

Worldwide Sales and Service

BARCO *Serving Industry Since 1908*
MANUFACTURING COMPANY, 518V Hough St., Barrington, Ill.



Ditcher Digs in Own Tracks With Three-Position Wheel

Development of a new ditcher able to dig to within 2¼ in. of the outside edge of either its right- or left-hand crawler is announced by Gar Wood Industries.

Known as the Gar Wood-Buckeye 308TP, the position of the new ditcher's digging wheel can be shifted to three separate positions, to the left or right of the main frame or in line with the main frame. The manufacturer claims that this feature overcomes much of the expensive hand digging that has heretofore been necessary when a conventional ditcher met such obstructions as buildings, poles and fences. Other features of the machine include hydraulic conveyor drive, hydraulic digging wheel hoist, variable bucket spacing, split-shaft excavator drive and simplified grouped operator controls. Gar Wood Industries, Inc., Wayne, Mich.

Continuous Smoke Sampler Aids Air Pollution Fight

As an aid to the battle against air pollution, Research Appliance Co. offers the AISI Smoke Sampler. It can be used to (1) make records of smoke concentrations over a long period of time, (2) trace sources of smoke and particles in the air.

The sampler, according to the company, records smoke and other air pollutants by pumping air samples through a filter-paper tape reeling off at half-hour, hour or two-hour intervals. An electric light shines through the polluted tape and the reduction of light transmission is measured by a light-sensitive cell and millivolt meter.

(*Continued on page 85*)



It is pointed out that the low cost ($165) of the device makes it possible for cities, utilities and industrial firms to scatter a number of them over a wide area to get a comprehensive set of samplings. The company lists some of the users of the sampler: Brown & Williamson Tobacco Corp., City of Cincinnati, Consolidated Edison Co. of New York, County of Los Angeles. The American Iron and Steel Institute sponsored the research that produced the Smoke Sampler. RESEARCH APPLIANCE CO., BOX 307, ALLISON PARK, PA.

Molded Insulation for Pipes Is Lightweight and Strong

Asbestos and calcium silicate are molded together in a Kaytherm, a new pipe insulation designed for temperatures up to 1,350 F. Produced in 3-ft-long half-cylinders, it is made for pipes up to 33 in. in diameter. Wall thicknesses range from 1 in. to 4 in. Metal bands hold the half-cylinders in place around a pipe.

Even the largest sizes are said to be lightweight and easy to handle. The manufacturer describes the material also as flame-resistant, chemically inert, insoluble in water, dimensionally stable, wear-resistant, easily workable with ordinary tools and strong enough to be fastened over irregular shapes without fear of breakage. KEASBEY & MATTISON CO., AMBLER, PA.



Emergency Warning Flasher Is Visible for One Mile

A new powerful red flashing emergency warning light is offered to mark obstructions, repair or danger areas.

Said to be visible for one mile, the unit includes a new power pack 4" by 5", consisting of two 6-v lantern batteries wired in parallel to yield, what the manufacturer claims, is the most powerful dry battery unit of its type ever developed. Laboratory tests indicate useful life of more than 50 hours of continuous flashing.

To set up, the light-head is merely placed on the battery terminals and two screw caps tightened. BURGESS BATTERY CO., FREEPORT, ILL.

Valve-in-Head Engine for Construction Applications

A new valve-in-head compact four-cylinder V-type engine designed for general application in the construction field has been announced by Avco.

Designated as Model CV4-180, the engine delivers 70 hp at 3000 rpm, and is air cooled.

The engine weighs about 463 lb, less electric starter, generator and flywheel housing which are offered as optional equipment. LYCOMING DIV., AVCO MFG. CORP., STRATFORD, CONN.

Midget 4-Blade Power Trowel Floats and Trowels Non-Stop

A new small model 4-blade cement finishing machine—smallest in a line of three power trowels—has been announced by Superior. The "midget" weighs only 75 lb, its light weight making it suitable for equipment rental firms, smaller contractors. The machine is small enough to pass through narrow doorways and light enough for one man to carry up or down stairs.

A crank adjustment permits the operator to switch blade pitch when the unit is in motion, thereby floating and troweling concrete in one non-stop operation. The crank may be used to change blade pitch up to 30 deg for polishing purposes. The machine is powered by a 1.5-hp gasoline motor and has a blade sweep diameter of 23 in. SUPERIOR CEMENT TOOL CORP., 11616 WRIGHT RD., LYNWOOD, CALIF.

POWERS

Service-Master®

THE ALL-PURPOSE SERVICE BODY



ACCLAIMED BEST

BY CONSTRUCTION EQUIPMENT MEN

Sales records prove that Service-Master is used by more service men than any other body. Service-Master makes work easier . . . saves more time . . . *builds greater profits!*

EXTRA FEATURES!

"Freeze-free" hinges that can't bind • Concealed fenders to protect compartment walls • "Hi-Lo" floor for easier loading • "No-Bounce" bins to keep parts in place • "Puddle-Proof" cargo area . . . and many other "extras".

OUTLASTS SEVERAL CHASSIS Carried in stock in all 48 states by LOCAL Distributors!

FIND OUT FOR YOURSELF Prove to yourself that Service-Master gives you more for your money. Mail this coupon for complete details and price information today.

McCABE-POWERS AUTO BODY CO.

5900 N. BROADWAY • ST. LOUIS 15, MO.
675 CEDAR ST. • BERKELEY 10, CALIF.

Please send me complete details on SERVICE-MASTER

Name_____

Company_____

Address_____

City & State_____

TZS

In Pasco, Washington, too— Clevelands do the digging

DISTRIBUTION SYSTEMS in Pasco and Kenewick, Washington, are being constructed for Cascade Natural Gas Company by A. J. Curtis Construction Company of Casper, Wyoming. Even in alleys and similar narrow rights of way, such as the 4-inch main installation shown, Curtis, cashing in on the compactness and maneuverability of his Cleveland trenchers, is averaging 1,650 feet of trench per 6-hour day.

Crowded cramped quarters or open fields, rocky soils or easy digging—Cleveland's original compactness, maneuverability, exclusive wide range of power and speed combinations and recognized quality construction are the reasons they dig *more trench . . . in more places . . . at less cost.* That's why you'll find Clevelands leading the way on gas work in the Pacific Northwest —as they have *everywhere* for over 30 years.

THE CLEVELAND TRENCHER CO.

20100 ST. CLAIR AVENUE • CLEVELAND 17, OHIO

Good Everywhere

Publications

Steel stud—A newly-revised, 16-page catalog has recently been produced by The Bostwick Steel Lath Co. The revision centers around the new Chan-I-Form Stud now being manufactured by the company. This four-page section of the catalog covers elements of construction, weights, flexibility, job adjustments, sizes, framing of openings, ceiling attachment, and full page of architectural specifications concerning steel studding. The remainder of the catalog deals with all the rest of the Bostwick products and their accessories. THE BOSTWICK STEEL LATH CO., NILES, OHIO.

Materials handling trucks—Lewis-Shepard, Watertown, Mass., offers a 132-page catalog on its "Master Line" of materials handling trucks, which describes all models of L-S trucks available. The catalog is indexed into five categories, fork trucks, stackers, cranes, handlift trucks and floor trucks. The company also has recently released a 2-page circular that describes its 2,500-lb. Space-Master Model JFTT 2.5, designed for extreme heavy duty operation. LEWIS-SHEPARD, INC., WATERTOWN, MASS.

Lighting folder—A revised catalog folder describes new improved Turreter "Series 5" heavy-duty industrial fluorescent lighting fixtures. Contained are specifications, photometric data and other information. The Smithcraft Turreter "Series 5" is designed to meet a wide range of industrial needs with a minimum of glare because of its 10% uplighting features. SMITHCRAFT LIGHTING DIV., CHELSEA 50, MASS.

Watertight pipe joints—A new-type rubber joint for coupling small diameter concrete bell and spigot pipe is described in a 4-page illustrated brochure just released. The brochure gives engineering data, sketches and photographs illustrating the use of the joint. REXON "K" GASKETS, HAMILTON KENT MFG. CO., 427 W. GRANT ST., KENT, OHIO.

Electrified baseboard—A new eight-page circular entitled "2200 3-in-1 Plugmold Electrified Baseboard" illustrates and describes the advantages of the product from the point of view of architects, builders, electrical contractors, etc. and shows its applications in residential, commercial and industrial buildings where multiple electrical outlets and additional circuits are needed. Form 590. THE WIREMOLD CO., HARTFORD 10, CONN.

DELIVERING WATER CHEAPER

This 49½" OD Dresser-Coupled steel pipe line called for wall thicknesses ranging from ⅝" to 1" to withstand line pressures up to 650 psi. Notice how deflection of the pipe in the Dresser Couplings permits construction of long curves, using only straight sections.

Local workmen with no special training made bottle-tight joints with Dresser Couplings. Couplings were wrench-installed in an average of less than 25 minutes.

Steel Water Line Beats Rugged Terrain to Serve Progressive Caracas, Venezuela

Like hundreds of other fast-growing South American cities, Caracas, Venezuela, faced a serious water supply problem. The problem is being solved for years to come with a 17.4-mile Dresser-Coupled steel water line running from the Tuy River to the city's reservoir at Mariposa.

From the job specifications alone, an engineer can picture the sort of terrain the line passes through. Line pressures run as high as 650 psi. Backfill cover depth ranges from 5 to 25 feet. The line bridges 128 ravines. In some sections the terrain is so rugged that aerial tramways had to be used to transport and lay the pipe sections.

Dresser Couplings played a vital part in the success of this difficult project. Even though the contractor had no previous experience with Dresser Couplings, the line went in at the average rate of 32 lengths a day, with inexperienced local laborers making bottle-tight joints. The deflection of pipe possible with Dresser Couplings was an invaluable advantage in the laying of curves. The high beam strength of steel pipe assured safe ravine crossings with a minimum of structural support.

This project is typical of the sort of foresighted engineering that is building great cities in South America today. Steel pipe and Dresser Couplings are the ideal combination for rugged terrain, and they assure a bottle-tight, trouble-free line that *delivers water cheaper* for generations to come. Dresser Manufacturing Division, Bradford, Pa.

ONE OF THE DRESSER INDUSTRIES

Conrad G. Seebolt, vice president of Seebolt, Inc., South River and Red Bank, says, "We specified a second Heltzel plant on the strength of performance of our first. I feel re-ordering to be the strongest kind of recommendation!"

Tony Stepher, secretary-treasurer Mutual Contracting Co., Belmar—"From the performance of our first—we have just purchased our second Heltzel plant—and when it comes time for the third—that, too, would be all Heltzel."

In New Jersey too, HELTZEL



Mr. Walter Cortier, owner Allied Transit Mix Corp., Freehold—"We are thoroughly satisfied with the Heltzel plant! We wish to further state that recently a nationally known firm of consulting engineers made a plant survey and reported that it is one of the best layed out plants they surveyed in the last few years."

Ted Farrell, manager Monmouth Lumber and Concrete, Deal—"We operate other makes, but this new Heltzel has them all beat for speed and accuracy. We are Batchmaster® boosters from now on."

Says Mr. Harold Collins of Collins Brothers, Inc., Keansburg—"We're extremely satisfied with our Heltzel Batchmaster®. I've just installed my second plant and if it's anything like the first, I'll be more than happy."

Christian Fisher, partner in Toms River Concrete Co., and Ocean Concrete Co., Manahawkin, reports, "My partner and I feel equipment is the keynote to success. We want the finest obtainable, and that's why we selected Heltzel."

stands out!

The story's the same wherever you go. Men who know concrete prefer *HELTZEL BATCHMASTER PLANTS*

The eight Heltzel Batchmaster Plants pictured on these pages are grouped within a few miles of each other along the North Jersey Shore, furnishing contractors of that area with all their concrete requirements. This concentration of Heltzel equipment is typical throughout the nation, for these fast, accurate, profit-producing plants have a universal appeal for those who know concrete.

There are dozens more of these plants in New Jersey, and hundreds of them spread throughout the 48 states, each providing its owner with efficient, trouble-free batching.

There's a reason for this leadership. Heltzel has been building concrete handling, forming and spreading equipment for almost 50 years. They know the industry and its needs. They have the background necessary to assure the finest in practical engineering, dependable products and quick service.

When next you're in the market for batching equipment, remember it costs no more to have the finest — that's a Heltzel Batchmaster* Plant!

At Wayside, New Jersey, Duncan Thacker, owner of Campbell Concrete Co., says, "We looked them all over, and talked with a lot of people before we made our selection. I'd say we have the finest equipment possible in our new Heltzel Batchmaster*".

*T.M.

THE HELTZEL STEEL FORM AND IRON COMPANY
89807 THOMAS ROAD
WARREN, OHIO

10019



Amsco Backhoe Buckets **WORK-HARDEN IN SERVICE**

One-piece castings of extra-tough manganese steel give maximum impact and abrasion resistance

Impact work-hardens manganese steel to as high as 550 BHN. Further abrasion only polishes this tough steel. That's why Amsco® manganese steel outlasts other steels by as much as ten to one, under heavy impact and abrasion.

An Amsco Backhoe Bucket is a tough, *one-piece* manganese steel casting. This one-piece body eliminates the danger which fabricated-bucket users face of the hoe bucket breaking up when digging in rock or rough operations. The teeth on Amsco hoe buckets are reversible and renewable, and side cutters can be bolted on to order.

On scores of tough digging jobs, you'll find these Amsco buckets cutting a full swath, unloading cleanly and providing maximum digging efficiency.

Available in both standard and special styles, in all regular sizes from ⅝-yard to 1½-yard capacity. For full information, call your nearby Amsco representative or your shovel manufacturer's dealer.

AMERICAN Brake Shoe COMPANY

AMSCO

American Manganese Steel Division • Chicago Heights, Ill.

OTHER PLANTS IN: DENVER, LOS ANGELES, NEW CASTLE, DEL., OAKLAND, CAL., ST. LOUIS- JOLIETTE QUEBEC

1. Basic Step—Coarse granular sub-base has been shot with 85/100 asphalt cement, and compacted, after old paving is removed.

2. First Course—Steel-tired roller compacts 1-in. leveling course of asphaltic concrete. Wire fabric sheets, at side, will be placed on this course.

3. Final Step—Two-inch asphaltic concrete binder course has been placed over fabric and is ready for bus use. Fabric is lapped for continuity.

Fabric Added to Bus-Stop Pad

Encouraged by the success of a test installation, the Port of New York Authority has recently completed resurfacing of the heavily traveled north passenger bus stop on the George Washington Bridge. A 50-ft test section, put down in October 1954, proved satisfactory under more than 500 bus loadings daily and, according to PNYA officials showed little or no rutting, rippling or shoving that has been apparent in unreinforced areas.

As a result, resurfacing of the entire 5,100-sq-yd area of the stop was undertaken during the summer as part of a general maintenance and repair program. The $28,297 contract (including curb removal) was awarded to Anthony Grace & Sons, New York City.

Job reports indicate that cost of asphalt in place was about $5 per sq yd, cost of the 3 x 6-10/10 fabric was about 40 cents per sq yd.

(F & O continued on page 92)

RUBBING CEILINGS?

Do it

G *with a*

I R A F F E

CEILING GRINDER

- **FASTER AND EASIER:** One man will average almost 4000 sq. ft. per day. Does not need scaffolding.
- **CHEAPER AND BETTER:** Money saved on finishing will help pay for grinding.
- **DEPENDABLE:** Individual GIRAFFES have worked more than 1,000,000 square feet without major overhaul.

GIRAFFE®

Heights up to 24 ft.

Has been adapted to cleaning ceilings.

CONCRETE GRINDING CORP.
300 STRAIGHT ST. PATERSON, N. J.



Asphalt Cap Solves Seawall Problem

Placement of an asphaltic stabilization cap apparently has solved a tough seawall repair problem at the Seattle (Washington) Army Terminal.

The original seawall was a 30-year-old two-step bulkhead of piling and gunite coated planks. Erosion and the pounding of waterborne debris had broken the rigid capping and allowed water to tear away the supporting riprap fill. The cavities thus created resulted in ever increasing settlement of the cap, and the excessive deterioration of the planking permitted water to enter the terminal's boiler room.

The repair problem was compounded by the fact that the seawall is completely covered by decking and pier structures—all in good shape—limiting headroom and access. With as little as 3 ft of clearance in some areas, use of equipment was out of the question.

Because of its flexibility, durability, and adaptability to manual application, asphalt was selected as the capping material.

The job involved the repair of 1,000 ft of seawall. Washed out riprap was replaced by 626 tons of rock, in stones ranging in weight from 20 to 225 lb. Voids were filled with 390 tons of spalls. A trench was left at the base of the slope to accommodate 18 in. of asphalt. On the rest of the slope, the asphalt cap was held to a thickness of 4 in.

The contractor used 379 tons of 85/100 penetration asphalt which, in loads of 7 to 8 tons, was dumped on the deck, and shoveled to men below. In spite of manual placement and interference from tides (work could be done only at low water) aggregate application averaged 40 tons per eight hour day.

The job was done by Larsen Construction Co. of Seattle under the direction of Stanley Nelson, principal engineer for the army terminal.

Novel Pile-Driving Method Expands Base, Shrinks Cost

To lick the foundation problems posed by sandy soil and a high water-table on a building site in Jacksonville, Fla., builder E. C. Kenyon adopted a novel method of pile driving devised by John Gravely, Jacksonville architect. He sank short casings, scooped out a wide cavity below the lower end of each and after placing the mix forced it to expand under pressure against the sand walls of the cavity. The method cost 75% less than conventional foundation construction.

The building is a one-story, 5,200-sq-ft rigid-steel-frame structure supported by 52 piles. Pile diameters vary from 18 in. to 24 in. at the top, 33 in. to 42 in. at the bottom. All penetrate at least 4½ ft below ground level.

The builder first dewatered the ground. Then, with the base of a cylinder set 3 ft deep (or below water level), a workman hollowed out the cavity below it with a posthole auger held at an angle. Cavity and casing were then filled with concrete and a 6-in. wood block floated on top of the wet mix. A series of blows on the block from a 500-lb hammer, forced the concrete to expand against the cavity walls, compacting the sand and enlarging the opening.



"heavy" concrete for reactor shields

High-density concrete, an efficient and practical radiation shielding material, is destined for wide use in nuclear reactors.

The high density results from the use of heavyweight aggregates and affords 1½ to 2 times more radiation protection than normal weight concrete of equal thickness. Its higher unit cost is offset by overall cost savings, which on one project amounted to $7,000,000!

INTRUSION-PREPAKT materials and methods are a proved solution for placing high-density concrete in massive, complex shields having a maze of obstructions. High-density aggregates are carefully preplaced to assure uniform density without segregation. Consolidation with INTRUSION mortar produces a PREPAKT concrete structure free of radiation leaks. Densities to 300 lbs./cu. ft. and over can be achieved, usually at less cost than by conventional methods.

INTRUSION-PREPAKT experience in placing high-density concrete reactor shields qualifies it as the top organization to work with on such projects. You will deal with a firm that *specializes* in concrete construction and maintenance, *has* a complete field construction group and *offers* an engineering design service. For information, write: INTRUSION-PREPAKT, Inc., Room 779-O, Union Commerce Bldg., Cleveland 14, Ohio. In Canada: INTRUSION-PREPAKT, Ltd., 159 Bay St., Toronto, Ontario.

A new technical bulletin on "High-Density PREPAKT *Concrete" is now in preparation. We will be glad to send you a copy. Send a request on your letterhead, please.*

INTRUSION-PREPAKT, INC.

OFFICES IN PRINCIPAL U.S. AND FOREIGN CITIES

Intrusion and Prepakt are trade marks of Intrusion-Prepakt, Inc., whose methods and materials are covered by U. S. Patents Nos. 2313110, 2655004, 2434302 and others, also patents pending.

How to make a school foundation
water repellent, sturdy and *long lasting*

THOROSEAL
Foundation Coating



Correct procedure is shown here, where foundation is given 2 brush coats of THOROSEAL Foundation Coating, immediately after construction forms are removed.

Poured concrete exterior walls and tunnel walls, 2 coats of Foundation Coating, and inside concrete block walls, 2 coats of THOROSEAL

Bagley School
Pontiac, Michigan
Architect—William Zimmerman
Contractor—Nolan Gottschall

NO MAINTENANCE COST HERE!

THOROSEALING the foundation walls of this new school building, means less upkeep, less repairs. Water cannot penetrate masonry now and cause costly damage.

Get our pictorially described literature
"HOW TO DO IT"
STANDARD DRY WALL PRODUCTS INC.
NEW EAGLE, PENNSYLVANIA

Obituaries

C. B. Williams, 54, vice president of Morrison-Knudsen Co., Inc., Boise, Idaho, died at Boise, August 4.

Mr. Williams worked as field supervisor or directly managed the building of 25 dam and tunnel projects during his 32 years with Morrison-Knudsen. At the time of his death, he was concerned with construction of Brownlee and Oxbow dams for Idaho Power Co. in Hells Canyon; Table Rock Dam in Missouri; Donnells Dam in California and Noxon Rapids Dam in Montana. He also was advisor for the company on Seyhan Dam in Turkey and a river development project in Iran.

He was credited with development of the jumbo for use in tunnel drilling; an overhead loading machine for removal of tunnel muck; and he contributed improvements to aerial cableways for placing concrete on big dams, and to a concrete batching system.

Clarence McDonough, 66, president and director of The Foundation Company, died in New York City on Sept. 19. A native of Gloversville, N. Y., he attended Cornell University and was graduated in 1912 from M.I.T. He joined The Foundation Company in 1913 and became district manager for the Pittsburg area. From 1926 to 1930 he was chief engineer in charge of foreign activities of the company.

Mr. McDonough was for two years director of engineering for the Public Works Administration and later served as general manager and chief engineer for the Lower Colorado River authority. In the latter capacity he had charge of construction of Buchanan, Inks, Mansfield, and Austin dams. He spent several years with the H. K. Ferguson Company before rejoining The Foundation Company in 1943. He became president of the firm three years ago.

Philip J. Gray, 67, died in April in Lake Worth, Fla. A 1912 graduate of Cooper Union, in New York City, Mr. Gray spent many years in heavy construction engineering, including erection of Hell Gate Bridge in Connecticut, the foundation of New York City Municipal Building, and the St. Lucie locks on the St. Lucie River.

William Murray Lybrook, 58, director of public service at Greensboro, N. C., died Sept. 10. A graduate of Virginia Polytechnic Institute in 1921, he had been with the City of Greensboro since October, 1927. He was promoted to superintendent of water and sewer plants in 1937 and was elevated to director of public service 10 years later.

strong

Roebling's finest!

Royal Blue's extra strength

vastly increases...even doubles...

wire rope service life

John A. Roebling's Sons Corporation, Trenton 2, N. J., Subsidiary of The Colorado Fuel and Iron Corporation BRANCHES: ATLANTA, 934 AVON AVE. • BOSTON, 91 SLEEPER ST. • CHICAGO, 5525 W. ROOSEVELT RD. • CINCINNATI, 3340 GLENDALE-MILFORD RD., EVENDALE • CLEVELAND, 13235 LAKEWOOD HEIGHTS BLVD. • DENVER, 4801 JACKSON ST. • DETROIT, 915 FISHER BLDG. • HOUSTON, 5315 NAVIGATION BLVD. • LOS ANGELES, 5340 E. HARBOR ST. • NEW YORK, 19 RECTOR ST. • ODESSA, TEXAS, 1920 E. 2ND ST. • PHILADELPHIA, 230 VINE ST. • PITTSBURGH, 1753 HENRY W. OLIVER BLDG. • SAN FRANCISCO, 1740 17TH ST. • SEATTLE, 900 1ST AVE. S. • TULSA, 321 N. CHEYENNE ST. • EXPORT SALES OFFICE, 19 RECTOR ST., NEW YORK 6.

WINDOW TREATMENT IN A HOSPITAL

...BUILDS PATIENT MORALE

ONE WHOLE WALL OF EVERY ROOM IS MADE INTO A PICTURE WINDOW BY COMBINING CECO-STERLING ALUMINUM DOUBLE-HUNG AND FIXED WINDOWS . . .

The therapeutic value of sunshine and view had much to do in guiding Pereira & Luckman, planners, architects and engineers of Los Angeles and New York City, in designing the Grossmont District Hospital. To give patients a better outlook they made the whole side of each room into a wall of glass—a picture window bringing in sunshine and acres of view.

Ceco-Sterling Aluminum Double-Hung and Fixed Windows accomplished the desired effect. Maximum glass was possible because of slender sleeving mullions and narrow sash sections. And important, too, was the tight weather-seal provided by Ceco Windows. On your next building project, consult Ceco Engineers. They will help you make effective use of metal building products.

CECO STEEL PRODUCTS CORPORATION

Offices, warehouses and fabricating plants in principal cities
General Offices: 5601 West 26th Street, Chicago 50, Illinois

IN CONSTRUCTION PRODUCTS CECO ENGINEERING MAKES THE BIG DIFFERENCE

Windows, Screens and Doors / Ceco-Meyer Steelforms / Concrete Reinforcing / Steel Joists / Metal Roof Deck / Metal Lath

Front elevation of Grossmont District Hospital, San Diego, California presents interesting pattern of light and shade, with Ceco-Sterling Aluminum Double-Hung and Fixed Windows and Screens providing echo accents for the main motif. Pereira & Luckman, planners, architects and engineers.

There's minimum air infiltration with the use of Ceco-Sterling Double-Hung Monumental and Commercial Windows, Series 200-B. That's because the sash float on stainless steel weather stripping, assuring tight, freely operating, vertical sliding windows. They operate silently, so necessary in hospital windows.



The sweep and pattern of the window treatment lend stately drama to Grossmont. Visors over the windows and right-angle fins control glare while admitting abundant light.



Note the heavy extruded box sections for rugged performance, and the double-contact stainless steel weather stripping for tightness. Similar weather strip at jambs provides a spring cushion contact, holds sash clear of frame for easy sliding.



Here's what you need to know about Cables for Bridges, Towers, Aerial Tramways

Bethlehem has just published a new and comprehensive handbook devoted to the uses of wire rope and strand in bridges, towers, aerial tramways, etc. This 160-page book is filled from cover to cover with practical information and interesting photographs. There are also drawings showing structural and anchorage details, and various types of sockets and clips. All in all, the book has more than 200 illustrations.

SEND FOR FREE COPY. A copy is yours for the asking. No charge, of course. Simply address your request to Publications Dept., Bethlehem Steel Company, Bethlehem, Pa.

And when you have questions on cables and fittings, please feel free to consult personally with our engineers. These technicians are very close to the subject; they live with it and work with it every day. You'll find them friendly and cooperative, and always interested in helping you solve your problems.

BETHLEHEM STEEL COMPANY, BETHLEHEM, PA.

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation. *Export Distributor:* Bethlehem Steel Export Corporation

Bethlehem makes bridge strand and bridge ropes in all the popular sizes. Moreover, our Williamsport plant has prestretching facilities for handling any length of strand or rope that can be manufactured and shipped.

BETHLEHEM STEEL

BETHLEHEM STEEL

Legal

A Contract May Require Compulsory Arbitration

All disputes within the scope of an arbitration clause must be settled by arbitration if either party to the contract insists upon it.

The following case shows some of the difficulties that may be met:

The owner, the Board of Education of the Town of Bath, New York, entered into a contract with two architectural firms in connection with the construction of school buildings. The contract between the owner and the architects contained the following provision: "12. Arbitration. All questions in dispute under this agreement shall be submitted to arbitration at the choice of either party." On the day the contract between the owner and the architects was entered into, the two architects entered into a contract of their own in reference to the work to be done, and this contract incorporated by reference the provisions of the contract between the owner and the architects.

Under the terms of the contract between the architects, one of them (Ervay J. Baker) was responsible for the issuance to the contractor of the supervision of construction and certificates entitling the contractor to interim payments. During the course of construction, Baker, believing that the payment of a requisition of $81,000 would amount to a total payment in excess of the contractor's cost up to that time and might enable the contractor to avoid the completion of the unfinished work within the contract price, notified the contractor that he required a justification of the requisition before he would approve the payment. The contractor notified the board and Baker of his intention to terminate the contract, and ceased work. Then the board negotiated a settlement with the contractor without consulting Baker or considering the data Baker had assembled, justifying, in his opinion, the refusal to certify the payment. The board then discharged Baker and this architect did not receive any subsequent compensation.

Baker filed claims against the board of education, one for the fees due to the associated architects and the second for Baker's share of the fees paid to the associated architects plus his disbursements, the second claim being founded on the theory of the board's liability arising from the board's action in compeling the other architect to sever his relation with him. Upon rejection of the claims, Baker requested the other architect and the board of education to arbitrate the dispute. The other architect and the board of education made an application to the court to issue an order staying the arbitration and such an order was granted. Baker then appealed to the Appellate Division which affirmed the determination of the lower court. Baker then appealed to the Court of Appeals which reversed the order of the lower courts and held that the matters in dispute under the terms of the contract were matters that should be determined by arbitration.[1]

The Court of Appeals made this observation: "It is our view that a bona fide dispute exists which must be arbitrated pursuant to clause 12 of the contract. Any differences between Baker and his associate architect, 'White and Helm,' arose out of the performance on his part of his duties under the contract. The dispute, therefore, is between Baker and the board as to the propriety of their respective acts. Since the disputes are within the scope of the arbitration clause, they must be settled by arbitration, if demanded by either party."

[1] Arbitration Between Baker and Board of Education of Central School District of Bath, 132 N. E. 2d 837, N. Y. Court of Appeals, Feb. 16, 1956.

Federal Anti-Kickback Law And Government Contracts

Agreements to pay consideration for getting a government contract are void. Under the Anti-Kickback Act, the government can recover the amount paid from the person who gave the bribe.

Here's how it worked in one case:

The Fisher Body Division of General Motors Corporation employed a supervisor who had authority to award subcontracts for the making of blueprints in connection with work Fisher was doing for the United States Government. The supervisor did not establish the contract price, but merely awarded subcontracts at a price predetermined by his superiors to subcontractors who had the available time and facilities for making blueprints. He was also limited in his choice to a list of qualified subcontractors prepared by his superiors.

One of the qualified subcontractors on the list had previously been engaged in blueprint subcontract work for Fisher. Not having recently re-

For Low Cost Paving or Patching

McConnaughay ASPHALT MIXERS



HTD-800: up to 10 tons hot mix, 30 tons cold mix per hour.

HTD-500: up to 7 tons hot mix, 15 tons cold mix per hour.

HTD-B: up to 5 tons hot mix, 10 tons cold mix per hour.

HTD-B TRUCK MOUNT: up to 5 tons hot mix, 10 tons cold mix per hour.

For details and specifications, write, wire or 'phone . .

K. E. McCONNAUGHAY
LAFAYETTE, INDIANA

National distributors: Asphalt Equipment Co., Inc., 3929 Buell Drive, Fort Wayne, Indiana

Summitville
GLAZED
Quarry Tile
...perfect for
pools
patios
distinctive walls
Summitville Glazed Quarries have all the rugged characteristics of Quarry tile, long famous for unequalled strength and durability. To these inherent qualities, Summitville has added beautiful ceramic glazes in a wide variety of colors and textures.
The new glazed quarries are waterproof and frostproof which makes them especially adaptable to exterior use. Suggested applications for glazed quarries include light duty floors, patios, feature walls, counter tops, store fronts and swimming pools.
Contact your Ceramic tile contractor for samples and full information or write to...
Summitville TILES, INC.
SUMMITVILLE, OHIO

ceived any subcontracts from Fisher, it contacted the supervisor who informed him not to expect any more orders for blueprints unless he shared his profits with the supervisor. The subcontractor agreed to do this and thereafter received orders from Fisher. The supervisor was paid $27,425 as his share of the profits.

The Government brought an action under the Anti-Kickback Act to recover the amount paid to the supervisor. The evidence produced at the trial showed that the subcontractor did not charge Fisher any more for the blueprints than it had charged before it made any kickbacks. The Government obtained a judgment for the full amount of the kickbacks paid.[1]

The court stated: "It has long been held that contracts for the payment of commissions for securing Government contracts or congressional favors which have a tendency to corrupt are void as against public policy. * * * The kickbacks paid to Brune (the supervisor) definitely had a tendency to corrupt him for the continued awarding of blueprint orders to the defendants who conditioned upon the payment of kickbacks to him and did influence his choice of subcontractors."

The action was brought against the subcontractor who furnished the blueprints and the court held that the Government could recover the amount paid to the supervisor even in the absence of proof of pecuniary loss on the theory that the subcontractor would have furnished the blueprints at a lower price if he had not paid bribes to get the contract.

[1] United States v. Davio, 136 F. Supp. 423, U. S. District Court, Dec. 30, 1955.

Acceptance of Building As a Waiver of Defects

When a purchaser buys a house from a builder, does his acceptance of the deed release the builder from liability for defects later discovered?

As the following case illustrates, the answer depends upon how the contract of sales is worded and whether the builder has misled the purchaser. These were the circumstances:

The purchaser of a building brought an action against the seller (who was also the builder) to recover damages for defects in a building. The action was predicated on two claims: first, that the purchaser was induced to enter into the contract for the purchase of the property as a result of fraudulent misrepresentation in an advertisement inserted in a New York paper; and second, on the ground that the building as constructed was defective and the purchaser was entitled to recover damages for breach of contract.

The seller asked the court to dismiss the action or to require that the pleadings be made more definite and certain. His reasons were these: First, that the purchase contract expressly provided that the written contract stated the entire agreement between the parties and relieves the seller from being bound by any stipulations, representations, agreements or promises, oral or otherwise, not printed or inserted in the written contract; and second, that the written contract provided that acceptance and delivery of the closing deed shall constitute full compliance by the seller with the terms of the contract on its part to be performed except as to matters which are specifically made to survive the title closing.

The court dismissed the action to the extent that the sale was based on fraudulent misrepresentations, the court holding that the contract barred the right to such action. As to the claim that the house was not properly built, the court held that the pleadings were too vague to show that the claimed defects came into the category of the exceptions set forth in the contract that were to survive the acceptance of the deed, and permitted the purchaser to serve an amended complaint to show that the defects in question came within the exceptions set forth in the contract.[1]

The court stated: "It is well established that every contract implies good faith and fair dealing between the parties. M. O'Neil Supply Co. v. Petroleum Heat & Power Co., 280 N.Y. 508, 19 N.E. 2d 676. A corollary of this principle is the doctrine that in every contract there is an implied covenant that neither party will do anything having the effect of destroying or injuring the right of the other party to receive the fruits of the contract. Halstead v. General Ry. Signal Co., Sup., 51 N.Y.S. 2nd 372, affirmed 268 App. Div. 1060, 52 N.Y.S. 2d 660. Thus, there was an implied term of the agreement here that the house would be constructed in a good and workmanlike manner in addition to the express covenants that the work and materials would comply with the requirements of the municipality having jurisdiction and those of the lending institutions making the mortgage loan. If the house did not meet such standards, then, in the absence of other contract provisions barring relief to the purchaser,

Beesleys Point, N. J. Bridge on Garden State Parkway.
Contractor and Erector: Ole Hansen.



Detail of Parapet Post and Railing

"Look, Pop, No Cranes"

Flynn-extruded aluminum bridge rails — the new pace-setting standard in modern bridge construction — completely eliminate the need for cranes, lift-trucks and large crews. At the Beesleys Point Bridge, one man was all they needed to install these gleaming, eye-appealing rails. That's because they're lightweight aluminum . . . extruded by Flynn for faster, easier, less costly installation.

What's more, they'll never need painting . . . are fully weather-resistant . . . and are engineered by Flynn's Bridge-Rail Headquarters for maximum strength with minimum material. Whether you want a custom-designed profile, or prefer one of the many dies in stock at Flynn, you can be sure of top quality, efficient service and on-schedule deliveries. On your next order, talk it over with Flynn. No obligation, of course.

FLYNN
EXTRUSIONS

MICHAEL FLYNN MANUFACTURING COMPANY
Extrusion Division
700 East Godfrey Avenue, Philadelphia 24, Penna.
Telephone: FIdelity 2-5500

51 East 42nd Street, New York 17, N. Y.
Telephone: MUrray Hill 2-0625

937 Radcliffe Road, Towson, Md.
Telephone: VAlley 3-2090

133 Maple Street, Springfield, Mass.
Telephone: REpublic 3-2814



If you can reach it, you can fasten it with *Ramset*®

One-hand operation in awkward places is simple with a light RAMSET powder-actuated tool. It's ideal for ladder and scaffold work.

For anchoring to concrete or steel, the new DUO-JOBMASTER® sets ¼" and ⅜" fasteners interchangeably—merely by switching barrels right on the job! Yet the tool does not change size or weight!

There's no need to exert physical power when you use RAMSET. Let the power charge do the work! No wires, no hose to drag or untangle. RAMSET is entirely self-contained.

Tough jobs are now easy with RAMSET. No more drilling, filling, plugging and bolting. RAMSET fasteners are set at the press of the trigger—have greater holding power than old-style methods.

Speed your production, make work easier for operators, cut your costs, get more dependable performance by using RAMSET whenever fastening to concrete, steel or other hard materials.

Write for free new catalog, ready for you now.

companion tool

Shure-Set
TRADEMARK

Baby brother to RAMSET, this hammer-in tool uses no cartridge, but makes your own hammer power more effective. For masonry, mortar joints, cinder block. Ask for literature.

Ramset Fastening System
WINCHESTER-WESTERN DIVISION
OLIN MATHIESON CHEMICAL CORPORATION
12107-J BEREA ROAD • CLEVELAND 11, OHIO

he would have an actionable claim for breach of contract." The court indicated, however, that where as in the instant case, the contract specifically provided that the acceptance and delivery of the deed shall be deemed to constitute full compliance by the seller as to certain matters stipulated in the contract, no right of action exists except as to matters that the contract stipulated would survive the acceptance of the deed.

As to the court's decision that the action couldn't be maintained on the grounds of fraudulent misrepresentations because of the fact that the contract contained a provision to the effect that it would not be liable for such misrepresentations, the writer desires to call attention to the case of Jackson v. State, 210 App. Div. 115, affirmed by the Court of Appeals (241 N.Y. 563). There the court stated: "A party to a contract cannot by misrepresentation of a material fact, induce the other party to the contract to enter into it to his damage, and then protect himself from the legal effect of such misrepresentation by inserting in the contract a clause to the effect that he is not to be held liable for the misrepresentation which induced the other party to enter into the contract. The effect of misrepresentation and fraud cannot be thus easily avoided. If it could be, the implied covenant of good faith and fair dealing existing in every contract would cease to exist."

[1] Lutz v. Bayberry Huntington, Inc., 148 N. Y. S. 2d 762, N. Y. Supreme Court, Nassau County, Jan. 16, 1956.

Right to Withdraw Bids After Errors Discovered

In some states, a contractor who discovers an error in a bid after it has been submitted may be able to get the contract rescinded.

In Georgia, for example, the Housing Authority of the City of Hazelhurst advertised for bids for the construction of two housing projects. The terms set forth in the invitation to bidders provided that "No bid shall be withdrawn for a period of thirty (30) days subsequent to the opening of bids without the written consent of the Housing Authority of the City of Hazelhurst, Georgia."

The low bid was submitted by H. W. Ivey and was in the amount of $463,733. It was accepted subject to the approval of the Public Housing Administration.

A representative of Ivey was present when the bids were opened and when the motion conditionally accepting the



Two-way protection for $60,000,000 Hudson River Bridge with

Pittsburgh's X-L-O STRUCTURAL STEEL PRIMER

1 Safeguards steel shapes against corrosion during shipment and erection

2 Provides excellent foundation coat for field painting

ONE OF THE important links of the New York-Buffalo New York State Thruway is the $60-million Hudson River Bridge between Tarrytown and South Nyack, N.Y., which is to be ready for use later this year. This important portion of this new highway comprises nineteen 250-foot units, such as those shown above, and a 1,212-foot main span and 602-foot side spans for a main-channel cantilever bridge. Spans for this bridge are being fabricated and erected by the American Bridge Division, United States Steel Company.

Structural shapes for this great new viaduct are being safeguarded against corrosion during transit and erection with Pittsburgh's new X-L-O Primer. This unusual product also reduces risk of surface failures that necessitate premature cleaning and painting. New X-L-O Primer also serves as an excellent foundation for final coats. It is available in combination of red lead and iron oxide, or can be supplied with 100% red lead if desired. You can get IRONHIDE or METALHIDE top coats in a range of colors suitable for field painting. For additional information write, phone or wire Pittsburgh Plate Glass Company, Industrial Sales Division, Pittsburgh, Pa., or the factory nearest you.

PITTSBURGH PLATE GLASS CO., Industrial Paint Division, Pittsburgh, Pa. Factories: Milwaukee, Wis.; Newark, N. J.; Springdale, Pa.; Atlanta, Ga.; Houston, Texas; Torrance, Calif.; Portland, Ore. Ditzler Color Division, Detroit, Michigan. Thresher Paint & Varnish Division, Dayton, Ohio. Forbes Finishes Division, Cleveland, Ohio. M. B. Suydam Division, Pittsburgh, Pa.

PITTSBURGH PAINTS

PAINTS • GLASS • CHEMICALS • BRUSHES • PLASTICS • FIBER GLASS

PITTSBURGH PLATE GLASS COMPANY

IN CANADA: CANADIAN PITTSBURGH INDUSTRIES LIMITED

BLOOD BROTHERS
Universal Joints mean DEPENDABILITY...

ON POWER WHEELBARROWS

Wherever you find 'em, you can count on Blood Brothers Universal Joints. On light or heavy equipment, they "get the power through" smoothly and dependably.

Look for them — on everything from power wheelbarrows to truck cranes. Where you see Blood Brothers Universals, you'll see a "good omen of good quality."

TRACTOR WINCHES

TRUCK CRANES

Universal Joints and Drive Line Assemblies

BLOOD BROTHERS
MACHINE DIVISION
ROCKWELL SPRING AND AXLE COMPANY
ALLEGAN, MICHIGAN

UNIVERSAL JOINTS AND DRIVE LINE ASSEMBLIES



DRILLED PILING and BELLED CAISSONS | *consultants on foundation problems*

ALSO FORMATION TEST HOLES, STARTER HOLES FOR PILE DRIVING, ELEVATOR SHAFTS, DE-WATERING AND UNDERPINNING . . .

CAISSON SIZES....16" to 84"
BELL SIZES.....2' to 15'
SHAFT DEPTHS.....to 200'

CASE FOUNDATION CO.
Rt. 1, Roselle, Ill.

Phone (Chicago) . . . . . Austin 7-3584
Write for Specifications

bid was adopted. That night Ivey found an error in the computation on which his bid was based in that subcontract bids aggregating $34,822 were not carried into or reckoned as a part of the bid figure. On the following day, Ivey sent the Authority a telegram, which was confirmed by letter, advising it of the error and the withdrawing of his bid. About three weeks later, the Public Housing Administration approved the acceptance of the Ivey bid and the Authority tendered him a written contract in the amount of his bid. Ivey declined to execute the contract and the Authority then entered into a contract with the next lower bidder. The Authority then brought an action against Ivey's surety to recover the sum of $14,267, being the difference between the two bids.

The Authority obtained a judgment at the trial but this judgment was reversed on appeal,[1] the appellate court holding that under Georgia law, where there is some reasonable excuse for an error made in calculating a bid, and the party receiving the bid knows of the mistake at the time the bid is accepted, the contractor may have the bid rescinded in equity.

(1) Peerless Casualty Co. v. Housing Authority, 228 F. 2nd 376, U. S. Court of Appeals, Dec. 16, 1955.

Uncertainty of Damages Is No Bar to Recovery

"Recovery of damages cannot be had if there is uncertainty as to whether the rights of the complainant have been invaded. But damages may be awarded where there is no uncertainty as to whether the rights of plaintiff were invaded, even though there may be some uncertainty respecting the amount of damages sustained. It is not essential that the amount be proved with absolute certainty. It is enough if the evidence adduced is sufficient to enable the court or jury, as the case may be, to make a fair and reasonable approximation."[1]

In most cases where actions are brought to recover damages for breach of construction contracts, especially in cases where the contractor has wrongfully been prevented from performance, it is necessary to prove damages by the testimony of experts.

[1] Stern v. Dunlap Company, 228 F. 2d 939, U. S. Court of Appeals, Dec. 27, 1955.

(These summaries of court decisions are prepared by I. Vernon Werbin, New York attorney and civil engineer.)

PERMANENT PROTECTION
for underground piping!

STILLWATER CERT-A-BAR* TUNNEL CONDUIT SYSTEM



New ceramic Cert-A-Bar Pipe Support Blocks eliminate the need for interior cast iron rests. The perforated block is laid as a structural support member at regular intervals, and the bars are simply inserted and locked in place.

THE vital consideration in selecting an underground conduit system is *permanent* protection . . . not for one year or five, *but for the life of the piping.* You get the best possible protection for your underground metal service piping with a Stillwater Conduit System of vitrified clay. It's chemically inert—can't rust, rot, corrode, or decay . . . ever. And it is manufactured in accordance with ASTM specification C-13-54, assuring proper strength and quality. Any combination of service piping can be protected. Conduit is available in a wide range of sizes, with a complete line of fittings and accessories, including alignment guides, lateral guides, and anchors. Any contractor's crew can handle the installation easily, or if you prefer, Stillwater Licensed Installers will assume the responsibility. The Cert-A-Bar Tunnel System can be installed with any of three suggested new waterproofing specifications—one for average conditions, one for intermittent ground water conditions, and a third for high water table conditions. It's the lowest-cost conduit per year of service that you can specify or install!



A few of the hundreds of possible combinations of piping for the Cert-A-Bar Tunnel System are shown at left. At right is the Lock-A-Bar Round System, used largely for short runs and replacement of other conduit.

LOCK-A-BAR*
ROUND SYSTEM



* T.M. Reg. App. For. Patents Pending.

WRITE FOR
new four-page file-size brochure, with full details

The Stillwater Clay Products Co.
STILLWATER CONDUIT DIVISION
3334A PROSPECT AVENUE, CLEVELAND 15, OHIO

STILLWATER CONDUIT SYSTEMS

SW-956-70



Lima Type 2400 shovel which incorporates a National Torque Converter. Here it is shown in use as a dragline with a 120-foot boom.

Where can you use NATIONAL Torque Converters?

National Torque Converters were developed specifically for the toughest, roughest industrial service. They are designed to provide a high degree of flexibility in operation of such equipment as power shovels, drag-lines, cranes, graders, shovel loaders, drilling rigs, mining and logging equipment.

In starting to move or lift a heavy load, a National Torque Converter acts as an automatic stepless transmission. Starts are smoother, easier . . . and acceleration of the load is faster. Result: more work per unit per operator per day.

Equipment is easier to operate and can be controlled more precisely. And there is less likelihood of overloading an engine or motor, or stalling it.

National Torque Converters are available in 6 basic hydraulic circuit sizes, each with a range of input ratings, permitting exact matching of torque converter to specific power-speed characteristics of a prime-mover. Precision fabrication of parts made to close tolerances assures uniform efficiency in operation, permitting standardization on your equipment.

Experienced National engineers are prepared to work with you on matching the right National Torque Converter to your requirements.

THE NATIONAL SUPPLY COMPANY

INDUSTRIAL PRODUCTS DIVISION

Two Gateway Center, Pittsburgh 22, Pa.

Pace-setters in the progress of industrial power transmission

New Bids on Chicago Toll Bridge are up 3.45%

Unit prices bid July 11 on the substructure of Calumet Skyway differ widely from rejected bids taken on April 30. Except for different piling, steel H-piles in the new and cast-in-place concrete in the rejected bids, all items and estimated quantities were identical. Both low bids on the substructure came from the same contractor. The superstructure contract was let on April 23. Chicago Department of Public Works, George L. DeMent, Commissioner, let both contracts for a total of $7,748,605.

This six-lane steel and reinforced concrete bridge over Calumet River in Chicago is 2,460 lin ft long. It includes three cantilever spans of 325 ft, 650 ft and 325 ft, approach deck-truss spans, steel towers and bents. The deck will be concrete with bituminous surfacing.

The $6,835,170 contract for the superstructure went to American Bridge Division of the U. S. Steel Corp. This was 10% above the engineer's estimate but 5.45% below the second low of four bids. The contract calls for 17.8 million lb of structural steel, cast and wrought iron drain pipe plus electrical facilities and navigation lights. Work under this contract must be completed in 575 calendar days, with $2,000 per day as bonus for earlier completion or as penalties for delays.

E. J. Albrecht Co., Chicago, will build the substructure for $913,435, 0.16% below the second low and 23.2% below the high seventh bid. This is 3.45% above the rejected low bid based on cast-in-place concrete piles. Completion time is 350 days with $275 penalty per day.

Excavation bid prices are higher, especially for piers which now cost $50 per cu yd compared to only $4 in April. Prices are up also for steel sheet piles 10%, carbon steel 6% and for stone fill 16.5%. But they are lower 12.5% to 54% for concrete in tremie seals, piers and fenders and 33.3% for structural steel erection. Reinforcing steel remains the same. The H-steel piling costs 17.85% more than the rejected cast-in-place concrete.

A threatened shortage of H-steel piles in April caused the city to revise plans in favor of cast-in-place concrete. However, when bids were received April 30, steel piles were available again, and bids were rejected to be advertised again for steel piles, July 11.

Chicago wage rates for unskilled labor were $2.575 until June when they were increased to $2.65. Wages for skilled labor jumped from $3.50 to $3.55 in June and to $3.592 in July.

Specifications require six sacks of cement per cu yd of class A, B, X and pavement concrete.

Bidders include:

Substructure with H-steel piles

1C E. J. Albrecht Co., Chicago, Ill $913,435
2 Industrial Construction Co, Chicago, Ill 914,887

Bids: 7-11-56 Items	Unit	Quantity	Unit Prices 1C	2
Excav, for struct	cy	2,310	$10.00	$11.00
for piers 5-5 & 6-6	cy	3,240	50.00	23.50
for pier fenders	cy	472	10.00	4.00
H-piles, steel, furn	lf	44,630	7.25	6.20
drive	lf	42,410	1.00	0.60
Conc, cl A, in tremie seals	cy	1,164	33.25	33.00
in piers	cy	4,344	35.00	64.20
in fenders	cy	750	25.00	30.00
Reinforcing steel	lb	323,000	0.15	0.16
Carbon steel, fabric	lb	43,800	0.35	0.33
Struct steel, erect	lb	43,800	0.10	0.13
Piles, stl sheet, for fenders	sf	18,720	2.75	2.95
Stone fill for fenders	t	3,572	7.00	9.70
Engineer's field office	ls	job	3,500	7,800

Time to complete: 350 calendar days
Liquidated damages: $375 per day

Substructure with cast-in-place concrete piles

1 E. J. Albrecht Co., Chicago, Ill $882,988
2 W. E. O'Neil Const. Co., Chicago & D. W. Winkelman Co., Inc., Syracuse, N. Y 990,088

Bids: 4-30-56 (rejected) Items	Unit	Quantity	Unit Prices 1	2
Excav for struct	cy	2,310	$8.00	$8.00
for piers 5-5 & 6-6	cy	3,240	4.00	28.00
for pier fenders	cy	472	4.00	10.00
Stl shells for cast-in-place conc piles furnish	lf	44,630	4.90	6.00
drive	lf	42,410	2.10	2.40
Conc, cl A, in tremie seals	cy	1,164	38.00	40.00
in piers	cy	4,344	76.00	60.00
in fenders	cy	750	35.00	50.00
Reinforcing steel	lb	323,000	0.15	0.15
Carbon steel, fabricated	lb	43,800	0.33	0.30
Struct steel, erect	lb	43,800	0.15	0.15
Piles, stl sheet, for fender	sf	18,720	2.80	3.80
Stone fill for fenders	t	3,572	6.00	7.00
Engineer's field office	ls	job	3,500	8,200

Time to complete: 350 calendar days
Liquidated damages: $375 per day

Superstructure

1C American Bridge Div. of U. S. Steel Corp., Chicago, Ill $6,835,170
2 Allied Structural Steel Co., Chicago 7,220,478

Bids: 4-23-56 Items	Unit	Quantity	Unit Prices 1C	2
Bit matl, prime coat	gal	1,940	$0.35	$1.00
Bit conc binder crse	t	1,170	12.00	15.00
surf crse	t	1,170	14.00	15.00
Conc for struct, cl A	cy	635	70.00	100.00
cl B	cy	4,228	138.00	135.00
lightweight	cy	988	165.00	150.00
Stl, reinf	lb	1,823M	0.1635	0.18
fabr carb. for deck truss				
simple spans	f	3,838M	0.1945	0.22
for cantilever spans	f	4,963M	0.2325	0.25
for towers & bents	f	1,449M	0.248	0.22
fabr silicon, for deck tr				
simple spans	f	1,441M	0.218	0.25
for towers & bents	f	476,000	0.278	0.25
fabr hi str low alloy,				
for cantilever spans	f	5,064M	0.2795	0.29
for towers & bents	f	530,000	0.299	0.27
struct, for cantil sp	a	10,027M	0.0795	0.085
for towers & bents	a	2,455M	0.435	0.07
for deck tr spans	a	5,323M	0.0615	0.095
Handrail, mat	lf	4,905	9.50	13.00
CIP, soil, drain, 6"	lf	90	25.00	30.00
Pipe, drain, wl, 8"	lf	3,292	25.50	25.00
10"	lf	830	32.00	35.00
Scupper, type A	ea	68	115.00	150.00
Elec facilities in struct	ls	job	47,000	50,000
Navigation lighting	ls	job	55,000	60,000

Time to complete: 575 calendar days
Liquidated damages: $2,000 per day
Bonus for earlier completion: $2,000 per day

You're Not Behind The Times IF You're Behind a

KERN INSTRUMENT

Obsolete surveying tools are time-consuming, wasteful ... out of step with modern construction equipment used on your jobs.



KERN THE MOST MODERN surveying instruments available. Down-to-fundamentals, functional design ... maximum operational efficiency and portability ... reliable precision results.

KNOWN THE WORLD OVER for accuracy, speed, reliability, economy.

- Minimum set-up time
- Fast, effortless, simple operation
- Readings at a glance
- Exceptional clarity and contrast of image

★

For Full Information Write for Brochure V554-1

PROMPT, RELIABLE SERVICE FACTORY TRAINED PERSONNEL

Kern and Only Kern Offers You The Latest Designs of

Dr. Henry WILD

Kern SWISS The FINEST in SURVEYING EQUIPMENT

KERN INSTRUMENTS INC.
120 Grand St., White Plains, N.Y

Delivering more than 53,000 cfm of air power

87 GYRO-FLO



Typical view of GYRO-FLO portable compressors at work on the Massachusetts Turnpike. Here, three 600 cfm units, operated near North Grafton, Mass., by the Gilbane Building Company, are supplying air power to five Ingersoll-Rand FM-3 Wagon Drills.

IR CONTRACTORS' COMBINATION

COMPRESSORS
ROCK DRILLS
AIR TOOLS
CARSET BITS
PUMPS

on the Massachusetts Turnpike

PORTABLE COMPRESSORS

help speed construction of this 123-mile cross-state expressway

STRETCHING from Boston on the east to a proposed connection with the New York State Thruway on the west, the Massachusetts Turnpike project is moving rapidly ahead to completion.

It's a big job—with the accent on speed. And 87 GYRO-FLO Portable Rotary Compressors—including 77 units each of 600 cfm capacity—are delivering a mighty large share of the air power required for the huge drilling and blasting work involved. Putting down the blast holes are a number of I-R Drillmaster and Quarrymaster superdrill rigs and many wagon drills, Jackhamers and other I-R rock drills.

In severe heavy-duty service such as this, the maintenance-free features of the GYRO-FLO portable cannot be over-emphasized. There are no pistons, rings, rods, or valves to wear out, adjust, or replace. This assures both simpler operation and greater dependability in performance. The GYRO-FLO provides cool, oil-free air, smoothly, without pulsation, at pressures that are automatically maintained between 100 and 110 psi under all load conditions.

Now available in 85, 125, 210, 315, 600 and 900 cfm sizes, GYRO-FLO compressors offer a new high in portable air-power efficiency. See your I-R distributor or branch office for full information on the compressor size that will meet your needs best.

Ingersoll-Rand

2-452 11 Broadway, New York 4, N.Y.

AN UNBEATABLE COMBINATION . . . GYRO-FLO COMPRESSORS AND I-R ROCK DRILLS

Materials and Labor Prices

Monthly Market Quotations by ENR Field Reporters

See following ENR issues for OTHER PRICES:

- Oct. 11 — Iron and Steel Products; Pipe
- Oct. 18 — Wood Products, Glass, Explosives, Chemicals
- Oct. 25 — Clay Products, Lime, Plaster Paint, Roofing
- Nov. 1 — Wage Rates, Building Board, Lath, Insulation

CEMENT, AGGREGATE, READY-MIXED CONCRETE — F. O. B. CITY

	PORTLAND CEMENT* Per bbl. C/L lots cash, dis. not deducted			SAND AND GRAVEL Per ton, carload lots			CRUSHED STONE Per ton, carload lots		CRUSHED SLAG Per ton, carload lots, f.o.b. plant		CONCRETE BLOCK 8x8x16-in.* truckload del.* per block		CONCRETE Ready Mixed 1:2:4 del. 50 cy & over
	Paper	Bulk	Mortar	Gravel, 1½ in.	Gravel, ¾ in.	Sand	1½ in.	¾ in.	1½ in.	¾ in.	Sand grav.	Lt. wgt. agg.	
Atlanta	$4.12a	$3.71a	$3.55	$2.75	$2.75	$2.60‡	$2.14	$2.24	$1.45	$1.65	$0.19	$	$13.75g
Baltimore	4.23c	3.82c	3.61c	2.80‡a	2.80‡a	2.25‡a	3.85‡a	2.90‡a	2.05‡a	2.00‡a	.18	.18a	12.75
Birmingham	3.73	3.90a/	.....	2.55a	2.55a	2.13a	2.75	2.75	1.55	1.65	.18	.18	12.30
Boston	4.91¼e	4.44a	4.71e	3.00a	3.00a	3.00a	1.65a	1.75a	.....	.....	.23	.275a	14.00h
Chicago	3.98a	3.57a	3.72	3.78‡b	3.78‡b	4.13‡b	3.95‡b	3.95‡b	2.25‡	2.25‡	.25	.25b	13.50
Cincinnati	4.22c	3.81c	3.60	2.10‡c	2.34‡c	2.34‡*	2.54‡c	3.54‡c	.....	.....	.205	.25a	12.40
Cleveland	N.A. in C.L.	3.86	.....	2.15ef	1.95f	1.65	4.30‡a	4.30‡a	3.30‡a	3.30‡*	.....	.23	16.15
Dallas	3.35a	2.95a	3.23	3.42	2.53	1.84	2.22	2.38	.....	.....	.11e	.2875	11.25
Denver	4.50a	4.09a	4.56	1.90	2.05	1.20	.....	.....	.....	.....	.22	.245a	10.70
Detroit	4.10a	3.45a•	3.73	4.25‡b	4.25‡b	4.00‡b	3.75‡	3.75‡	3.80‡	3.80‡	.23	.22a	14.20
Kansas City	4.30‡	4.10‡	4.10	.....	.....	1.70•‡a	2.00‡a	2.00‡a	.....	.....	.20a	.24c	13.50‡p
Los Angeles	5.12‡k	4.05‡k	5.60	2.41‡a	2.76‡a	2.41‡a	2.46‡a	.....	.....	.....	.145/m	.255m	12.95‡k
Minneapolis	4.40a	4.09a	3.99	2.70‡ag	2.70‡ag	1.60‡ag	3.25‡ag	3.25‡ag	.....	.....	.19	.....	14.00f
Montreal	3.11d	2.86d	3.59	1.95‡a	2.20‡a	2.25‡a	1.95‡i	2.20‡i	.....	.....	.20	.20a	10.80ek
New Orleans	3.85a	3.15a	3.48	2.44	2.44	2.00	.....	.....	1.45	1.65	.275	.....	13.65
New York	4.50a	4.15a	3.88	3.05‡k	3.05‡k	2.00‡k	2.90‡l	2.90‡l	.....	.....	.25	.30b	16.00an
Philadelphia	4.03/4.42‡a	3.72/4.09‡a	3.64/4.27‡	2.85‡ap	2.85‡ap	2.35‡ap	2.70‡	2.80‡	2.00	2.35	.22/.28	.....	13.20de
Pittsburgh	4.15a	3.76a	3.75	2.40‡	2.40‡	2.20‡	2.60‡	2.60‡	2.15	2.15	.25d	.31	14.00
St. Louis	3.88/4.18e	3.46/3.78e	3.71/4.00	3.25am	3.10am	2.40/2.10am	1.60j	1.70j	.....	.....	.23	.28c	12.90
San Francisco	3.70e	3.39e	.....	2.02	2.02	2.12	2.17	2.17	.....	.....	.24	.28d	12.50c
Seattle	4.30a	3.75a	.....	4.00‡bm	4.00‡bm	4.00‡bm	4.50‡bm	4.50‡bm	.....	.....	.26	.27	13.30j
Toronto	4.00	4.00	4.00	2.25‡	2.25‡	1.85‡	2.05	2.05	2.05	2.05	.35	.31e	14.55

‡ Delivered. * Prices incl. dealers discount except as noted.

CEMENT: •a Less 10¢ disc, 15 days. •b Less 2% disc, 15 days. •c Less 10¢ disc, 10 days. •d Truckload lots, deliv. 10¢ disc, 20 days. •e Truckload lots •f Fob mill, add $13.11 to $19.16 per car switching charges •g fob mill + freight •h LCL.

SAND GRAVEL, STONE & SLAG: •a Truck lots. •b Per cu. yd. •c 5 tons or more. •e ½". •f Pea gravel. •g Less 5% for cash. •h Less than 5 tons. •i Plus 5% mun. & prov. tax •j F.o.b. quarry. •k Barge lots and. •l F.o.b. snow Hudson river. •m Less 2% for cash. •n F.o.b. cars. •o 1-3 mi zone. •p Add 10¢ for ea. add'l mi zone. •r Revised

CONCRETE BLOCK: •a Cinder •b Waylite. •c Haydite. •d Celocrete •e 5¼ x 8 x 12 in. •f 8 x 4 x 16. •g F.o.b. truck at job. •i Less 2% for cash •j F.o.b. plant San Rafael. •m F.o.b. yard.

READY MIXED CONCRETE: •a 5 cu. yds. or over del. Man. •b 25 cu. yds or more •c 10-100 cy. brackets. •d 1-3 mi. zone. •e 2,000 lb comp. •f 2,500 lb. comp. •g Less 25¢ disc, 15 days. •h Less 50¢ for cash. •i 5% off for cash. •j 2% off for cash. •k Federal tax included. Add 5% mun. & prov. •l 1:2½:3½. •m F.o.b. yard •n Plus escalator clause. •o Add 15¢ for ea. add'l 3-mi zone. •p Correction; $1360 eff. Sept. 1

CASH DISCOUNTS CEMENT to Contractors: Truck delivery, 2% for cash on 10th of month; on carload deliveries, no trucking, same as dealer cash discount 10¢ per bbl. for payment within 15 days of date of invoice. Subject discount 10¢ per bbl. 20 days in Montreal.

CURRENT MAXIMUM PRICES AT CEMENT MILLS

Charge for bags not included. For paper bags add 40¢ per bbl., not refundable.

	Bulk		Bulk		Bulk		Bulk		Bulk
Richard City, Tenn	$3.15†	Buffington, Ind	$3.10†	Steelton, Minn	$3.20†	Muskegon, Mich	$3.15†	Toledo, O	$3.15†
Clinchfield, Ga	3.15†	Independence, Kan	2.95†	Leeds, Ala	3.00†	Saginaw, Mich	3.15†	Milwaukee, Wis	3.20†
Kingsport, Tenn	3.15†	Hannibal, Mo	3.10†	Duluth, Minn	3.20†	Wyandotte, Mich	3.15†	Green Bay, Wis	3.20†
West Des Moines, Iowa	3.20†	Northampton, Pa	3.20†	Hudson, N. Y	3.20†	Buffalo, N. Y	3.25†	Ironton, O	3.15†
Nazareth, Pa	3.20†	Universal, Pa	3.20†	Alpena, Mich	3.05†	Oswego, N. Y	3.30†	Montreal City	3.55†
Bath, Pa	3.20†	Waco, Tex. (+ 10¢ tax)	3.10†	Detroit, Mich	3.15†	Cleveland, O	3.20†	W. Winfield, Pa	3.20†
Lesley, Pa	3.20†	Giant, S. C	3.25†	Howes Cave, N. Y	3.20†	Alsen, N. Y	3.20†	Security, Md	3.20†

† *Prices to hold for Fourth quarter of 1956.*

PAVING BRICK, BLOCK, ASPHALT, ROAD OILS — F. O. B. CITY

	PAVING BRICK AND BLOCK			PAVING ASPHALT Per ton, less than 80 penetration		ASPHALT BINDERS—FLUXES Per gal., 80-300 penetration		CUTBACK ASPHALT MC per ton		ROAD OIL Per gal.	ASPHALT EMULSION RSI Per gal.	
	Granite Per M lots of 50,000 4x4x8 in.	Brick per M 3x4x8½ in. carload lots	Wood per sq. yd. 3½ in. 16-lb. treat	Tank car	Drums	Tank car	Drums	Tank car	Drums	Tank car	Tank car	Drums
Atlanta	.....	.....	.....	$27.60	$40.00	$0.15	$0.25	$0.114Pw	$0.276Pw	$0.15	$0.15	$0.25
Baltimore	180.00‡	.....	.....	23.00s	.....	.095s	0.185s	.10swE	.196swE	.10f	.105s	0.195s
Birmingham	.....	62.00s	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Boston	.....	.....	.....	22.00ap	35.00ap	22.00as	30.00as	.095swFw	.195•Fw	.095a	.095swG	.175swG
Chicago	180.00‡	85.00‡b	3.95/4.00‡j	21.85b	31.85b	20.85bs	30.85bs	.10swH	.18swH	.08b	.....	.....
Cincinnati	.....	.....	.....	23.00A	.....	23.00A	.....	.....	.....	.....	.....	.....
Cleveland	.....	83.00d	5.90g	23.00A	.....	23.00A	.....	1025AswF	.....	.....	.1028AG	.20AG
Dallas	0	40.00	0	25.20	44.29	.1066	.1894	28.55	50.08	.1030	.1066	.1894
Denver	.....	80.00	.....	.....	.....	.....	.....	.....	.....	.....	.....	.....
Detroit	.....	113.00	.....	20.65	.....	20.65s	.....	.1385swI	.....	.1026	.....	.25
Kansas City	0	0	0	7.00cl	.....	18.90s	.....	.095•swJ	.....	.075c	0.125	.....
Los Angeles	0	.....	0	18.50dmx	.....	18.50dsx	.....	20.00dx K	.....	19.00dx	.09j	.19j
Minneapolis	.....	.....	3.17A	26.50	.....	26.50	.....	0.115sw	.....	0.105	.1242	.....
Montreal	0	0	0	27.00n	39.50n	.135n	.190n	16.90swR	20.90swR	.132n	.197ns	.239ns
New Orleans	.....	.....	.....	17.90s	.....o	17.60es	.....o	.085sw	.....o	.085B	.09BL	.....
New York	.....	.....	3.70f	23.80gCD	44.56gD	23.80sCD	44.56sD	.1073swCDF	.1939swDF	.....	.1073CD	.1939D
Philadelphia	175/185	110/120	4.06	22.00	.....	22.00	.....	.095swF	.....	.095	.....	.....
Pittsburgh	165.00	48.00	4.60	27.00	38.00	.10	.21	27.00E	40.00E	.098	.11	.224
St. Louis	.....	.....	.....	20.63o	.....	.1764	.....	.0925fswN	.....	0.18	.105	.....
San Francisco	.....	70.00s	.....	20.80g	37.80g	20.80gks	37.80gks	21.84gN	39.00gN	21.25s•	.0925g	.1825•
Seattle	.....	.....	.....	24.50s	38.50s	18.75ks	.....	26.00K	.....	22.25ks	.0925s	.1025sr
Toronto	.....	.....	4.40	34.20	59.65	0.19	0.24	0.20sw	0.25sw	0.20	0.20	.24

‡ Delivered.

PAVING BRICK & BLOCK: •a CL. •b 3 x 4 x 8. •c 2½ x 8½ x 4. •d LCL, truck deliveries. •e Not used. •f 2" interior 8# treat. •g 3" •h 2" tr, 8# •i 3 x 3½ x 8½. •j 2½", 6 lb. tr.

ASPHALTS: •a Price at plant, Everett, Mass. •b F.o.b. refinery, Lockport, Ill. •c F.o.b. Sugar Creek, Mo. •d F.o.b. refinery, El Segunda. •e F.o.b. Baton Rouge. •f F.o.b. Hartford, Ill. •g F.o.b. Richmond, Calif. •h F.o.b. Martinez. •i F.o.b. refinery, Baltimore. •j F.o.b. refinery, Inglewood, Calif. •k 90-110 penetr. •l Less than 100 penetr. •m 40/50 penetr. •n Fed. tax included; add 5% for mun. & prov. •o Drums not avail. Shipped in steel bbl. •p 60/70 penetr. •q 40/85 penetr. •r In customer's drums. •s Shipped in drums, per drum. •t 85/200 penetr. •u Per 100 gal. •v Per ton. •w Per gal. •x Also tank trucks. •y F.o.b. Oakland •z F.o.b. Edmonds •A F.o.b. refinery, Cleveland. •B F.o.b. Destrehan, La. •C Bulk. •D Prices based on transporting to Manhattan via truck. •E RC. •F Also RC. •G Also MS, SS. •H RC 0-5 incl. •I MC 4. •J MC, RC .0675. •K MC 3, 4 & 5. •L MS. •M MC 1-5, RC 1-5, .088. •N MC 3. •O fob Roxanna, Ill •P F.o.b. refinery Savannah; $0.09/gal., tank cars; $0.29/gal., drums.

No job too little . . . or none too tough for BOWER STRAIGHT ROLLER BEARINGS

A complete line, a wide range of sizes to fit your specific needs

Square pegs weren't made for round holes. And aircraft bearings aren't built for farm equipment, either. That's why Bower designs a complete line of straight roller bearings—a line broad enough to meet any product requirement.

Jet planes break the sound barrier . . . need bearings that'll keep pace. So Bower aircraft bearings are engineered with exactness and precision to tolerances held to millionths of an inch. Bower tractor bearings, on the other hand, are built for ruggedness . . . to take heavy loads and real punishment, day after day, month after month.

Bower Roller Bearings are proved performers *in every field*, for *any* straight roller bearing application. From motors to earthmoving equipment, they're on the job—cutting maintenance and downtime, setting new standards of efficiency and economy. Get details on the *complete* line from a Bower engineer.



Tapered, Straight and Journal Roller Bearings for every field of transportation and industry

BOWER ROLLER BEARINGS

BOWER ROLLER BEARING DIVISION • FEDERAL-MOGUL-BOWER BEARINGS, INC., DETROIT 14, MICHIGAN

Bids Asked—Low Bidders—Contracts Awarded—First Section—

Compiled by Business News Department—Engineering News-Record, 330 W. 42nd St., New York 36, N. Y., ELSIE EAVES, Manager
J. A. MAHONEY, M. WETZEL, L. M. FELIX, M. E. SCIORRA, F. S. DEMBEK, Reports.
J. H. WEBBER, M. R. ROESSLER, E. R. HUBER, Statistics.

NEW ENGLAND

BUILDINGS—BA

▲ **Conn., Newtown**—THERAPY—BA 10/17—State P. Wks. Dpt., 165 Capitol Ave., Hartford, Proj. BI-A-109, occupational therapy bldg., Fairfield State Hospital. $1,350,000. Plans deposit $35. Fletcher-Thompson, Inc., 211 State St., Bridgeport, archt. CD 11/28/51.

BUILDINGS—SLC

▲ **Conn., Stamford**—SCHOOL, etc.—Diocese of Bridgeport, Chancery Office, 395 Washington Ave., Bridgeport, soon lets contract Catholic high school and convent, Newfield Ave. between Case and Vine Rds. $2,250,000. J. Gerald Phelan, 211 State St., Bridgeport, archt. Fletcher-Thompson, Inc., 211 State St., Bridgeport, engr. CD 8/27.

▲ **Mass., Cambridge** — SHOPPING CENTER — B & M Realty Co., 6 Beacon St., Boston, soon lets contract shopping center, Porter Square, Mass. Ave., White, Elm and Davenport Sts. $1,000,000. Herman L. Feer & William E. Nast, 27 School St., Boston, archts. Star Market Co., 283 Walnut St., Newton, lessee. CD 1/11.

BUILDINGS—LB & CA

▲ **Standard Constr. Co.**, 250 Builders Exchange Bldg., Minneapolis, Minn. LB **$1,721,400**. (6 bidders) general constr. two BUILDING addns., at Cambridge State School & Hospital, CAMBRIDGE, MASS. State, Dpt. Admin., 19 State Capitol, St. Paul, Minn. Bids Sept. 19. CD 8/27.
Healy Plumbing & Heating Co., 278 W. Kellogg Blvd., St. Paul, Minn. LB **$357,000**. (7 bidders) plumbing and heating work. (Cambridge, Mass.).

▲ **State, Dpt. Mental Health**, c/o Div. Bldg. Constr., 38 Chauncy St., Boston, Mass., rejected bids Aug. 17, M-716, admission treatment bldg., State Hospital, MEDFIELD, MASS. LB **$1,830,431**. Will re-advertise. CD 8/21, under LB.

Ernest F. Carlson, Inc., 1694 Main St., Springfield, Mass. LB **$571,473**, est. $525,000. State Aided 667-1 HOUSING for the elderly, St. James Ave. and Carew St., SPRINGFIELD, MASS. Springfield Housing Auth., 124 Putnam Circle, Springfield, Mass. CD 9/6, under LB.

MIDDLE ATLANTIC

HEAVY CONSTRUCTION—BA

NEW JERSEY-PENNSYLVANIA — BA 10/11 — Delaware River Port Auth. of the Commonwealth of Pennsylvania and the State of New Jersey, Administration Bldg., Camden, N. J.
Walt Whitman Bridge Contract No. P-13, installing new stacks on power plant of Publicker Industries, Inc., Delaware and Packer Ave., Phila., Pa. Plans deposit $10. Bids 9/13 rejected; adv. ENR 10/4. CD 8/28.

BUILDINGS—BA

▲ **Md., Baltimore**—HOSPITAL—BA 10/10—City, Bureau Bldg. Constr., 410 Municipal Bldg., Baltimore, Zone 2, brick, concrete, steel city hospital east wing alteration and new rear west wing. $1,000,000. Plans deposit $100. Lucius R. White Jr., 1009 N. Calvert St., Zone 2, archt. CD 5/21.

▲ **Md., Baltimore**—HOUSING—BA 10/17—U. S. Eng., 24 St. and Maryland Ave., Zone 18, construct and finance 198 armed services housing units, (Capehart), ENG-18-020-57-4, $2,000,000. Plans deposit $25. Lawrence A. Menefee, 803 Park Ave., Zone 1, archt.-engr. CD 8/16, under LB.

N. Y., Oswego—DORMITORY—BA 10/18—At office Dormitory Auth., 55 Grant Ave., Albany, Zone 6, dormitory at State University Teachers College, $800,000. Plans deposit $40 each, general constr., plumbing work electric and lighting fixtures, heating and ventilating Lorimer Rich & Assoc., 35 W. 53 St., New York, Zone 19, archts.

BUILDINGS—SLC

▲ **Del., Wilmington**—PARKING, etc.—Wilmington Parking Auth., City Hall Bldg., soon lets contract 4 story, bsmt., 361x179 ft. auto parking bldg. and 7 stores, 300 car capacity. $2,000,000. Whiteside Moeckel & Carbonett, 909 Tatnall St., archts. Louis H. Doane, Penna. R.R. Bldg., consult. engr.-archt.

HEAVY CONSTRUCTION—LB & CA

▲ **PENNSYLVANIA**—State Hy. Dpt., 506 N. Office Bldg., Harrisburg.
Marsolino Constr. Co., 309 Fayette National Bank Bldg., Uniontown, Pa. CA **$2,739,102**. constr. 38,908 ft. divided road crushed aggregate base with bit. surf. 28 ft. wide each side of concrete divisor, two 1-beam bridges, 2 prestressed precast rein.-conc. bridge, Somerset Twp. T. A. 31, Washington Co. CD 9/10, under LB.

† **Southern Commercial Constr. Co., Inc.**, 1341 Penn. Ave. S. E., Wash. 3, D. C. CA **$775,300**. technical training bldg., Andrews Air Force Base, ENG-57-9-(9), ANDREWS AIR FORCE BASE, MD. U. S. Eng., First and Douglas Sts. N. W., Wash. 25, D. C. Bids Aug. 15. CD 8/23.

▲ **Underground Constr. Co.**, 1900 Jefferson-Davis Hy., Box 2115, Potomac Station, Alexandria, Va., LB **$4,873,064**. (4 bidders) Section 4, East Branch, Piney Branch trunk sewer in Kansas Ave. and S St. from Varnum St. to Ingraham St. N. W., WASH., D. C. D. C. Govt., Dpt. Sanitary Eng., 499 Pennsylvania Ave. N. W., Wash., D. C. Bids Sept. 19. CD 8/9.

BUILDINGS—LB & CA

▲ **Suburban Park Homes**, c/o Herman H. York, archt., 90-04 161 St., Jamaica, N. Y. Owner Builds. **$1,300,000**. 65 HOUSES, Plainview Rd. south of Old Country Rd., PLAINVIEW, N. Y.

▲ **Whitehall Park Homes**, c/o Stanley J. Shaftel, archt., 166-21 90 Ave., Jamaica, N. Y. Owner Builds. **$2,300,000**. 60 HOUSES on 30 acre tract at Maplemoor Lane and North St., WHITE PLAINS, N. Y.

▲ **Arthur Kligman**, 1062 Kilsythe Rd., Elizabeth, N. J. Owner Builds, **$2,000,000**. 134 HOMES, Middle Rd., Kenwood Estates, Raritan Twp. CENTERVILLE, N. J. Erwin Gerber, 11 Commerce St., Newark, N. J., archt.

▲ **Lester M. Entein**, 10 S. Harrison St., East Orange, N. J., Owner Builds, **$2,000,000**. 89 HOMES, Starlight Dr. and Sussex Dr., Rainbow Acres, Morris Twp., MORRISTOWN, N. J. R. H. Fitzsimmons, 24 Gregory Rd., West Orange, N. J., and Percy Simon, 362 Cedar Lane, Teaneck, N. J., archts.

▲ **Bd. Freeholders, Burlington Co.**, Mount Holly, N. J., rejected bids Aug. 29, 4 story, 90,000 sq. ft. OFFICE, site imprvs., parking area, MOUNT HOLLY, N. J. LB **$1,242,249**. CD 9/6, under LB.

▲ **Joseph Pennella**, 35 Waldo Ave., Caldwell, N. J. Owner Builds, $3,000,000. 140 HOME development at Swimming River Acres, Hance Ave., NEW SHREWSBURY, N. J. Rudolph L. Nowak, 89 Central Ave., Clifton, N. J., archt.

John J. McDonnell, Inc., 69 and Market St., Upper Darby, Pa. CA **$500,000**. AUDITORIUM, CONVENT, RECTORY and SCHOOL for Queen of the Universe R. C. Church, LEVITTOWN, PA. R. C. Archdiocese of Phila., 225 N. 18 St., Phila., Pa. Gibson & Kline, 117 S. 17 St., Phila., Pa., engrs. CD 7/30.

Master Masons Constr. Co., 1619 W. Thompson St., Phila., Pa. CA **$500,000**. OFFICE, PHILA., PA. Penn Federal Savings & Loan Assoc., 1623 Walnut St., Phila., Pa. Robert E. McLaughlin, 1411 Walnut St., Phila., Pa., engr. CD 5/24.

▲ **Aetna-Standard Engineering Co.**, Frick Bldg., Pittsburgh, Pa. CA Total Est. $3,500,000 mechanical portions work for installing 12-stand continuous weld PIPE MILL, add 50,000 sq. ft. to west side of existing plant, for Mercer Pipe Division, SHARON, PA. Sawhill Tubular Products, Inc., Clark St., Sharon, Pa. Ramseyer & Miller, Inc., 11 W. 42 St., New York, N. Y. engrs.
Salem, Brosius Co., Arch St., Esten., Carnegie, Pa. CA Furance (Sharon, Pa.)

Windsor Constr. Co., 2401 Frederick Ave., Baltimore 23, Md. LB **$449,000**. concrete, steel, masonry South Shore Elementary SCHOOL, Crownsville, ANNAPOLIS, Md. Anne Arundel Co., Bd. Educ., Annapolis, Md. Bids Sept. 19. CD 9/12.

SOUTH

HEAVY CONSTRUCTION—BA

▲† **Georgia and South Carolina**—BA About 12/18—U. S. Eng., 200 East St. Julian St., Savannah, Ga., Hartwell Dam and appurtenance works, Hartwell Proj., Savannah River, near Hartwell, CIVENG-09-133-57-105. CD 9/19.

BUILDINGS—BA

▲ **La., Fort Polk**—HOUSING—BA 10/18—U. S. Eng., Box 1229, Galveston, Tex., construct and finance 2,000 housing units (Capehart) ENG-57-8. $15,000,000. CD 8/13, under LB.

HEAVY CONSTRUCTION—LB & CA

▲ **Burkholder & Burkholder**, 147 S. Adams St., Rockville, Md., LB **$1,511,440** Schedule A; LB **$92,250** Schedule B, landing strip extension, clearing, grading, drainage, Tri-State Airport, HUNTINGTON, W. VA. Tri-State Airport Auth., Box 1509 Huntington, W. Va. Bids Sept. 18. CD 9/6.

▲ **FLORIDA**—State Road Dpt., Tallahassee,
Fla.—**Cone Bros. Contg. Co.**, Box 1301, Tampa, Fla., LB **$1,093,813** (11 bidders) limerock base with b. conc. drainage structures 9.671 mi. SR 5, F-003-5 (3), Job 7002-277, Brevard Co.;
Fla.—**George G. Tapper Co.**, Port St. Jos., Fla., LB **$564,377** (4 bidders) shell stab. base with bit., sand-asph. hot mix surf., shell base wid'n. strips, 15.444 mi. SR 30 and 30-A, F-017-2 (9) and F-017-2 (10) (Jobs 4909-201, 4901-202, 5101-204 and 5107-202), Franklin and Gulf Counties;
Fla.—**J. W. Conner & Sons, Inc.**, Box 2522, Tampa, Fla. LB **$629,102**. (8 bidders) limerock base with b. conc. c. conc. small drainage structures 8.493 mi. SR 55 and 584, F-025-1 (10) Job 1515-208 and Job 1508-107, Pinellas Co.;
Fla.—**Marion Constr. Co.**, Box 577, Ocala, Fla., LB **$248,002** (3 bidders) limerock base with bit. b. conc. resurf. with b. conc., drainage structures 7.842 mi. SR 40, F-029-2 (3), Job 1114-201 and Job 1114-106, Lake Co.;
Fla.—**A. B. Covell**, Defuniak Springs, Fla., LB **$84,794** (6 bidders) sand-clay base with bit., small drainage structures 4.696 mi. SR S-191-A, S-408 (1), Job 5859-250, Santa Rosa Co.;
Fla.—**Jas. H. Craggs Constr. Co.**, Box 22, Gainesville, Fla., LB **$823,651** (4 bidders) limerock base, b. conc. surf. course, storm sewers, drainage structures 4.197 mi. SR 25, Jobs 2601-111 and 2602-115, Alachua Co.;
Fla.—**Jaxon Constr. Co.**, Box 2587, West Bay Annex, Jacksonville, Fla., LB **$214,492** (7 bidders) limerock base, surf. tr. storm sewers 2.915 mi. Job 3358-150, Lafayette Co.; limerock stab. base, surf. tr. 3.885 mi. Job 335-2150, SR S-53, Lafayette Co.;
Fla.—**W & M Constr., Inc.**, Williston, Fla., LB **$136,229** (5 bidders) stab. base, surf. 5.93 mi. SR S-337, Job 3458-175, Levy Co.;
Fla.—**J. D. Manly Constr. Co.**, Box 586, Leesburg, Fla., LB **$78,038** (8 bidders) limerock base, surf. 1.553 mi. Job 3659-150, SR S-352, Marion Co.;
Fla.—**Coggin & Deermont**, Chipley, Fla., LB **$137,251** (3 bidders) shell stab. base, surf. 1.83 mi. and 0.621 mi. respectively Job 4655-152, SR S-22A, and Job 4656-153, Bay Co.;
Fla.—**Dubose Constr. Co.**, Box 2592, Cloverland Sta., Montgomery, Ala., LB **$239,991** (12 bidders) concrete box culverts, 99 ft. concrete slab deck bridge, 4.621 mi. Job 5370-150, SR S-271, Jackson Co.;
Fla.—**Caddell & Jackson**, Box 2217, Jacksonville 3, Fla., LB **$133,465** (3 bidders) storm drainage Job 7267-153, Duval Co. Bids Sept. 20. CD 9/13.

▲† **McWilliams Dredging Co.**, Box 584, New Orleans, La. CA **$2,316,860**. Old River Outflow Control, channel dredging, consisting of 13,400,000 cu. yd., Concorida Parish, Inv. 57-31, LOUISIANA. U. S. Eng., foot of Prytania St., New Orleans, La. Bids Sept. 5, awarded Sept. 19. CD 9/18, under LB.

(Continued on page 115)

PROJECTS COVERED

By Size

Construction projects here reported cover the United States and Canada, are of these minimum sizes or larger: water supply, earthwork, waterways $44,000; other public works $73,000; industrial buildings $93,000; other buildings $344,000. Also Foreign projects of $100,000 and more in size of interest to American contractors.

By Regions & Classes of Construction

(In order of Listing)

BIDS ASKED
LOW BIDDERS
CONTRACTS AWARDED

New England
Middle Atlantic
South
Middle West
West of Mississippi
Far West

PROPOSED WORK

Water Supply
Sewers, Waste Disposal
Bridges
Streets & Roads
Earthwork, Waterways
Public Buildings
Mass Housing
Commercial Buildings
Industrial Buildings
Unclassified

In These Stages

PROPOSED WORK: Before and including appointment of engineers or architects.
BIDS ASKED: BA (new announcements only). For full calendar, see also preceding issues.
SOON LETS CONTRACT: SLC
LOW BIDDERS: LB On jobs below $500,000 in value all low bidder news will be the final reports published on the projects involved except where award is not made to the low bidder. In this case, a supplementary contract award report will be published.
CONTRACTS AWARDED: CA Except awards to low bidders previously reported in low bidder stage.
CD dates shown are of Construction Daily Issue in which last previous report was published.
OWNERS, ENGINEERS, ARCHITECTS, CONTRACTORS are invited to report their new jobs for listing in these reports when they meet or exceed the size minimums shown above. Address these news releases to J. A. Mahoney, REPORTS, ENGINEERING NEWS-RECORD, 330 W. 42 St., New York 36, N. Y.

Symbols and Abbreviations Include:

† Federal Government
▲ Project of $1,000,000 or over.
ENR Engineering News-Record
CD Construction Daily
For additional reports see Construction Daily.

The Problem:

To get water for irrigation from one side of the Rio Grande to the other

The Solution:

D. D. Skousen & Son, Albuquerque contractor, builds 1200-ft. siphon under the river with

BLAW-KNOX STEEL FORMS



• One of the most unusual projects in which Blaw-Knox Steel Forms have played an important part is the construction of a siphon under the Rio Grande near Albuquerque, New Mexico. The siphon is necessary to divert water from one side of the river to the other during the low water season, so that irrigation can be maintained on either side of the river. The 84" diameter concrete conduit, with 15" thick walls reinforced with steel, dips 40 ft. below the river bed at one point.

One of the most important aspects of this job was the time-pressure under which contractor D.D. Skousen & Son worked. The entire job had to be completed between November 15 and the annual Spring high water period. By the use of specially built Blaw-Knox Forms, Skousen was able to set and pour two 25-ft. sections of conduit per day. Working seven days a week, the project was completed without delay.

Siphons, Sewers, Big Dams, Bridges—whatever your concreting problem—solve it the low-cost way by taking advantage of Blaw-Knox forming experience. Bulletin 2430 contains special design suggestions and complete details about the Blaw-Knox Steel Form Consultation Service. Send for it *today*, while your next job is in the preliminary planning stage.

BLAW-KNOX COMPANY
STEEL FORMS DEPARTMENT
BLAW-KNOX EQUIPMENT DIVISION
P.O. BOX 1198 • PITTSBURGH 30, PA.
PHONE STERLING 1-2700

BLAW-KNOX STEEL FORMS
CONSULTATION SERVICE

50th Anniversary
BLAW-KNOX
1906 1956

©J. H. Baxter & Co. 1955

"Can't get this dad-burned sliver o' wood to burn," rumbled Paul Bunyan to Babe, the Blue Ox. A mountain top trembled and fell, damming up a river. "Babe, what the cuss do you suppose them Baxter folks done to this here piece o' plywood? ✻ She's dry—but she JEST DON'T BURN!"



BAXCO
FIRE-
RETARDANT
PLYWOOD
(Pressure treated with Protexol)

✻ Sorry, Paul, old timer—but even you couldn't get that wood to burn! It's BAXCO's new fire-resistant plywood, pressure treated with Protexol fire retardants and kiln dried after treatment. These are the most effective and widely approved fire retardants. Protexol-Pyresote affords termite and decay protection as well to the treated plywood. Protexol meets all important fire hazard and flame-spread classifications. BAXCO will quote promptly—send your inquiry today.

RECOMMENDED USES: *Partitions . . . Core Stock—Panels and doors . . . Interior trim and finish . . . Barns, stables and stalls . . . Railroad car flooring . . . Ship and Yacht interiors . . . Cabinet work.*

J. H. BAXTER & CO. *120 Montgomery Street, San Francisco 4, California*

(Continued from page 112)

▲ **W. R. Aldrich & Co.**, Box 147, Alexandria, La. LB $1,622,340. (6 bidders) Proj. No. 1 and 2, extens. to municipal sanitary system, ALEXANDRIA, LA. City Council, Alexandria, La. Bids Sept. 18. CD 9/10.

BUILDINGS—LB & CA

▲† **Wise Contg. Co.**, 8th and Grace Sts., Richmond, Va., CA $5,176,444. eight BARRACKS, ENG-44-110-56-35, FORT LEE, VA. U. S. Eng., foot of Front St., Norfolk 1, Va. Bids June 26, awarded Sept. 14. CD 7/9, under LB.

▲ **English Constr. Co.**, Altavista, Va., CA, $2,292,031. HIGH SCHOOL, HAMPTON, VA. City School Bd., Hampton, Va. Bids Aug. 30. CD 9/6, under LB.

† **Young Lumber Co.**, Beaufort, S. C., LB $717,996 (4 bidders) 50 enlisted men's QUARTERS, U. S. Naval Hospital, NBy 611, Spec. 611/56, CAMP LEJEUNE, N. C. P. Wks. Office, Fifth Naval Dist., U. S. Naval Base, Norfolk 11, Va. Bids Sept. 18. CD 9/5.

▲ **P. Smith Constr. Co.**, 310 N. Rome Ave., Tampa, Fla., CA, Total est. $4,000,000. general contract aeronautical navigation sys. mfg. PLANT, near Pinellas County Airport, ST. PETERSBURG, FLA. Minneapolis-Honeywell Regulator Co., 2743 Fourth Ave. South, Minneapolis, Minn., CD 8/2;
Huffman-Wolfe Southern Corp., 408 Sawtl. Ave. S. E., Atlanta, Ga., CA, mechanical work. (St. Petersburg, Fla.);
Bigby Electric Co., Inc., 208 Florida Ave., Tampa, Fla., CA, electrical work (St. Petersburg, Fla.).

MIDDLE WEST

BUILDINGS—BA

▲ **O., Maple Heights**—HIGH SCHOOL—BA 10/23—Maple Heights Bd. Educ., A. E. Hadfield, supt., 5500 Clement Dr., Junior High School. $1,200,000. Plans deposit $35. Outcalt, Guenther & Assoc., 13124 Shaker Square, Cleveland, Zone 20, archts. CD 8/8.

HEAVY CONSTRUCTION—LB & CA

▲ **OHIO**—State Hy. Dpt., Columbus,
O.—**John R. Jurgensen Co.**, Round Bottom Rd., Newtown, O. CA $709,363, est. $975,600, Type T-35, 16.202 mi. U. S. R. 62, Sects. 13.97, (0.00-1.19), (2.38), 0.00, Fayette, Madison and Pickaway Counties;
O.—**W. L. Johnson Constr. Co. & Assocs.**, P. O. Box 6668, Bexley Station, Columbus, O., CA $1,098,060, est. $1,329,300, Type T-35 on B-20 and structures 7.723 mi. S.R. 161, Sect. 5.12; SR 37, Sect. 15.09, Licking Co. Bids Sept. 5. CD 9/12, under LB.

† **Great Lakes Dredge & Dock Co.**, Williamson Bldg., Cleveland 14, O. CA $636,600, est. $575,000. maintenance dredging, Cuyahoga River, OHIO. U. S. Eng., Engineer Park, Buffalo 7, O. Bids Sept. 6, awarded Sept. 19. CD 9/11, under LB.

▲† **William A. Smith Contg. Co., Inc.**, 1401 Fairfax Trafficway, Kansas City, Mo., LB $1,759,815, est. $1,795,876 (8 bidders) relocating Baltimore & Ohio R.R. bridge superstructures and trackwork, Dillon Reservoir Proj., Licking River, CIVENG-46-022-57-6. OHIO. U. S. Eng., 237 Fourth Ave., Huntington, W. Va. Bids Sept. 20. CD 8/29.

▲† **Merritt-Chapman & Scott Corp.**, Standard Bldg., Cleveland, O., CA $3,358,344. Stage II, removal of 1,134,900 cu. yd. rock and earth from Ashtabula Harbor at Ashtabula, OHIO. U. S. Eng., Engineer Park, Buffalo 7, N. Y. Bids Sept. 20. CD 9/10, under LB.

▲ **John Klag & Assoc.**, 3838 Secor Rd., Toledo, O., LB $485,817, est. $495,054 (2 bidders), Sect. F, 10,185 ft. 8- to 21-in. sewers, 612 V.F. manholes, etc. Laskey Road Sanitary Sewer, TOLEDO, O. Comrs. Lucas Co., Court House, Toledo, O. Bids Sept. 14. CD 9/6.
Niezgoda Bros., 1219 Belmont St., Toledo, O. LB $627,679, est. $627,988 (2 bidders), Sect. G, 11,715 ft. 8- to 21-in. sewers, Douglas Rd. from Laskey Rd. to Michigan Line, 664 V.F. manholes, etc. Laskey Road Sanitary Sewer (Toledo, O.);
L. H. Halpin Co., 3173 Aldringham St., Toledo, O. LB $681,957, est. $682,893 (3 bidders) Sect. H, 13,513 ft. 8- to 21-in. sewers, Fairgreen Dr. and Secor Rd. from Laskey Rd. to Michitan line, 760 V.F. manholes, etc. Laskey Road Sanitary Sewer (Toledo, O.).

Thomas McQueen & Co., 1313 Circle St., Forest Park, Ill., CA, $849,576. Lake St. bridge (Northwest Expressway) across Chicago River, Halsted St. to Des Plaines, CHICAGO, ILL. City, City Hall, Chicago, Ill. Bids July 18. CD 7/25, under LB.

▲ **Santucci Constr. Co.**, 5035 Church St., Skokie, Ill., CA, $1,294,000. Beverly Calumet Sewerage System, Morgan St., CHICAGO, ILL. City, City Hall, Chicago, Ill. Bids Aug. 6. CD 8/31, under LB.

▲ **WISCONSIN**—State Hy. Comn., State Office Bldg., Madison,
Wis.—**Robert W. Ryan Co.**, Janesville, Wis., LB $311,829. Contract 1, ballast, base course 4.098 mi. S.T. Hy. 57 and 84, F-02-3 (13), F 02-3 (12) and S-0138 (1), Ozaukee Co.;
Wis.—**John F. Bloomer Co.**, 341 W. College Ave., Appleton, Wis., LB $385,710. Contracts 2 and 1, ballast, base course 5.473 mi. S.T. Hy. 57, Proj. F 02-3 (13) and F 02-3 (17), Ozaukee and Sheboygan Counties;
Wis.—**L. G. Arnold, Inc.**, 201½ N. Dewey St., Eau Claire, Wis., LB $107,322. Contract 1, grading base, structure 1.074 mi. S.T. Hy. 93, Proj. T 090 (5), Trempleau Co.;
Wis.—**James Peterson & Sons**, Medford, Wis. LB $181,975. Contract 1, grading, ballast, base 5.071 mi. S.T. Hy. 35, Proj. T 028-2 (2) St. Croix Co.;

Write today for the big, new, 40 page Acker Drill Supplies Catalog. It illustrates and describes over 150 drilling tools and accessories that will save you time and money on auger borings, core drilling and soil sampling.

Yes, send me the new Acker bulletin 50

Name_____ Title_____

Company_____

Street_____

City_____ State_____

ACKER DRILL CO., INC. 725 W. Lackawanna Avenue Scranton, Penna.

a complete line of Soil Sampling Tools, Diamond and Shot Core Drills, Drilling Accessories and Equipment

GRATING
Open steel flooring; welded or riveted pattern; fabricated in carbon or stainless steel, aluminum, monel and alloys.
when you specify KLEMP You Cut Construction and Maintenance Costs from the start!
HEXTEEL
A steel floor armor designed to prolong the life of floors 5 times! Installed in concrete or mastic on new or existing concrete or wood floors
KLEMP

KLEMP METAL GRATING CORPORATION
6601 South Melvina Avenue
Chicago 38, Illinois
POrtsmouth 7-6760

Write for your FREE "Data and Specification Manual" today!

ENR

KLEMP METAL GRATING CORPORATION
6601 South Melvina Avenue, Chicago 38, Ill

Gentlemen:
Kindly send me a copy of your "Data and Specification Manual."

Name_____
Firm_____
Address_____
City_____ Zone____ State_____
Phone_____

Onan Model 5DRP mounted on trailer with extension lighting standard.

Series 3DSP, 3,000 watts, single-cylinder.



Series 5DRP, 5,000 watts, two-cylinder, opposed.

Cut lighting costs with

Onan portable air-cooled Diesel Electric Plants

Make substantial savings on any job where extensive night-lighting is necessary by using Onan Diesel-driven electric plants. Diesel fuel has a big edge in economy and it's readily available on job sites. Onan Diesel plants are built for rugged service, with extra-large bearing surfaces, Stellite exhaust valve seats and other long life features. Engine and generator are direct-connected . . . no belts or couplings. Air-cooling eliminates trouble from freezing or leaking coolants. Compact and light weight. Put an Onan Diesel Plant on your next job and check the savings.

Diesel Plants—3,000 and 5,000 watts.
Gasoline Plants—500 to 50,000 watts.

Write for folder

Onan ELECTRIC PLANTS

D. W. ONAN & SONS INC.

2992 University Ave. S.E., Minneapolis 14, Minnesota

IF IT'S A

WET JOB

PLAY SAFE! ASK FOR A DEWATERING ANALYSIS BY

GRIFFIN

WELLPOINT CORP.

881 East 141st Street, New York 54, N. Y.
Hammond, Ind. Houston, Tex. Jacksonville, Fla.

You Get Things Done With Boardmaster Visual Control



- ☆ Gives Graphic Picture of Your Operations—Spotlighted by Color
- ☆ Facts at a Glance—Saves Time, Saves Money, Prevents Errors
- ☆ Simple to Operate—Type or Write on Cards, Snap in Grooves
- ☆ Ideal for Production, Traffic, Inventory, Scheduling, Sales, Etc.
- ☆ Made of Metal. Compact and Attractive. Over 100,000 in Use

Complete price **$49.50** including cards

FREE 24-PAGE BOOKLET NO. R-20 Without Obligation

Write for Your Copy Today

GRAPHIC SYSTEMS

55 West 42nd Street • New York 36, N. Y.

Wis.—**H. Turner & Son**, Boscobel, Wis., LB **$416,494** Contract 1, grading, ballast, base course 7.379 mi. S.T. Hy. 70, Proj. T 0283 (8) Price Co.;
Wis.—**O'Keefe Constr. Co.**, De Pere, Wis. LB **$249,212.** Contract 1, base, b. conc. 4.591 mi. S.T. Hys. 17 and 70, Proj. T 0287 (7) and T 024-1 (4) Vilas Co.;
Wis.—**Murphy Constr. Co.**, Black Creek, Wis. LB **$703,044.** Contract 1, base, c. conc. 2917 mi. S.T. Hy 96, Proj. T 0338 (2) and T 0338 (5), Outagamie Co.;
Wis.—**Highway Pavers, Inc.**, 1409 N. 27 St., Milwaukee, Wis. LB **$221,281.** Contract 1, c. conc. base, b. conc. 1.551 mi. U. S. Hy. 12 and S.T. Hys. 13 and 23, Proj. T 04-3 (9), Sauk Co. Bids Sept. 18. CD 8/31.

BUILDINGS—LB & CA

Fabe Constr. Co., 3700 Reading Rd., Cincinnati, O. CA Est. **$500,000.** two 4-story, 43x91 ft. APARTMENTS, off Columbia Parkway, CINCINNATI, O. Ohio River Vista Corp., 4320 Erie Ave., Cincinnati, O. Lee Firth, 3040 Madison Rd., Cincinnati, O. archt. Awarded Sept. 17.

Wigton Abbott Corp., 1225 South Ave., Plainfield, N. J. CA, **$550,000.** 2 story, brick dental and surgical supply PLANT, parking area, State Rd. 2, LA PORTE, IND. Austenal Laborat, Inc., 5932 S. Wentworth Ave., Chicago, Ill.

▲ **E. H. Marhoefer Jr. Co.**, 2424 N 25 Ave., Franklin Park, Ill., CA, **$4,259,524,** general contract, PSYCHIATRIC HOSPITAL and TRAINING HOSPITAL, 1607-59 W. Taylor St., West Side Medical Center, CHICAGO, ILL. State of Illinois, Capitol Bldg., Springfield, Ill. Bids Aug. 21. CD 8/29, under LB;
Gallagher & Speck, Inc., 546 Harrison St. Chicago, Ill., CA, **$1,272,922,** heating work (Chicago, Ill.);
Economy Plumbing & Heating Co., 1308 S. Pulaski Rd., Chicago, Ill., CA, **$748,400,** plumbing work (Chicago, Ill.);
Harmon Electric Co., 4511 Madison St., Chicago, Ill., CA, **$693,495,** electrical work (Chicago, Ill.);
Hanley & Co., 1503 Michigan Ave., Chicago, Ill., CA, **$370,500,** ventilating work (Chicago, Ill.).

Ockerlund Constr. Co., 4911 N. Lincoln Ave., Chicago, Ill. CA, **$750,000.** 1 story, 70,000 sq. ft. brick BAKERY addn., CHICAGO, ILL. Burny Bros. Bakeries, 4600 W. Chicago Ave., Chicago, Ill. Bids Aug. 20. CD 8/13.

Admiral Builders, 3349 Dempster St., Skokie, Ill. Own Forces. **$500,000.** 2 story, brick HOTEL, 9323 Waukegan Rd., MORTON GROVE, ILL. Ronald Simon, 1733 W. Pratt Blvd., Chicago, Ill., archt.

▲ **South Gate Corp.**, c/o Charles F. Agree, archt., 1140 Book Bldg., Detroit, Mich. Owner Builds. **$4,500,000.** Southgate SHOPPING CENTER, 40 stores Eureka and Trenton Rds., ECORSE, MICH. CD 9/8/52.

▲ **Krieghoff Co.**, 66661 French St., Detroit, Mich. CA, **$1,853,533,** general constr. Chalfonte JUNIOR HIGH SCHOOL, Grosse Pointe Farms, GROSSE POINTE, MICH. Bd. Educ., Grosse Pointe Pub. Schools, 390 St. Clair Ave., Grosse Pointe 30, Mich. CD 9/12, under LB.

▲ **Oakland Co.**, c/o Charles N. Agree, Inc., archt., 1140 Book Bldg., Detroit 26, Mich. Owner Builds. **$2,500,000.** SHOPPING CENTER, Greenfield and Oakwood Rds., MELVINDALE, MICH. CD 4/27.

WEST OF MISSISSIPPI

HEAVY CONSTRUCTION—BA

▲ **Mo., St. Louis**—LIGHTING AND UNDERGROUND CONDUIT—BA 10/23—City, Frank J. McDevitt, pres. Bd. P. Service, 304 City Hall, 12 Blvd. and Market St., Zone 3, installing mercury vapor lighting and underground conduit on Grand Blvd. and East Grand Ave. from Holly Hills Blvd. to North Broadway, 8.26 mi., $591,000; on Franklin Ave. and Easton Aves. from North Jefferson Ave. to western city limits, 4.85 mi., $355,000; on Gravois Ave., Grand to Chouteau Ave., 13 St., Cass Ave. to Mullanphy St. and parts of Mullanphy and Palm Sts., and north Florissant Ave., 4.09 mi., $382,000.

BUILDINGS—BA

▲ **Kan., Merriam**—SCHOOL—BA 10/11—Shawnee-Mission High School Dist., 7401 Johnson Dr., Merriam, Shawnee-Mission High School East at 75 and Mission Rd. $4,000,000. Neville, Sharp & Simon, 12 and Walnut St. Bldg., Kansas City, Mo., and Perkins & Will, 309 W. Jackson St., Chicago, Ill., archts. CD 3/21.

Mont., Billings—HOSPITAL—BA 10/17—Sisters of Charity, Leavenworth, 5 story St. Vincent Hospital addn. $850,000. Plans deposit $50, Cushing, Terrell & Assoc., 1333 N. 27 St., archts. CD 8/16.

▲ **Minn., Anoka**—FOOD SERVICE—BA 10/25—State, Dpt. Admin., P. T. Peterson, dir. Purchases, 19 State Capitol, St. Paul, 1 story, 169x261 ft., food service bldg., Anoka State Hospital. $1,150,000. Plans deposit $50. Lang & Raugland, 802 Wesley Temple Bldg., Minneapolis, archts. CD 7/29/55.

▲ **Tex., Texas City**—SHOPPING CENTER—Bids Asked—Harbor Village Development Corp., c/o J. C. French, Texas City, shopping center. $2,750,000. CD 9/19.

BUILDINGS—SLC

Colo., Denver—OFFICE—Colorado Hospital Service, 1653 Lawrence St., Denver, soon lets contract 3 story, full bsmnt., 37,200 sq. ft. Blue Cross-Blue Shield Office. $630,000. Baume & Pollivnich, 1225 Bannock St., engr. Bids 8/30 rejected, LB **$805,800.** CD 9/11, under LB.

Colo., Denver—STUDENT CENTER, etc.—Regis College, W. 50 Ave. and Lowell Blvd., soon let contract student center and dormitory, $900,000. Edwin A. Francis, 218 E. Speer Blvd., engr.-archt. CD 6/13/55.

(Continued on page 118)



THIS UNIQUE SYSTEM of moving complete sections of shoring to new pour areas is used by Wigton-Abbott Corp., Plainfield, N. J., to eliminate the job of disassembling and reassembling the shoring. Eleven "Trouble Saver" Sectional Shoring units, each covering 720 sq. ft., are pulled on wood sills by a hand winch. Each unit was slid three times for succeeding concrete pours during construction of the 189' x 231' Monsanto Chemical Co. warehouse, Kearney, N. J. Form work was "permanently" placed on those sections between drop heads.



WHEELED HYDRAULIC dolly is used to move four-frame unit of "Trouble Saver" Shoring to next pour. This system speeds operation for William J. Moran Co. on Emporium-Capwell Co. warehouse covering a city block in Oakland, California. 3,600 frames were used on this building.

Good Planning Cuts Shoring Costs

ONE OF THE MOST IMPORTANT advantages of modern sectional steel shoring is the fact that it can be planned on the drawing board. Load bearing strength can be accurately calculated, the number of units pre-determined and the whole installation laid out to assure greatest efficiency on the job.

It is during this planning period that the engineering ability, experience and imagination of The Patent Scaffolding Co. Inc., pays dividends to the contractor. For when a shoring installation is properly laid out on the drawing board, a lot of time, money and trouble are saved on the job.

First, PS Co. helps the contractor select the right kind of shoring by carefully studying the character of the job. Contractors planning with PS Co. have a choice of three types of steel shoring: "Trouble Saver"® Sectional, "TubeLox"® tube and coupler type Shoring and Burton's single post Shores. Once selected, the shoring is laid out to carry the desired loads with an adequate factor of safety and also to get maximum re-use from the number of units needed. Unique methods of rolling, sliding and lifting entire sections of sectional shoring from one pour area to another are often worked out at this stage too.

The complete story on PS Co. Shoring can be found in Bulletin PSS-33 "Modern Shoring for Concrete Construction". It's available at no obligation from the Patent Scaffolding Co., Inc.

To help you with your scaffolding and concrete shoring methods, PS offers a complete nation-wide engineering service available to you locally. See the Yellow Pages in your 'phone directory for the nearest Patent Scaffolding office or representative that **sells** and **rents** "Gold Medal" Scaffolds.



SAFE WORKING LOADS for "Trouble Saver" Sectional Steel Shoring vary according to spacing between 5'-wide frames, distance between rows, and position of stringers on frames. This prefabricated, engineered shoring will handle the heaviest loads and provides a clean, neat installation. It is easily adaptable to all types of construction: flat slab, slab with drop head, pan joist, poured arch and beam.

FOR GREATER SAFETY...EFFICIENCY...ECONOMY

THE PATENT SCAFFOLDING CO., Inc.

38-21 12th Street Dept. ENR Long Island City 1, N. Y.
West Coast: 6931 Stanford Ave., Los Angeles 1, Calif.
Branches in all principal cities
In Canada: 355 Dufferin St., Toronto

Ask For Catalog No. 100

Ask For Catalog No. 600

These CATALOGS are PLANNED TO HELP YOU PLAN

Ask For Catalog No. 300

Ask For Catalog No. 350



Ask For Catalog No. 650

Ask For Catalog No. 450

Ask For Catalog No. 500

Ask For Catalog No. 550

And for the framework of your structure, SPECIFY SHLAGRO STOCK Steel Products

Ask For Catalog No. 150

Ask For Catalog No. 700

IF IT'S MADE OF STEEL, CALL ON SHLAGRO

SHLAGRO STEEL PRODUCTS CORP.

8 WASHINGTON ST., SOMERVILLE, MASS.

(Continued from page 116)

HEAVY CONSTRUCTION—LB & CA

▲ **Barbarossa & Sons**, St. Cloud, Minn. and **Nodlund Constr. Co.**, Alexandria, Minn. CA **$1,286,190**. Sect. A of sanitary sewers Trunk Sewer Imprvt. No. 3, GOLDEN VALLEY, MINN. Village, R. W. Owens, clk., Golden Valley, Minn. CD 9/21, under LB.

† **Wm. G. Cook Constr. Co.**, Box 8466, Jackson, Miss. LB **$860,120**, est. $927,665. constr. Missouri River Agricultural Levee Unit. 497-L located along left bank of Missouri River in vicinity of Forest River, new channels for Cannon and Morehead Creeks, levees, appurtenant structures on both banks, ENG-57-9, MISSOURI. U. S. Eng., Federal Office Bldg., Kansas City, Mo. Bids Sept. 18. CD 8/23.

† **Kansas City Bridge Co.**, 928 Broadway, Kansas City, Mo. CA **$536,725**, est. $488,505. constr. and repair approx. 35,000 lin. ft. dike and revetments Kenmoor to Bean Lake Bends, Missouri River, Atchison, Atchison Co., KANSAS. U. S. Eng., 1800 Federal Office Bldg., 911 Walnut St., Kansas City 6, Mo. Bids Sept. 14, awarded Sept. 17. CD 8/24.

▲ **H. J. Hoppel**, 5501 E. Admiral St., Tulsa, Okla., CA **$1,112,440**, est. $1,150,000. Mingo Valley Sewage Treatment Plant, Contr. SA-55-6, TULSA, OKLA. City, City Hall, Tulsa, Okla. Bids Aug. 28, awarded Aug. 31. CD 9/19, under LB.

▲ **TEXAS**—State Hy. Comn., Austin,
Dean Wood Co., P.O. Box 330, New Braunfels, Tex., CA **$1,323,438**. flexible base, hot mix b. conc. 4.387 mi. Hy. US 81. Proj. 1 8 (14), Travis Co. Bids Sept. 12, awarded Sept. 19. CD 9/17, under LB.

▲ **TEXAS**—State Hy. Comn., Austin,
Tex.—**Heldenfels Bros.**, P.O. Box 1917, Corpus Christi, Tex., CA **$787,142**, flexible base, b. conc. 2.912 mi. Hy. SH 9 and US 77. Proj. F 657 (14), San Patricio and Nueces Counties;
Tex.—**Killian-House Co.**, 4600 Broadway, San Antonio, Tex. CA **$1,096,094**, flexible base, hot mix b. conc. 3.249 mi. Hy. Loop 13. Proj. F 1075 (6), Bexar Co.;
Tex.—**L. H. Lacy Co.**, 5630 Zale Blvd., Dallas, Tex. CA **$927,984**, grading, structures, G.C. and S.F. Ry. overpass, Hy. US 82. Proj. F 595 (17), F 549 (7), F. FG 549 (8), Cooke Co.;
Tex.—**Texas Bitulithic Co.**, P.O. Box 10365, Dallas, Tex. CA **$1,092,126**, flexible base, c. conc. pavement, hot mix b. conc. pavement 0.714 mi. Hy. Loop 217, Proj. U-1101 (6) and U-UG 1101 (7), Tarrant Co. Grand total $3,903,346. Bids Sept. 11, awarded Sept. 19. CD 9/17, under LB.

▲ **Spaw-Glass, Inc., 2411 Times Blvd., Houston, Tex.** CA **$1,196,838**, est. $1,150,000. 600 ft. open steel, concrete type wharf, HOUSTON, TEX. Port Comn., Wharf No. 3, Houston, Tex. Bids Aug. 30. CD 9/11, under LB.

† **Elton E. Peterson**, Casper, Wyo., CA **$631,442**, est. $700,000. grade, base, bit. surf. and bridge 1.7 mi. West Side Hy. Proj. 3A, Teton Co., WYOMING. Bureau P. Rds., Dpt. Commerce, Bldg. 40, Denver Federal Center, Denver, Colo. Bids Sept. 13, awarded Sept. 14. CD 9/19, under LB.

▲† **Robert E. McKee, General Contr., Inc.**, 211 Washington Ave., Santa Fe, N. M. CA **$14,370,000**. 328,750 sq. ft. Cadet Quarters Bldg., Air Force Academy, COLORADO SPRINGS, COLO. Dpt. Air Force, P.O. Box 1670, Colorado Springs, Colo. Bids Sept. 11, awarded Sept. 14. CD 9/14, under LB.

BUILDINGS—LB & CA

▲ **Watson Constr. Co.**, Baker Bldg., Minneapolis, Minn. LB Est. **$3,000,000**. (10 bidders) general constr., central WAREHOUSE and MANUFACTURING BLDG. west of Douglas Dr. and north of Minneapolis, Northfield & Southern Ry. tracks, GOLDEN VALLEY (P.O. MINNEAPOLIS), MINN. Minneapolis-Honeywell Regulator Co., 2753 Fourth Ave. S., Minneapolis, Minn. Bids Sept. 17. CD 8/21.

▲ **Johnson, Drake & Piper, Inc.**, Baker Bldg., Minneapolis, Minn. CA **$8,000,000**. PLANT, incl. three 1 story bldgs., administration, boiler installations, warehouse totaling 565,000 sq. ft., ROCHESTER, MINN. International Business Machines Corp., 590 Madison Ave., New York 22, N. Y. CD 3/19.

▲† **Parsons Constr. Co.**, 2512 Deer Park Blvd., Omaha, Neb., LB **$1,506,100** (3 bidders) construction only of COURT HOUSE and POST OFFICE, COUNCIL BLUFFS, IOWA. General Services Admin., P. Bldgs. Service, 2306 East Bannister Rd., Kansas City, Mo. Bids Sept. 18. CD 8/9;
Uteck Corp., Dallas, Tex., LB **$1,800,006**, construction and financing of court house and post office, (Council Bluffs, Iowa).

▲ **Weitz Co., Inc.**, 406 Fleming Bldg., Des Moines, Iowa. LB **$2,397,000**. general contract converting building into TECHNICAL SCHOOL, DES MOINES, IOWA. Bd. Educ., 629 3 St., Des Moines, Iowa. Bids Sept. 11. CD 8/3;
A. J. Allen Plumbing & Heating Co., 623 6 St., Des Moines, Iowa. LB **$663,400**. mechanical work (Des Moines, Iowa.).

▲ **Herdlein, Bumiller, Meyersieck**, 2604 Cherokee St., St. Louis 18, Mo. Owner Builds. **$1,000,000**. 140 addnl. RESIDENCES in Oak Crest subdivision, off Bid Bend Rd. via Spellman Dr., CRESTWOOD (ST. LOUIS 23 P.O.), MO.

Parsons Constr. Co., 2512 Deer Park Blvd., Omaha, Neb. CA **$952,450**. CA general constr., Creighton HIGH SCHOOL (Prep School) 72nd and Western Ave., OMAHA, NEB. Creighton University, 27 and Hamilton Sts., Omaha, Neb. Bids Sept. 11. CD 9/18, under LB.

▲ **Peter Kiewit Sons Co.**, 1024 Omaha Natl. Bank Bldg., Omaha, Neb., CA Est. **$30,000,000**. PLANT, near OMAHA, NEB. Western Electric Co., 195 Broadway, New York, N. Y.

▲ **Charles M. Dunning Co.**, 418 N. Hudson St., Oklahoma City 2, Okla. LB **$1,263,270**, est. $1,132,000. U. S. Grant HIGH SCHOOL addn., OKLAHOMA CITY, OKLA. Bd. Educ., 900 N. Klein St., Oklahoma City, Okla. Wright & Selby, Hightower Bldg., Oklahoma City, Okla., archts. CD 3/30.

Walter Kidde Constructors, Inc., 1205 Holman St., Houston, Tex. CA Est. **$500,000**. concrete atomic radiation LABORATORY to develop refinery processes, PONCA CITY, OKLA. Continental Oil Co., P.O. Box 2197, Houston, Tex. Walter Kidde Nuclear Laboratories, 975 Stewart Ave., Garden City, N. Y., engrs. CD 1/4/52.

Southwestern Constr. Co., Box 1204, Houston, Tex. CA **$534,430**. HOME FOR AGED, HOUSTON, TEX. Sisters of Charity of The Incarnate Word, 6510 Lawndale St., Houston, Tex. Bids Aug. 15. CD 8/8.

▲ **Marshall Constr. Co.**, 1811 Crawford St., Houston, Tex. CA **$962,490**, GEOLOGY BLDG.; CA **$1,009,000**, BIOLOGY BLDG., HOUSTON, TEX. Rice Institute, Main St., Houston, Tex. Bids Sept. 7. CD 9/19, under LB.

Doss-Blackmon Constr. Co., Mineral Wells, Tex. Own Forces. **$500,000**. 1 story, brick, tile, concrete SHOPPING CENTER, Hy. 183, HURST, TEX. CD 8/2.

D. W. Marshall Constr. Co., Box 32, Victoria, Tex. CA **$697,500**. CHURCH, SCHOOL, RECTORY, VICTORIA, TEX. Most Rev. Robert E. Luckey, Archbishop, 230 Dwyer Ave., San Antonio, Tex. Bids Sept. 5. CD 8/30.

▲ **Procon, Inc.**, 23 E. Jackson St., Chicago, Ill. CA Est. **$1,000,000**. modernize REFINERY, constr. CATALYTIC CRACKING UNIT, GREAT FALLS, MONT. Phillips Petroleum Co., north of Great Falls, Mont.

FAR WEST

HEAVY CONSTRUCTION—BA

▲ **Calif., Los Angeless**—BA 10/16—Bd. Supervs. Los Angeles Co., Hall of Records, bridge and imprv. Slauson Ave. over San Gabriel River, Santa Fe & Southern Pacific Rys. $1,000,000. Plans deposit $5.20.

BUILDINGS—SLC

▲ **Calif., Palo Alto**—MANUFACTURING—Varian Assoc., 611 Hanson Way, soon lets contract 2 story, 125,000 sq. ft. rein.-con. vacuum tube mfg. bldg., consist of research laboratories of cafeteria and processing and mfg. Stanford Industrial Tract, $1,500,000. Michael Gallis, 414 Mason St., San Francisco, archt. Isadore Thompson, 133 Kearny St., San Francisco, engr. CD 7/19.

HEAVY CONSTRUCTION—LB & CA

▲† **Strong Constr. Co.**, Springville, Utah, CA **$1,156,224**. first 5-mile section of 25-mi. access road to Glen Canyon Dam, site from Bitter Springs, ARIZONA, Bureau Reclamation, Dpt. Interior, Bldg. 1A, Denver Federal Center, Denver, Colo. CD 8/21, under LB.

▲ **Baker-Anderson Corp.**, 12420 S. Bloomfield Ave., Norwalk, Calif., CA **$4,930,000**. Section A and Section B, Unit II, North Central Outfall Sewer, LOS ANGELES, CALIF. Bd. P. Wks. City Hall, Los Angeles, Calif. Bids Sept. 12, awarded Sept. 14. CD 9/19, under LB.

Trepte Constr. Co., 2001 Kettner Blvd., San Diego, Calif., LB **$869,348**, Earl Thomas Reservoir, SAN DIEGO, CALIF. City, Water Dpt., Civic Center, 1600 Pacific Hy., San Diego, Calif. Bids Sept. 14. CD 8/13.

BUILDINGS—LB & CA

▲ **Pennsylvania Engineering Corp.**, New Castle, Pa., CA, 3rd installation top blown OXYGEN STEEL CONVERTERS, FONTANA, CALIF. Kaiser Engineers Div. of Henry J. Kaiser Co., 1924 Broadway, Oakland, Calif. CD 5/23/56, under CA.

St. John Constr. Co., 5121 W. Jefferson Blvd., Los Angeles, Calif., LB **$881,536**, est. $695,000 (4 bidders) GYMNASIUM, SWIMMING POOL, CLASSROOMS, PHYSICAL EDUCATION FACILITIES, at Inglewood High School, INGLEWOOD, CALIF. Inglewood Unified School Dist., 111 N. Grevillea Ave., Inglewood, Calif. Bids Sept. 17.

† **Hilp & Rhodes**, 918 Harrison St., San Francisco, Calif., CA **$772,626**. BUILDING 112 addn., incl. laboratory, office space, vault and library, LIVERMORE, CALIF. U. S. Atomic Energy Comn., Eng. Div., 518 17 St., Oakland, Calif. Awarded Sept. 14. CD 9/20, under LB.

Erickson Constr. Co., 1119 E. Bassettlaw Ave., North Sacramento, Calif., LB **$571,408**. general contract 1 story, 68,000 sq. ft., rein.-con. SHOPPING CENTER, El Camino and Watt Sts., SACRAMENTO, CALIF. El Camino Investment Co., c/o B. T. Lusk, 2450 Watt St., Sacramento, Calif. CD 9/6.

▲ **George A. Fuller Co.**, 3100 W. 8th St., Los Angeles, Calif., CA **$1,000,000**. rein.-con. WAREHOUSE and OFFICE, SOUTH SAN FRANCISCO, CALIF. Sperry & Hutchinson, c/o contractor. John S. Balles, Pier 5, San Francisco, Calif., archt. Awarded Sept. 14.

CANADA

HEAVY CONSTRUCTION—LB & CA

▲ **BRITISH COLUMBIA**—B. C. Govt., Parliament Bldgs., Victoria,
Ben Ginter Constr. Co. Ltd., Prince George, B. C., CA, **$1,956,176**. Proj. 778, 22.9 mi. Elko-Roosville Hy. Fernie Electoral District. CD 9/6, under LB.

(Continued on page 120)

an ACCO product

ACCO Registered* Dualoc Boom Cables



Why You Need ACCO Registered Boom Cables on Your Equipment:

...Every Buckled or Dropped Boom Results from Boom Cable Failure

Failure results from either overloading or fatigue. You can avoid overloading, but fatigue occurs every time vibration is stopped suddenly in a wire rope and it is practically impossible to measure how badly the rope is fatigued before failure occurs.

Because vibration in a boom cable occurs in more than one plane, any type of connector which can move in a single plane only, forces the wire rope to stop vibration in all other planes. Therefore, fatigue is set up.

ACCO Registered Boom Cable Connectors give movement in FOUR DIRECTIONS and thus change fatigue to wear, which can be measured easily.

To decrease the amount of this wear and to absorb any vibration which might not be handled by the connectors, ACCO Registered Boom Cables use the damping action of the patented DUALOC ending which absorbs the vibration over a considerable area without dangerously localized fatigue.

ONLY ACCO REGISTERED BOOM CABLES protect your investment through their following Exclusive Features:

1. FOUR-DIRECTIONAL MOVEMENT BY CONNECTORS
2. DUALOC VIBRATION DAMPING
3. WARRANTED STRENGTH
4. CERTIFIED PROOF TEST

*Trade Mark Registered

Write today for your copy of **Catalog DH-220** which includes complete information, including dimensions and breaking strengths on the complete line of ACCO-Registered DUALOC Boom Cable assemblies.

ACCO

AMERICAN CHAIN & CABLE

Wilkes-Barre, Pennsylvania

Wilkes-Barre, Pa., Atlanta, Chicago, Denver, Houston, Los Angeles, New York, Odessa, Tex., Philadelphia, Pittsburgh, Portland, Ore., San Francisco, Bridgeport, Conn.
In Canada: Dominion Chain Co., Ltd., Niagara Falls, Ont.

Better Value

WHY LUFKIN HI-LINE WOVEN
TAPES are more accurate


Percentage variation caused by moisture or temperature less than .000406.
Tensile strength 21,035 PSI.
Miracle epoxy resin coating, waterproof, corrosion and abrasion resistant.
Wool thread is one continuous piece of synthetic dimensionally stabilized yarn.
Abrasion resistant clear plastic.
Jet black protected markings.
34 warp threads of full length synthetic, dimensionally stabilized yarn.

Here's a woven tape that approaches the accuracy of metal tapes. Made from continuous, synthetic, dimensionally stabilized fibres that are non-conductive and have high dielectric strength. The thirty-four lengthwise warp strands are interwoven with endless cross strands so that there are no ends to fray on the edges. Attractive leather case with rust-resistant steel liner. 25 to 150 foot lengths.

BUY LUFKIN TAPES • RULES
PRECISION TOOLS
AT YOUR HARDWARE OR TOOL STORE

THE LUFKIN RULE CO., Saginaw Mich.
New York City Barrie, Ontario

416

FOR SAFE AND SPEEDY HOISTING

Heavy construction calls for heavy-duty blocks and MADESCO blocks combine the performance features developed through 30 years of specialized engineering for the construction field. Heavy steel shells and fittings, heavy iron or steel graphite-bronze, self lubricating sheaves are grooved to give you the maximum return for your rope investment. Sheaves equipped with bronze or anti-friction bearings for easy operation and long service.

Our special service departments will help you with their recommendations. Write for our catalog or consult your equipment dealer who can supply you with MADESCO products.



MADESCO BLOCKS
MADESCO TACKLE BLOCK CO.
EASTON, PA.
Engineered to Serve
Your Special Service Needs

FOUNDATION CONSTRUCTION
BY
McKINNEY
DRILLING CO.
BOX 190—LOGAN 4-8373
NACOGDOCHES, TEXAS
CAISSONS
DRILLED & UNDERREAMED
PIERS
WIRE OR PHONE FOR A QUOTATION ON YOUR NEXT FOUNDATION JOB
ANYWHERE IN THE WORLD
OFFICES IN
ATLANTA, GA. • PITTSBURGH, PA.

DUDGEON HYDRAULIC JACKS
SALES
RENTALS
• CAPACITY TO 600 TONS
FOR:
PILE TESTING
•
UNDER-PINNING
•
BRIDGES
•
PIPE PUSHING
•
SOIL TESTING

RICHARD DUDGEON INC.
799 BERGEN ST. • ST 9-4040 • BROOKLYN, N. Y.

(Continued from page 118)

▲ Canadian Vickers Ltd., Maissonneuve, Montreal, Que., CA, $4,269,825. mitre gates at locks of St. Lawrence Seaway, ONTARIO and QUEBEC. St. Lawrence Seaway Auth., No. 2 Temporary Bldg., Ottawa, Ont. Bids Sept. 18. CD 9/24, under LB.

BUILDINGS—LB & CA

▲ Thomas Fuller Constr. Ltd., 190 Richmond Rd., Ottawa, Ont. CA $6,330,765. (3 bidders) 8 story, bsmnt., I-shaped GEOLOGICAL BLDG., Booth St., OTTAWA, ONT. Dpt. P. Wks., Hunter Bldg., Ottawa, Ont. CD 9/26/55.

▲ Bouchard & Gravel, Inc., 150 rue Jean Dufresne, Jonquiere, Que. CA Est. $1,500,000. CLASSICAL COLLEGE, JONQUIERE, QUE. Les Peres Oblats de Marie, Immaculee, Bursar's Office, 3456 Avenue, Ontario, Montreal, Que. Dauphinais & Belanger, 582 Blvd. Lamarche E., Chicoutimi, Que., engrs. CD 1/6/56.

▲ A. N. Bail Co. Ltd., 1440 St. Catherine St. W., Montreal, Que. CA $1,760,000. (9 bidders) 2 story, bsmnt., rein.-con. fdn. pulp and paper RESEARCH INSTITUTE of Canada, at Pointe Claire, MONTREAL, QUE. Dpt. P. Wks., Hunter Bldg., Ottawa, Ont. Bids Aug. 22, awarded Sept. 14. CD 8/28, under LB.

▲ Leon M. Adler, 2200 Ward Ave., Montreal, Que. CA $1,000,000. SHOPPING CENTER, northern outskirts of town, ST. JEROME, QUE. Maxwell Cummings Sons, 1390 Sherbrooke St. E., Montreal, Que. Bids Aug. 15, awarded Sept. 14. CD 9/6, under LB.

LATIN AMERICA

BUILDINGS—LB & CA

▲ Black, Sivalls & Bryson, Inc., 7500 E. 12 St., Kansas City, Mo., CA Est. $2,200,000. eleven SILOS and WAREHOUSES, BRAZIL. Govt. of Brazil, Rio de Janeiro, Brazil.

PROPOSED PROJECTS

WATER SUPPLY

▲ N. Y., Rome—City Council, City Hall, constr. fish creek storage dam, $1,500,000. Malcolm Pirnie, Engr., 25 W. 43rd St., New York, N. Y., consult. engrs.

Okla., Clinton—City, City Hall, voted bonds, well water supply. $680,000. C. H. Guerusey & Co., 2701 N. Oklahoma City, consult. engr. CD 8/29.

SEWERS, WASTE DISPOSAL

Conn., Plainville—Town, Town Hall, sanitary sewers Mountain View Area, $521,000.

▲ Mich., Pontiac—City, City Hall, sewage treatment plant consisting of new humus tank at existing site, interceptor to new 4.5 m.g.d. activated sludge plant 1 mi. downstream, sludge dewatering and incineration at new plant for all sludge produced, $2,650,000, Jones, Henry & Williams, Security Bldg., Toledo, O., engrs.

▲ N. Y., Paris—Town, Town Hall, sewerage sys. $1,037,000. William S. Lozier, 10 Gibbs St., consult. engr. CD 9/5/55.

▲ N. Y., Syracuse—Bd. Supervs. Onandaga Co. Lakeland trunk sewer, Nine-Mile Creek pumping station and force mains. $1,700,000.

▲ O., Ashland—City, City Hall, imprv. sewerage sys., $1,020,000. CD 1/12.

Va., Falls Church—City, 151 E. Broad St., bond election Nov. 6, street and storm drainage work. $595,000. CD 1/15/53.

▲ Wash., Ronald—Ronald Sewer Dist., Richmond Highlands, Ronald, bond election Nov. 6, sewerage sys. and treatment facilities, $5,300,000. Hill & Ingman, 1728 E. Madison St., Seattle, consult. engrs. CD 11/20/51.

BRIDGES

▲ Conn., Hartford—Hartford Bridge Auth., 11 Asylum St., Hartford,
Glastonbury—Wethersfield bridge approach from Relocated Rte. 9, Wethersfield, approaches from Glastonbury Expressway to east end of bridge with overpasses at Naubuc Ave. and Main St., Glastonbury, $5,844,000. Edward B. Burdick, c/o owner, engr. DeLeuw, Cather & Brill, Inc., 202 E. 44 St., New York, N. Y., consult. engr. CD 4/11.

▲ OKLAHOMA—State Hy. Dpt., Capitol, Oklahoma City, Zone 5,
Johnston Co.—2 concrete, steel bridges, U. S. Hy. 70, $190,000.
Leflore Co.—3 concrete, steel bridges, U. S. Hy. 270, Stapp, $200,000.
Mayes Co.—3 concrete, steel bridges, SH Hy. 82, Locust Grove, $250,000.
McCurtain Co.—3 concrete, steel bridges, SH Hy. 21, Broken Bow, $190,000.
Stephens Co.—2 concrete, steel bridges, SH Hy. 7, in Marlow, $200,000.
Tulsa Co.—3 concrete, steel bridges, U. S. Hy. 66, Tulsa, $560,000.
1 concrete, steel bridge, U. S. Hy. 66, Tulsa, $100,000. G. H. Bittle, c/o owner, engr.

▲ Virginia — Chesapeake Bay Ferry District Comn., Box 120, Norfolk,
24 mi. low level bridges and tunnel across Chesapeake Bay, from eastern shore to Norfolk, $100,000,000. Sverdrup & Parcel Eng. Co., 1134 Locust St., St. Louis, Mo. will make feasibility study. Wilbur S.

(Continued on page 122)

Contractor Takes Tractair to Church and Solves Unusual Construction Problem

Remodeling of this large church depended on plenty of air power.

"Inside" job was confined, crowded, with poor footing.

Here's how a construction firm found the answer with a Le Roi Tractair.

A self-propelled Le Roi Tractair compressor went to church recently to help the Caspian Construction Company of Caspian, Michigan with an unusual air-power problem.

The job was different and difficult. St. Mary's Church in Wausau, Wisconsin was to be remodeled inside, from the ground up. Plenty of air power was needed to work essential tools. But long hose wouldn't work because of friction loss and danger of abrasion from debris. Not even small trucks could get inside the building.

To solve the problem, a Le Roi 125 Tractair, capable of working in crowded conditions . . . maneuvering in tight corners . . . "stepping" through loose, deep sand, was driven into the church. In this way continuous air power was provided for the job, without tying up additional equipment or men.

The contractor states, "The Tractair was a life-saver on this job, due to the fact that it is so mobile. It did a very fine job for us and served all of our needs at a very low cost of operation."

Ready to work at any job. Tractair, a combination 42-hp wheel tractor and 125-cfm air compressor, can be equipped with a variety of drilling attachments, front-end loader, backhoe, rotary sweeper, backfill blade, and operates Le-Roi-Cleveland air tools — rock drills, pavement breakers, clay spades, backfill tampers.

On this job, the Tractair functioned as a specialized tool providing a complete answer to the need for dependable air power inside the church. The Le Roi Tractair was also used outside the church to break concrete, along with a portable Le Roi Airmaster compressor. On many jobs, the Tractair can replace a truck-towed compressor with a 50% saving in equipment costs and manpower — and unlimited savings in time.



(Above) Work outside St. Mary's church in Wausau, Wis., used Le Roi Tractair and Le Roi Airmaster compressor to break concrete.

(Below) Inside church, Le Roi Tractair provided air power when and where needed because it can move about in confined, crowded places.



Le Roi Division of Westinghouse Air Brake Co., Milwaukee 1, Wisconsin also manufactures portable and stationary air compressors, air tools, and engines. Write today for information about any of these products.

T-45

BOOM LINES by VULCAN
NEVER SAW A JOB MOVE ALONG LIKE THIS ONE... WHO'S THE GUY ON THAT PILE DRIVER ?
DON'T GIVE ME THE CREDIT...IT'S THAT NEW SUPER-VULCAN THE BOSS ORDERED!
TALK ABOUT POWER! WE'VE GOT ABOUT THE LONGEST, TOUGHEST PILES TO DRIVE AND THE SUPER-VULCAN JUST TAKES 'EM IN STRIDE!
RIGHT! THE SIMPLE RUGGED DESIGN OF SUPER-VULCAN MEANS MORE WORK, FEWER REPAIRS!
Bulletin 70-C illustrates all available sizes, including the world's largest 200-C. Specifications and duplicate parts are included. Write for your copy to:
VULCAN IRON WORKS INC.
327 NORTH BELL AVENUE • CHICAGO 12, ILLINOIS

Dependable
POWER!
Machinery, now in use in many of the nation's finest movable bridges, is renowned for its dependable power, long life and
is another member of the famous Earle line of precision-made products that include gears and speed reducers.
CATALOGS AVAILABLE
EARLE Gear and Machine Co.
4707 Stenton Avenue
Philadelphia 44, Pa.

TEST BORINGS
for
• COAL
• MINERALS
• DAMS & BRIDGES
• BUILDINGS
We bore into the Earth
PENNSYLVANIA Drilling CO.
DRILLING CONTRACTORS AND MFRS.
PITTSBURGH 20, PA.

GUNITE
Since 1915
CONCRETE
SAND AND CEMENT
"Placed by Air"
We have the equipment, personnel and experience to complete any and all GUNITE work regardless of size or location.
Send for specifications and bulletins
GUNITE CONCRETE & CONST. CO.
1301 WOODSWETHER RD., KANSAS CITY 5, MO.
2016 WEST WALNUT, CHICAGO 12, ILLINOIS
3206 HOUSTON, HOUSTON 9, TEXAS
3545 LINDELL BLVD., ST. LOUIS 3, MO.
Milwaukee and Twin Cities · Denver · New Orleans

(Continued on Page 120)

Smith & Assocs., 265 Church St., New Haven, Conn., is making traffic study.

STREETS AND ROADS

▲ **CONNECTICUT**—State Hy. Dpt., 165 Capitol Ave., Hartford,

North Canaan—relocation of Route U. S. 7 incl. 5 grade separations, structures and interchange with Route U. S. 44, $2,000,000. Philip W. Genoves & Assocs., 249 Elm St., New Haven, consult. engrs. CD 5/25.

▲ **Mich., Mount Clemens**—Bd. Road Comrs. Macomb Co., Roy Conner, chn., County Bldg., improve 250 mi. county roads, $12,000,000.

▲ **Mo., St. Louis County**—St. Louis County, Luman F. Matthews, co. superv., Court House, Clayton, Zone 5, opening and constr. of Innerbelt Hy. across county, total distance 18 mi. $16,000,000. Sverdrup & Parcel Eng. Co., 1134 Locust St., St. Louis, Zone 1, consult. engr.

▲ **OKLAHOMA**—State Hy. Dpt., Capitol, Oklahoma City, Zone 5,

Atoka Co.—surf. 1.21 mi. Hy. 69, Atoka, $355,000.
Beckham Co.—grade, drainage 2.87 mi. US Hy. 66, Sayre, $800,000.
grade, drainage 5.5 mi. SH Hy. 6, Retrop, $160,000.
Bryan Co.—grade, drainage 6.8 mi. SH Hy. 70, Roberta, $126,000.
Caddo Co.—grade, drainage 4 mi. SH Hy. 8, Anadarko, $200,000.
Cimarron Co.—grade, drainage 11.57 mi. SH Hy. 114, Boise City, $500,000.
Creek Co.—grade, drainage 5.22 mi. SH Hy. 77, Shamrock, $125,000.
Dewey Co.—surf. 5 mi. SH Hy. 47, Butler, $142,000.
surf. 5 mi. SH Hy. 47, Alado, $133,000.
Garfield Co.—surf. 4 mi. US Hy. 64, Enid, $495,000.
Grady Co.—surf. 2.43 mi. US 81, Chickasha, $1,346,000.
surf. 1.11 mi. US Hy. 81, Chickasha, $400,000.
Grant Co.—grade, drainage 6.45 mi. SH Hy. 11, Medford, $60,000.
Greer Co.—surf. 8.74 mi. SH Hy. 6, Granite, $160,000.
Johnston Co.—grade, drainage 5.3 mi. US Hy. 70, $200,000.
Latimer Co.—grade, drainage 5.81 mi. SH Hy. 2, Wilburton, $500,000.
Leflore Co.—grade, drainage 10.2 mi. US Hy. 270, Stapp, $323,000.
Love Co.—surf. 1 mi. Hy. US 77, Marietta, $65,000.
Mayes Co.—grade, drainage 5.5 mi. SH Hy. 82, Locust Grove, $200,000.
McAlester Co.—surf. 4.96 mi. US Hy. 69, Pittsburgh, $948,000.
McClain Co.—grade, drainage 6.7 mi. US Hy. 77, Gooldsby, $750,000.
McCurtain Co.—grade, drainage 5.88 mi. SH Hy. 21, Broken Bow, $150,000.
Nowata Co.—surf. 1.6 mi. US 60, Nowata, $75,000.
grade, drainage 2.61 mi. SH Hy. 10, Lenapah, $65,000.
Okfuskee Co.—grade, drainage 8.01 mi. US Hy. 62, Paden, $230,000.
Oklahoma Co.—grade, drainage 3.5 mi. US Hy. 77, Oklahoma City, $1,320,000.
surf. 0.44 mi. US Hy. 270, Oklahoma City, $60,000.
grade, drainage 2.79 mi. US Hy. 77, Oklahoma City, $1,300,000.
Pontotoc Co.—surf. 1.16 mi. SH Hy. 3, Ada, $375,000.
Sequoyah Co.—surf. 3.9 mi. Hy. US 64, Moffett, $487,000.
Stephens Co.—grade, drainage 1.76 mi. SH Hy. 7, Marlow, $150,000.
Tulsa Co.—grade, drainage 3.25 mi. US Hy. 66, Tulsa, $200,000. G. H. Bittle, c/o owner, engr.

▲ **TENNESSEE**—State Hy. Dpt., Nashville,

Shelby Co.—15 mi. expressways, Memphis. $15,000,000. Harland Bartholomew & Assocs., 317 N. 11 St., St. Louis 1, Mo., preliminary engineering report and plans and spec. Clark & Daily, Urbana, Ill., structural design of bridges.

▲ **Tex., Angleton**—Brazoria Co., new road constr. and paving, $700,000; road maintenance, repairing, reconstr., $800,000. CD 6/26.

▲ **Tex., Orange**—Comrs. Orange Co., Court House, Orange, public roads sys. approx. 160 mi. $4,940,000. CD 6/20.

▲† **WASHINGTON**—U. S. Forest Service, Dpt. Agriculture, 14 St. and Independence Ave. S. W., Wash. 25, D. C.

Skamania Co.—timber access road to upper Lewis River area of Gifford Pinchot National Forest $4,000,000.

▲ **Alta., Edmonton**—City, City Hall, ratepayers vote Oct. 17 on bylaw paving on arterial and residential streets. $1,000,000.

Alta., Edmonton—City, City Hall, ratepayers vote Oct. 17 on bylaw for asphalt surfacing on gravel roads. $950,000.

EARTHWORK, WATERWAYS

▲† **Kentucky**—U. S. Eng., 830 W. Broadway, Louisville, Lock and Dam 41 Ohio River, lock 110x1,200 ft., all equip., incl. cofferdam, 2,000 ft. long, 55 ft. high, Louisville, Jefferson Co. $10,000,000. ($800,000 appropriated). To go ahead in 1957.

▲† **Kentucky**—U. S. Eng., 830 W. Broadway, Louisville, dam and spillway, rolled earth, fill dam with upstream rock protection, stream diversion, road over spillway and dam, Rough River Reservoir, Breckenridge and Grayson Counties. $1,000,000 appropriated.

▲† **Oregon**—U. S. Eng., 628 Pittock Block, Portland, The Dalles Dam. $42,457,000 appropriated.

(Continued on page 125)

American Industry rests on
RAYMOND FOUNDATIONS



Tidewater Oil Co.'s cat cracker and deethanizer, Avon Flying A Refinery, Associated, Cal.

take OIL for example

OIL . . . the lifeblood of our civilization is continually expanding to fulfill tomorrow's demands today. And helping the industry to meet this dynamic expansion has been Raymond's role for over 50 years. You'll find Raymond foundations supporting off-shore structures, tanker wharves, "cat crackers" and storage tanks just about everywhere oil is drilled, pumped and refined. In all, Raymond has handled 189 contracts for domestic oil companies in the past 10 years alone. This includes projects for such leaders in the field as Standard Oil, Gulf, Tidewater and Sinclair, to mention a few. If you have a foundation or heavy construction problem, whatever industry you're in, we'll be happy to discuss it with you.

RAYMOND AT HOME AND ABROAD

IN THIS COUNTRY
Foundations . . . Marine Structures . . .
Heavy Construction . . . Soil Investigations.

OUTSIDE THE UNITED STATES
Complete services for all types of construction.

RAYMOND
CONCRETE PILE CO.
140 Cedar St. • New York 6, N. Y.
Branch offices in Principal Cities of the United States, Canada, Central and South America

advanced design in turbochargers means... air-cooling!

AiResearch turbochargers possess this all-important characteristic

There's little quarrel in the diesel industry about the air-cooling principle being highly-desirable in a turbocharger. It eliminates the need for extra plumbing on installation, puts no additional burden on an engine's cooling system and makes for a lighter, smaller unit in relation to output.

AiResearch turbochargers now available have been designed on this principle — which promises to be universal in the future. In addition, our units increase power up to 100% depending on design and application of your engine, cut fuel costs, reduce noise and decrease or eliminate smoking. The removable rotating assembly makes them easier to maintain than other turbochargers.

We invite your inquiry on how you can improve the performance of your diesels by the application of our turbochargers.

BASIC SPECIFICATIONS FOR AIRESEARCH TURBOCHARGERS

MODEL	T-10	T-14	T-15	T-30-2	T-30-6
Diameter — in. nom.	9	11.5	15.25	15.25	16
Length — in.	9	14.12	16.75	17.25	21.75
Weight — lb.	40	95	125	135	195
Output — lb/min. (Standard Conditions)	25-40	35-65	35-65	70-95	115-175

THE GARRETT CORPORATION

AiResearch Industrial Division

9225 South Aviation Blvd., Los Angeles 45, California

DESIGNERS AND MANUFACTURERS OF TURBOCHARGERS AND SPECIALIZED INDUSTRIAL PRODUCTS

(Continued from page 122)

▲† **Texas**—U. S. Eng., Box 1600, Fort Worth, embankment for Canyon Reservoir, in Comal Co., Guadalupe River; outlet works for Canyon Dam. $1,600,000 appropriated. Bids about December, 1956. CD 6/9/44.

AIRPORTS

▲† **Ariz., Phoenix**—RUNWAY—U. S. Eng., 751 S. Figueroa St., Los Angeles, Calif., plans by Johannessen & Girand, 415 Central and Washington Bldg., 3,500 ft. concrete southwest end of the northernmost parallel NE-SW Runways exten., Luke Air Force Base. $2,000,000. CD 8/23.

† **Me., Brunswick**—QUARTERS—First Naval Dist., 495 Summer St., Boston, Mass., plans by Coletti Bros., 687 Boylston St., Boston Mass. bachelor officers' quarters and mews, U. S. Naval Air Station, (Second increment), $600,000. CD 8/27.

Mo., Springfield—AIRPORT—City, Bart Avery, Mgr., City Hall, $300,000 bond election Nov. 27, administration bldg. and extensions and imprvs. at municipal airport. $600,000. CD 8/16/55.

▲ **O., Columbus**—AIRPORT—City, City Hall, voted bonds Sept. 14, Port Columbus Airport. $3,975,000. CD 7/6.

▲† **O., Dayton**—APRON PARKING, etc.—U. S. Eng., 830 W. Broadway, Louisville, Ky., apron parking, 63,750 sq. yds. rein.-con paving, b. conc. stabilized shoulders, storm drainage, fuel dispensing sys., water hydrant lighting, $1,000,000; 1 story, 9,200 sq. ft. Test A/C and Missile, $1,000,000; 3,500 sq. ft. permanent, non-combustible high altitude training bldg. addn., etc., $70,000; two 3 story 25,900 sq. ft. each permanent non combustible airmens dormitories, central heating plant, site preparation, utilities, $1,000,000, Bids October 1956; 3 story, 89,000 sq. ft. 196-men officers quarters, incl. walks, parking area, utilities, steam heating from central distr. sys., Approx. $1,000,000, Bids November 1956 at Wright-Patterson Air Force Base. CD 8/22.

▲ **Utah, Salt Lake City**—ADMINISTRATION BLDG.—Salt Lake City Corp., City-County Bldg., plans by Ashton, Evans & Brazier, 24 S. W. Temple St., administration bldg. at airport. $3,750,000. Bids in 1958. CD 8/26/54.

PUBLIC BUILDINGS

Ala., Chatom—HOUSING—Chatom Housing Auth., Chatom, plans by T. Cooper Van Antwerp, 354 St. Francis St., Mobile, 44 housing units. $550,000. G. B. Espy, Jr., Jackson, Ala., engr. CD 4/1/52.

Ala., Enterprise—HOUSING UNITS—Enterprise Housing Auth., Enterprise, plans by Bond & Bond, Carter Hill Rd., Montgomery, 50 housing units. $500,000. Bids in March.

Ala., Fayette—HOSPITAL—Fayette County Hospital, Fayette, plans by Charles H. McCauley, Jackson Bldg., Birmingham, Zone 3, county hospital addn. $535,000. CD 8/16.

▲† **Ala., Tuskegee**—HOSPITAL, etc.—Veterans Admin., Munitions Bldg., Wash., D. C., buildings and utilities addns., alterations. $1,500,000-$2,000,000.

Ala., Wetumpka—HOSPITAL—Elmore County Hospital, Wetumpka, plans by Charles H. McCauley, Jackson Bldg., Birmingham, county hospital addn. $500,000.

▲ **Calif., Hawthorne**—SCHOOL—Centinela Valley Union High School Dist., 365 Hawthorne Way, plans by Llewelling & Moody, 766 Colorado Blvd., Los Angeles, Hawthorne High School addns. $1,266,463.

Calif., West Covina—SCHOOL—Bd. Educ., West Covina School Dist., West Covina, plans by Llewelling & Moody, 766 Colorado Blvd., Los Angeles, Monte Vista School. $555,000. CD 2/10.

▲ **Conn., New Haven**—COURT HOUSE—Comrs. New Haven Co., 121 Elm St., plans by Carl R. Blanchard, Jr., 111 Whitney Ave., court house. $4,400,000. Douglas Orr, 111 Whitney Ave., consult. engr. CD 2/3.

Conn., Somers—SCHOOL—Town, Town Hall, plans by Olson, Miller & Assocs., 742 Asylum Ave., Hartford, high school, $700,000. John P. Legnos, 30 Gillett St., Hartford, consult. engr., CD 9/7.

▲ **D. C., Wash.**—SCHOOLS—Bd. Educ., Franklin School, Wash., D. C., Kenilworth Elementary School addn. $700,000; elementary school, 56 and Eades Sts. N.E., $818,000; elementary school, 6 and Chesapeake Sts. N.W. $857,000; elementary school, Texas Ave. and Burns St. S.E., $875,000; senior high school in Congress Heights, $4,000,000.

Fla., Fort Lauderdale — HOUSING — Fort Lauderdale Housing Auth. plans by Robert G. Jabelka, 701 E. Broward St., 84 housing units, $800,000.

▲ **Fla., Miami**—HOME and HOSPITAL—Comrs. Dade Co., Court House, $1,500,000 bond election Nov. 6, Dade County Home and Hospital expansion program in Kendall. CD 12/2/55.

▲ **Fla., Miami**—HOSPITAL EXPANSION—Comrs. Dade Co., Court House, $7,500,000 bond election Nov. 6. Jackson Memorial Hospital expansion program. CD 12/2/55.

▲ **Fla., Miami**—HOUSING—Miami Housing Auth., J. T. Knight, exec. dir., 327 N.W. 62 St., plans by Steward & Skinner, 223 S.E. 1 St., 148-unit housing N.W. 83 to 85 Sts. from 5 Ave. to 6 Court. Over $2,000,000.

▲ **Fla., Palatka** — SCHOOL — Putnam County School Bldg., Palatka, plans by Goin & Moore, 518 N.E. 4 Ave., Gainesville, Junior High School. $1,500,000.

▲ **Fla., Plant City** — HOUSING — Plant City Housing Auth. plans by Thomas V. Talley, Lakeland, 200 housing units. $1,856,000.

Provide for Fastenings to Concrete Before Concrete is Cast

PD Concrete Inserts Save Time and Labor



Fastenings to pre-cast, pre-stressed concrete products can be made by simply spacing PD Inserts at predetermined positions in wood or steel forms. STAR PD Concrete Inserts are precision die-cast of non-corrosive zinc alloy having holding powers from 100 to 2,500 lbs.

Write Dept ER-8 for details



① A—Fasten Plug to wood form with nail. or B—Bolt concrete insert to steel form.

② PD Concrete Insert set in concrete — will not move if concrete is vibrated.

③ A—Strip wood form in conventional way. Remove Plug and re-use. or B—Remove bolt and strip steel form.

★STAR PRECISION DEVICES, INC.

Dept. ER-10, 142 Liberty Street
New York 6, N. Y.

MANITOWOC
SECTIONAL BARGES



A 50 x 30 foot four-section barge suitable for 2 yard dragline or clam.

● For floating lift cranes, clams, draglines and other contrators' equipment. Easily assembled or knocked down for transporting by rail or highway.

Length of sections from 20 to 50 feet in 10-foot increments.

Spuds, deck fittings, loading ramps and other accessories available.

Loading a 40-foot section for highway transportation.

MANITOWOC SHIPBUILDING, INC.
MANITOWOC, WISCONSIN

Write for information and prices.

Sold direct or through Manitowoc Engineering Corp. distributors.

Do You Have This PIPE PROTECTION PROBLEM?

Underground piping must be protected against destructive forces of corrosive soils and electrolytic conditions. Normally, coal tar coating as called for in AWWA specifications C-203 and C-204 would be hot-applied at a coating mill. However, there are times when the volume of pipe involved or the distance of a coating mill make this impractical from a time and cost standpoint.

You'll find the ANSWER with TAPECOAT *. . . the Quality Coal Tar Coating in Tape Form*

TAPECOAT is the widely-accepted alternate material that is equivalent to mill-applied hot coal tar protection. With this easy-to-use material, protection can be applied in the field by your own men, because technical know-how, kettles and special crews are not required. You save time and money while providing the long-life protection called for.

TAPECOAT is easily applied, using a torch to soften or bleed the pitch which gives both bond and protection. Available in widths from 2" to 24", it is spirally wrapped or cigarette wrapped around pipe, pipe joints, couplings, conduit, cable, and insulated piping.



Write for illustrated brochure.

The TAPECOAT® *Company*

Originators of Coal Tar Coating in Tape Form

1551 Lyons Street
Evanston, Illinois

▲ **Ga., Augusta**—HOUSING—Augusta Housing Auth., Augusta, plans by Scroggs & Ewing, 1331 Greene St., and F. Arthur Hazard, Marion Bldg., Proj. GA 1-5, 250 dwelling units, exceeds $2,000,000; plans by Eve & Stulb, Masonic Bldg., and Kuhlke & Wade, 122 8th St., Proj. GA 1-6, 275 dwelling units, exceeds $2,000,000. Bids February or March 1957.

Ga., Camilla—HOUSING—Camilla Housing Auth., plans by C. A. Smith, Loew's Grand Theatre Bldg., Atlanta, 50 housing units. $595,000. Robert O. Bradley Co., Albany, consult. engrs. CD 7/28/52.

Ga., Summerville—HOUSING—Summerville Housing Auth., plans by Ayers & Godwin, Bona Allen Bldg., Atlanta, 80 housing units, $800,000. CD 1/13/53.

▲† **Idaho, Arco** — BUILDING, etc. — Atomic Energy Comn., Idaho Operations Office, Idaho Falls, buildings, utilities and other facilities in SPERT III area of National Reactor Testing Station, incl. 59x80 ft. structural steel reactor building. $1,000,000. Bids this month. CD 3/24/49.

▲ **Ill., Belleville** — COUNTY NURSING HOME — Bd. Supervs. St. Clair Co., Court House, $1,100,000 bond election Nov. 6, 1 story multi-winged of 140 bed capacity, brick, rein.-con. county nursing home, Collinsville Ave., Swansea, adjacent to Belleville. CD 8/31/54.

▲ **Ill., Oak Park**—SCHOOLS—Bd. Educ. Dist. 200, East Ave. and Ontario St., plans by Shaw Metz & Dolio, 208 S. LaSalle St., Chicago, 3 story, bsmt. brick, stone. Oak Park and River Forest High School addn., East Ave. and Ontario St. $1,500,000.

▲ **Ill., Rockford**—SCHOOLS—City, Bd. Educ., Rockford, plans by Raymond A. Orput, 311 Empire Bldg., Hubbard & Hyland, Gas-Electric Bldg., Bradley & Bradley, Rockford Trust Bldg., and Gilbert A. Johnson, American National Bank Bldg., all Rockford, 4 schools. $8,389,900. CD 11/9/53.

▲ **Ind., Hobart**—SCHOOL—Hobart Twp. School, c/o Ivan Miesger, trustee, 3452 Central Ave., East Gary, plans by Wildermuth & Wildermuth, 527 Broadway, Gary, 2 story, brick Hobart Twp. High School, Huber Blvd. $1,500,000.

▲ **Ind., Sellersburg**—SCHOOL—Silver Creek Twp. Headquarters, Sellersburg, plans by Walker, Applegate, Oaks & Ritz, 218 Elsby Bldg., Spring and Pearl Sts., New Albany, high school, incl. academic bldg., recreation bldg., auditorium. $1,700,000.

Ind., Terre Haute—ELEMENTARY SCHOOL—Bd. School Trustees, 667 Walnut St., plans by Miller, Vrydagh & Miller, 200 Opera House Bldg., 1 story, 80x326 ft., masonry, structural steel elementary school. $500,000. Homer A. Howe, 204 Opera House Bldg., structural engr.

▲ **Ky., Louisville**—SCHOOLS—Jefferson Co. Bd. Educ., 618 W. Jefferson St., plans by Hartstern, Louis & Henry, McDowell Bldg., brick, concrete Kerrick Elementary School, Pleasure Ridge Park, near Louisville, $500,000; brick, rein.-con. Junior High School, Goldsmith Lane, $600,000; elementary school on Herr's Lane near Westport Rd., $600,000; elementary school, Brown's Lane, $500,000, E. R. Ronald & Assoc., 554 S. Third St., consult. engrs.

▲ **Ky., Mount Sterling** — HOUSING — Mount Sterling Housing Auth. plans by James Allan Clarke, P.O. 230, 82 housing units. $1,018,000. CD 2/6/56.

Ky., Winchester—HOUSING—Winchester Housing Auth. plans by James A. Clarke, Winchester, 54 housing units. $500,000.

La., Bogalusa—HOUSING—Housing Auth., Morton Roche, chn., 1420 N. Columbia Rd., plans by A. Hays Town, 310 Triad Bldg., Baton Rouge, 80 housing units, La 24-5. $710,000.

La., Bunkie—HOUSING—Housing Auth., C. J. Dupont, exec. dir., Town Hall, plans by C. Scott Yeager & Assoc., P. O. Box 1105, Alexandria, 50 housing units, La 62-1, $396,200.

▲ **La., Lake Charles**—HOUSING—Lake Charles Housing Auth., Alva P. Fritch, exec. dir., P. O. Box 934, plans by Matkin & Fritch, 4101 San Jacinto at Cleburne, Houston 4, Tex., 142 housing units, Proj. LA-4-3, $1,338,200; 50 housing units, Proj. LA-4-6, $460,700; 100 housing units, Proj. LA-4-5, $947,000; 108 housing units, Proj. LA-4-4, $1,005,800.

▲ **La., Ruston**—HOUSING—Ruston Housing Auth., plans by L. Milton King, Kusin Bldg., Monroe, 100 brick veneer duplex housing units. $1,135,000.

La., Shreveport—HOUSING—Housing Auth., F. D. Jackson, exec. dir. 2725 Southern Ave., plans by Neild-Somedahl Assoc., 960 Jackson St., 250 housing units, La 2-3, $2,290,000; 250 housing units, $2,000,000. CD 4/8/52.

▲ **Md., Hagerstown**—HOUSING—Hagerstown Housing Auth., plans by Chapman & Lefler, 27 N. Jonathan St., 155 housing units. $1,000,000. CD 2/2/51.

† **Md., Laurel**—WAREHOUSE—D. C. Govt., Director Bldgs. & Grounds, 499 Pa. Ave. N. W., Wash., D. C., warehouse at Childrens Center, $781,000.

▲ **Mass., Swampscott** — SCHOOL — Town, Town Hall, plans by Warren H. Ashley, 967 Farmington Ave., West Hartford, Conn., Junior Senior High School. $1,000,000.

Mich., Adrian—SCHOOL—Madison Township Bd. Educ., Archie Wallace, supt., voted $750,000 bonds Sept 10, high school. CD 9/17.

▲ **Mich., Bloomfield Hills**—SCHOOLS—Bd. Educ., Bloomfield Hills School Dist., elementary school, $600,000; Junior High School, $750,000.

Mich., Hamtramck—CITY HALL—City Council, City Hall, City Hall. $900,000. I. M. Kopkowski, City Hall, city engr.

Mich., Hastings—HOSPITAL—Bd. Supervs. Barry Co., County bldg., 104 bed capacity hospital. $700,000.

Mich., Adrian—SCHOOL—Madison School Dist. School Bd., high school. $750,000.

▲ **Minn., Eveleth**—HOSPITAL—City, E. I. Talpale, clk. J. Primozich, chn. Hospital Bd., voted $500,000 bonds Sept. 11, $1,000,000. CD 9/7.

Minn., Minneapolis—SCHOOL—Bd. Educ., H. Held, archt.-engr., 807 N.E. Broadway, plans by Shiffet, Backstrom & Assoc., 17 W. Franklin Ave., Shingle Creek Elementary School along Shingle Creek between 50 and 51 Aves. North and between Newton and Penn Aves. $700,000. (Correction-architects). CD 2/3.

Minn., Mountain Lake—SCHOOL—Bd. Educ., J. F. Eitzen, clk., $955,000 bond election Jan. 25, grade school, $525,000; gymnasium-auditorium addn. to high school, $350,000; other imprvs. Pass, Rockey & Church, Mankato, archts. CD 12/22.

Miss., Aberdeen — HOUSING — Aberdeen Housing Auth. plans by John L. Turner & Assoc., Box 1348, Jackson, 88 housing units, $800,000.

Mo., Springfield — FIRE STATION, etc.—City, Bart Avery, mgr., City Hall, $635,000 bond election Nov. 27, 4 fire stations and police station.

▲ **Nev., Reno**—HOUSING—Reno Housing Auth. plans by John Crider, 225 W. 1st St., 150 housing units, $2,000,000. John A. Bonnell, consult. engr.

▲ **N. J., Bayonne**—HOUSING—Bayonne Housing Auth. plans by Mr. Erwin Gerber, 1180 Raymond Blvd., Newark, 126 housing units, $1,000,000.

N. J., Edison—HOUSING—Housing Authority & Redevelopment Agency, Edison Twp., Middlesex Co., 1036 Amboy Ave., Fords, plans by Ricker & Axt, 6115 Hudson Ave., West New York, 60 housing units. $600,000.

▲ **N. J., Jersey City**—HOUSING—Jersey City Housing Auth., 514 Newark Ave., plans by Kelly & Gruzen, 80 Fifth Ave., New York, N. Y., 712 housing units. $7,000,000. CD 6/27/50.

▲† **N. Y., Bath**—RECREATION AND THEATER—Veterans Admin., Munitions Bldg., Wash., D. C., recreation and theater bldg., alterations to two bldgs. $1,500,000-$2,000,000. CD 10/26/45.

N. Y., Plattsburgh — HOUSING — Plattsburgh Housing Auth. plans by Sargen, Webster, Crenshaw & Folley, Division St., 50 housing units. $500,000.

▲ **N. Y., Syracuse**—HOUSING—Syracuse Housing Auth. plans by Fred O'Connor, 1221 Chimes Bldg., 318 housing units. $3,000,000.

▲ **N. Y., Utica**—AUDITORIUM, etc.—City, City Hall, plans by Gilbert Seltzer of Gerhron & Seltzer, 101 Park Ave., New York, municipal auditorium and sports arena, $3,000,000.

N. C., Concord—HOUSING—Concord Housing Auth. plans by Bemis Lester, Concord, 60 housing units. $732,858.

N. D., Williston—HOUSING—Williston Housing Auth., Williston, plans by Mr. Myron R. Denbrook Jr., Wells & Denbrook, Box 1440, Grand Forks, N. D., 60 housing units, $600,000. CD 2/5/52.

▲ **O., Columbus**—SCHOOLS—Bd. Educ., 270 E. State St., voted bonds Sept. 14, school addns., imprvs. $12,900,000. CD 6/27.

▲ **O., Columbus**—HOSPITAL EXPANSION and IMPRVS. —Comrs. Franklin Co., Court House, voted bonds Sept. 14, money to be allocated to various units of Columbia Hospital Federation for necessary expansion and imprvs. $15,000,000. CD 6/27.

▲ **O., Columbus**—MEDICAL-SURGICAL UNIT—Dpt. P. Welfare, State Office Bldg., S. Front St., medical-surgical units and regional service unit for Columbus Mental Institutions. $1,560,000 and $700,000, respectively. CD 1/12.

▲ **Okla., Stillwater**—APARTMENTS—Oklahoma Agricultural & Mechanical College, Stillwater, plans by Wright & Selby, Hightower Bldg., Oklahoma City, and Philip A. Wilber & Assocs., Stillwater, apartments. $2,250,000. CD 9/6.

▲ **Ore., Portland**—HIGH SCHOOL—Multnomah School Dist. No. 1, 631 N. E. Clackamas St., plans by Stanton, Boles, Maguire & Church, Concord Bldg., 74 room high school, 86 and Bush Sts. $5,000,000. Bids April 1958.

Pa., Beaver Falls—HOUSING—Beaver County Housing Auth., plans by Frank J. Dickerson, Sabli Bldg., 44 housing units, $650,000.

▲ **Pa., Brownsville** — HOUSING — Brownsville Housing Auth., Brownsville, plans by Altman & Altman, Craig and Derrick Sts., Uniontown, 100 housing units, $1,200,000. Bids in April.

▲ **Pa., Johnstown**—HOUSING—Johnstown Housing Auth., Johnstown, plans by Joseph Triglia & Assoc., Ebensburg, 450 housing units. $4,500,000. CD 10/2/50.

▲ **Pa., McKeesport**—HOUSING—McKeesport City Housing Auth. plans by Catli Flynn, archt.-engr., 335 Shaw Ave., 300 housing units. $3,000,000.

▲ **Pa., Pittsburgh** — HOUSING — Pittsburgh Housing Auth., 200 Ross St., plans by Mitchell, Ritchey, Douden & Simonds, 430 Alcoa Bldg., Zone 19, North View Heights Housing Proj. PA-1-9, 999 units, 26 Ward, North Side, 89.5 acres, $14,000,000. CD 9/4; plans by Frey, Ringel, Grove, Schafer & Assoc., 615 W. Diamond St., Zone 12, Garfield Heights Housing Proj. PA-1-12, 532 units, 10 Ward, near East Liberty, 47.5 acres, $5,000,000, CD 8/27; plans by Curry, Martin & Taylor, 201 N. Craig St., Pittsburgh, Zone 13, Addison Terrace Addition Housing Proj. PA-1-13, 168 units, Fifth Ward, Hill District, 5.5 acres, $2,000,000. CD 8/27.

▲ **Tenn., Franklin**—HOUSING—Franklin Housing Auth., plans by Robert Macdonald, Harpeth Natl. Bank Bldg.,

(Continued on page 128)

Concrete treated with Columbia Calcium Chloride speeds construction schedules, makes stronger concrete faster, permits earlier form removal, helps to eliminate costly night finishing.
100 LBS. NET
COLUMBIA
CALCIUM
CHLORIDE
FLAKE
NOT FOR FOOD OR DRUG USE
COLUMBIA SOUTHERN CHEMICAL CORPORATION
PITTSBURGH, PENNSYLVANIA

Use Columbia Calcium Chloride in cold weather for better, stronger concrete

Columbia Calcium Chloride is a big money saver and time saver. It makes concrete better, stronger, faster. These are the proved benefits from using Columbia Calcium Chloride in winter concrete work:

1. Cuts initial set by at least two-thirds, that is, from 3 hours to 1 hour.
2. Reduces final set by same ratio—from 6 hours to 2 hours.
3. Speeds early strength—at 40°F, for example, Columbia Calcium Chloride treated concrete has the strength in 1 day equal to plain concrete at 3 days. In 2 days it has the strength equal to untreated concrete after 5 or 6 days.
4. Ultimate strength increases substantially. Tests by impartial testing organizations show an increase of 10 percent in 5 years when using calcium chloride in the mix.
5. Integral curing is improved. Columbia Calcium Chloride establishes favorable conditions for hydration during the setting and hardening period of the concrete, *despite adverse conditions of low humidity.*

The lower the temperature, the more pronounced are the advantages of Columbia Calcium Chloride treated concrete over plain concrete. Columbia Calcium Chloride is not an anti-freeze, however, and it should not be considered as such. Normal cold weather protective measures should always be followed. Its use in the mix does reduce the protective period, often from 7 days to 3 days.

Plan now to use Columbia Calcium Chloride this winter for better, stronger concrete

These are the advantages you get by using Columbia Calcium Chloride in your mix: quicker set, higher early strength, better curing, faster form removal, greater ultimate strength, increased wear resistance, increased workability.

For further information, write today to Calcium Chloride Department at the Pittsburgh address.

COLUMBIA-SOUTHERN CHEMICAL CORPORATION

SUBSIDIARY OF PITTSBURGH PLATE GLASS COMPANY

ONE GATEWAY CENTER · PITTSBURGH 22 · PENNSYLVANIA

DISTRICT OFFICES: Cincinnati • Charlotte • Chicago • Cleveland • Boston New York • St. Louis • Minneapolis • New Orleans • Dallas • Houston Pittsburgh • Philadelphia • San Francisco

In Canada: Standard Chemical Limited and its Commercial Chemicals Division

FREE BOOKLET WAITING FOR YOU

Shows how Atlantic Pneumatic Pipe Drivers Pay For Themselves!

The ATLANTIC Pneumatic Pipe Driver is sturdily built for today's improved high speed machines! *Fast* — no delay in coupling additional lengths of pipe — specially designed recess in driving head does not burr pipe.
Universal joint action between driving head and shank simplifies driving in small spaces. Wide size range. Fits standard pneumatic pavement breakers.

ATLANTIC STEEL CORP.
Since 1918 . . . Always First with the Finest!
1775 Broadway, New York 19

Goldblatt

"fresno" concrete trowel



$11.50
f.o.b. Kansas City, Mo.

1056 tools

FREE TOOL CATALOG—1,056 tools for trowel trades. 100-page illustrated book. Send name on postcard.

Exceptionally fine quality single-action "Fresno" trowel. Preserves balance despite roughest use. Tempered, ground and polished spring-steel blade is permanently riveted to sturdy aluminum mounting. Includes 6-ft. Ash handle with heavy steel ferrule. Fully adjustable. 30"x5" trowel size, order No. 30-SA. Check, money order or C.O.D. Fully guaranteed.

GOLDBLATT TOOL COMPANY, Dept. G10
1928 Walnut, Kansas City 8, Mo.

PHOENIX BRIDGE COMPANY
Engineers—Fabricators
Erectors
Structural Steel
BRIDGES and BUILDINGS

AISC

General Office and Shops
PHOENIXVILLE, PA.
Subsidiary—Barium Steel Corporation

McKIERNAN-TERRY
WIDE-RANGE LINE OF
PILE HAMMERS AND EXTRACTORS

Now made in complete standardized line of 11 double-acting hammers, 5 single-acting hammers and 2 double-acting extractors. Also Sand Drain Equipment and Steam Generators.

Write for free descriptive Bulletins.
Also builders of coal and ore bridges and unloaders, and specially designed machinery.

McKIERNAN-TERRY CORP.
32 Mercer Street, Dover, N. J.

(Continued from page 126)

and Donald Steinbaugh, Third Natl. Bank Bldg., Nashville, 78 housing units. **$1,000,000.**

▲ **Tenn., Nashville**—SCHOOLS—Bd. Educ., 700 Broadway, plans by Victor Stromquist, 1618 Church St., school, Wade St. **$344,000**; plans by Billis, Johnson & McDonald, 57 Arcade St., addn. to Meigs School, an elementary and Junior High School, Ramsey St. **$400,000**; plans by James Wilson, Presbyterian Bldg., Wharton School, **$600,000**; constr. new city technical high school. **$2,000,000.**

Tex., Baytown—HOUSING—Housing Auth., O. C. Behymer, chmn., 309 N. Pruett St., plans by Matkin & Fitch, 4101 San Jacinto at Cleburne, Houston, 60 housing units, **$540,360**; 40 housing units, **$360,000.** CD 1/20.

Tex., Breckenridge — HOUSING — Breckenridge Housing Auth., Breckenridge, plans by Wyatt C. Hedrick, T & P Passenger Station Bldg., Fort Worth, 50 housing units. **$500,000.** CD 3/9/50.

Tex., Bryan—HOUSING—Housing Auth., Joe P. White, Jr. exec. dir., P. O. Box 605, plans by William Nash, City Natl. Bank Bldg., 110 housing units, **$957,000.** CD 1/13/53.

Tex., Hallsville—SCHOOL—Hallsville School Dist., Hallsville, plans by Kelly & Deteau, 1st. Natl. Bank Bldg., Longview, school constr. **$500,000.** CD 3/7.

▲ **Tex., Harlingen**—HOUSING—J. B. Housing Auth., 1201 E. Harrison, plans by Lyman Ellis, 201 Jackson St., 120 housing units, **$1,135,200.** CD 8/8/52.

▲ **Tex., Laredo** — HOUSING — Housing Auth., Ed. S. Russell, chn., 1820 Houston St., plans by Olin Boese & Assoc., T & P Bldg., Ft. Worth, 200 housing units, **$2,045,600.** CD 5/7.

▲ **Tex., Port Neches**—SCHOOLS—Port Neches Independent School Dist., Port Neches, bond election Sept. 29, elementary school, **$469,135**; Junior High School at Groves, **$1,250,000**; Junior High School, **$1,750,000**; elementary school at Groves, **$450,000**; storage garage and warehouse, **$95,000.** CD 9/19.

▲ **Tex., Waco**—HOUSING—Waco Housing Auth., 3115 Austin Ave., plans by Wm. M. MacPherson, 114 Princess Pass, San Antonio, Proj. Tex. 10-4, 250 unit housing, **$2,284,750**; Tex. 10-5, 64 unit housing, **$648,570**; Tex. 10-6, 50 unit housing, **$488,350**; Tex. 10-7, 36 unit housing, **$302,750.**

▲ **Tex., Orange**—HOUSING—Housing Auth. of the City of Orange, P. O. Box 1787, plans by Matkin & Fitch, archts.-engrs., 4101 San Jacinto at Cleburne, Houston, Zone 4, 100 housing units. **$1,319,031.**

▲ **Tex., Orange**—LIBRARY, etc.—City, City Hall, library, auditorium and youth center, **$1,250,000.**

Tex., Wichita Falls—HOUSING—Wichita Falls Housing Auth., 501 Webster St., plans by Harkrider, Clark & Jones, T & P Passenger Station, Fort Worth, 60 housing units. **$584,880.** Joe E. Ward, 1608 Monroe St., engr. CD 1/11/52.

▲ **Va., Danville**—HOUSING—Danville Redevelopment & Housing Auth., Danville, plans by William W. Patterson, 664 Main St., 124 unit housing, **$1,000,000.**

▲ **Va., South Norfolk**—HOUSING—South Norfolk Redevelopment & Housing Auth., 10 Admirals Rd., plans by A. Ray Pentecost, Jr., Colonial Ave. at 21st St., 100 masonry housing units. **$1,800,000.**

▲ **Wash., Kennewick**—SCHOOL—School Dist. 17, voted $500,000 bonds Sept. 11 Junior High School, **$1,600,000.** J. S. Villesvik, Liberty Bldg., Yakima, archt. CD 2/8.

▲ **Wash., Mount Vernon**—HOSPITAL—Hospital Dist. No. 1 plans by J. W. Maloney & Assocs., Central Bldg., Seattle, 78 bed hospital. **$1,110,000.** $120,000 bonds voted Sept. 11. CD 7/27.

▲ **Wash., Tacoma**—County—City WING—Pierce Co., Co. Courthouse, and City, City Hall, bond election. Nov. 6 for law enforcement wing to county city bldg., **$2,700,000.** CD 8/21.

Wash., Ritzville—SCHOOL—School Dist. 160-67, Ritzville, intermediate grade school, **$700,000.**

▲ **Wis., Milwaukee**—SCHOOL—Bd. School Directors, 1111 No. 10 St., Zone 3, plans by Gassoid, Johnson & Assocs., 734 N. Jefferson St., Zone 2, Junior High School, S. 39th St. and W. Ohio Ave. **$2,500,000.**

▲ **Wis., Oshkosh**—SCHOOL—Bd. Educ., Oshkosh, **$3,500,000** bond election Nov. 6, high school. CD 12/13/55.

▲ **Wis., Sheboygan**—SCHOOLS—Bd. Educ., 837 Jefferson Ave., plans by Satre & Senescall, 707 Center Ave., elementary school, **$660,875**; plans by Bradley & Bradley, 924 N. Main St., Rockford, Ill., Junior High School, **$1,500,000**, CD 8/23; plans by Stubencauch & Assocs., 712 Erie Ave., Senior High School, **$3,000,000.** CD 7/25.

COMMERCIAL BUILDINGS

▲ **Ala., Montgomery**—HOSPITAL—St. Margaret's Hospital, 834 Adams Ave., plans by Charles McCauley, Jackson Bldg., Birmingham, hospital addn. **$1,500,000.** CD 12/9/49.

▲ **Ark., Little Rock**—HOSPITAL—Missouri Pacific Hospital, 1310 Lincoln St., plans by Richard W. Groh, 807½ W. 3rd St., 4 floor hospital annex to be used primarily to house patients. **$1,000,000.** Completion set for Jan. 1958.

▲ **Calif., Hayward**—STORE—Branden Constr. Co., 3470 Tennyson Rd., plans by David T. Johnson, 3409 Grand Ave., Oakland, 2 story, 160,000 sq. ft. rein.-con. Kahn's Dpt. Store. **$3,000,000.** CD 5/4/54, under CA.

▲ **Calif., Los Angeles**—APARTMENT—Wagner Constr. Co., 1022 S. La Cienega Blvd., plans by Reigh & Maxwell, 1022 S. La Cienega Blvd., 124,000 sq. ft.

(Continued on page 130)

Good news to a profit-minded contractor

Estimated 30 days

FINISHED IN 12!

That's the kind of news every contractor likes to hear. And that's the kind of performance record BAY CITY is associated with more and more, on job after job. For instance, the estimate of 30 days on excavating to a depth of 25 feet in Ohio blue shale was cut to 12 days by Tom Simich & Sons Construction Company, one of the leading sewer and water contractors of Cleveland. He was using a BAY CITY 1½ yard Hoe with 54 inch dipper. Join the growing ranks of "profit-minded" contractors who are using BAY CITY excavating and material handling equipment—either crawler or rubber tire mounted. Take the first step today by writing for Catalog—no obligation, of course.



253

BAY CITY SHOVELS INC. • BAY CITY, MICHIGAN

BAY CITY

SHOVELS • CRANES • HOES • DRAGLINES • CLAMSHELLS

129

(Continued from page 128)

apartment, 2 swimming pools, 7½ acres to be landscaped. $1,500,000.

Conn., Cheshire—CHURCH—St. Bridget's R. C. Church, Highland Ave., plans by Howard Sullivan, 1397 Chapel St., New Haven, church bldg. to seat 600, Parish Center, Main St. $500,000. CD 7/24.

▲ **Conn., Hartford**—HOSPITAL—Mount Sinai Hospital, 500 Blue Hills Ave., plans by Ebbets, Frid & Prentice, 862 Asylum Ave., 4th floor hospital addn. $2,500,000. Paul D. Bemis, 36 Pearl St., and A. John Macchi, 57 Farmington Ave., engrs. CD 5/25.

▲ **Conn., Shelton**—COUNTRY CLUB, etc.—Shelton Yacht & Cabana Club, Inc., River Rd., 300 boat marina and country club, Housatonic River, three-fourth acre swimming pool and skating rink. $1,000,000; pier, Housatonic River, off River Rd., $200,000.

▲ **Conn., West Hartford**—HOUSE DEVELOPMENT—Carter Constr. Co., 1125 New Britain Ave., plans by Hollis W. Kincaid, 81 Market Sq., Newington, 48 house development, Fuller Heights, Fuller Dr. $1,291,-200.

▲ **D. C., Wash.**—DORMITORY—Trinity College, Michigan Ave. and Franklin St. N.E., plans by Gaudreau & Gaudreau, 330 N. Charles St., dormitory, incl. cafeteria and recreation rooms on present campus. $1,276,000.

▲ **Fla., Palm Beach**—MOTEL—J. Meyer Schine, Schine Hotels, Inc., 2201 Collins Ave., Miami Beach, 400-room motel, south of Phipps Park. $2,000,000.

Ill., Chicago—HOSPITAL—Belmont Community Hospital, 4058 Melrose St., plans by Roy W. Stott, 2915 W. 95th St., Evergreen Park, hospital addn. $500,000.

▲ **Kan., Halstead**—HOSPITAL—Sisters of St. Joseph Hospital, plans by Ash & Harrison, 307½ Laura St., Wichita, hospital addn. $1,000,000. CD 11/25.

Kan., Parsons—HOSPITAL—Sisters of St. Joseph, Parsons, plans by Ash & Harrison, 307½ Laura St., Wichita, Mercy Hospital. $500,000.

▲ **La., New Orleans**—SUPER MART—Grimball-van-Amerongen, (owner and archt.) 403 Baronne St., 3 story, rein.-conc. Material Super Mart, $1,000,000.

▲ **Md., Hyattsville**—HOMES—Owner, c/o John D'Epagnier, archt., 1004 Riply St., Silver Spring, 155 homes known as Beacon Heights, West Hyattsville. $1,550,-000.

Md., Takoma Park—DORMITORY, etc.—Washington Missionary College plans by Ronald Senseman, 327 Carroll Ave. N.W., Wash., D. C., dormitory and dining room. $500,000.

▲ **Mass., Fall River**—HOSPITAL—Union Hospital, 538 Prospect St., plans by Curtin & Riley, 45 Newbury St., Boston, 2 story, bsmnt. hospital addn., alterations, Prospect St. $1,425,000. CD 3/14/55.

▲ **Mich., Detroit**—SCHOOL—Detroit Lutheran High School Development, Dr. Henry Ulbrich, chn., 5040 Joy St., plans by Alfred Emmerling, 112 Madison St., Zone 26, high school, East Side, Kelly Rd. south of Eighth Mile Rd. $1,500,000. CD 3/29.

Mo., Joplin—HOSPITAL—St. John's Hospital, 2226 Jackson St., plans by Maguolo & Quick, 4908 Delmar St., St. Louis, and R. J. Braeckel, 1224 Broadway, Joplin, hospital addn. $800,000.

▲ **N. J., Asbury Park**—DWELLINGS, etc.—City of Asbury Park Redevelopment Auth., Asbury Park, Title I, plans by Isadore Candeub, 359 South Orange Ave., Newark, dwellings and business buildings on west side property between Springwood, Sylvan and West Cookman Aves. and Lincoln Pl. $5,000,000-$6,000,000.

N. J., Fair Lawn—CLASSROOMS, etc.—Jewish Center, 10-10 Norma Avenue, plans by Sidney Schenker, 52 Church St., Paterson, addn. to existing bldg., incl. classrooms, activity rooms, gymnasium, etc. $500,000.

▲ **N. J., New Brunswick**—HOUSING—New Brunswick Housing Auth., Somerset St., plans by Turano & Gadner, 35 W. 53 St., New York, N. Y., Title I, housing, George St., New St., Memorial Parkway and Richmod St. $10,000,000-$12,000,000.

▲ **N. Y., Buffalo**—NURSING SCHOOL AND RESIDENCE—Deaconess Hospital, 536 Riley St., plans by Cannon, Thiele, Betz & Cannon, 2637 Main St., Niagara Falls, 5 story, 54,000 sq. ft. nursing school and residence bldg.; alterations, imprvs. to present bldg., landscaping and parking lots on east and west sides of bldg., $2,750,000. Cresap, McCormick & Paget, 342 Madison Ave., New York, consult engrs. CD 5/8.

N. Y., Elmira—DORMITORY—Elmira College, Elmira, plans by Haskell, Considine & Haskell, Hulett Bldg., dormitory, $665,000. CD 9/6.

▲ **N. Y., Rochester**—MOTEL, etc.—Wilmorlte, Inc., Scottsville, 122 unit motel and 50 suite medical center. $1,500,000.

▲ **N. Y., Syracuse**—HOUSING—Syracuse University, Syracuse, housing facilities for married students. $6,000,000.

▲ **Ore., Portland**—CLUB—Multnomah Atlantic Club, 1849 S.W. Salmon St., plans by Church, Newberry & Roehr, Builders Exchange Bldg., club addn. $1,000,-000.

▲ **Tenn., Nashville**—OFFICE BLDGS.—Baptist Sunday School Bd., 127 9th Ave. N., two office bldgs., between Broadway and Church St. $5,000,000. CD 12/23/48.

Tex., Beaumont—CHURCH—Saint Marks Episcopal Church, 680 Calder St., church bldg. expansion, $500,000.

▲ **Tex., Ft. Worth**—SANCTUARY—Travis Ave. Baptist Church c/o Rev. R. E. Naylor, 3000 Travis Ave., plans by Preston M. Geren, 1607 Ft. Worth Natl. Bldg., sanctuary, 3200 seating capacity with chapel, air conditioned. $1,000,000.

▲ **Tex., Houston**—APARTMENT - HOTEL—Hermann Drive Assn., 1400 Hermann Dr., apartment-hotel, 1400 Blk., Hermann Dr. $2,000,000.

▲ **Tex., San Antonio**—BANK, OFFICE—Groos National Bank, 143 W. Commerce St., bank and office bldg., W. Commerce St. $2,750,000.

Vt., Derby—SCHOOL—Derby Academy, Main St., plans by Roland W. Whittier, 108 Shelburne St., Burlington, 33,000 sq. ft. high school, $500,000.

▲ **Wis., Waukesha**—HOSPITAL—Waukesha Memorial Hospital, 725 American Ave., plans by Eblin, Plunkett & Keymar, 1220 N. Milwaukee St., Milwaukee, 71 bed hospital addn. $1,500,000. CD 3/14.

▲ **Wis., West Allis**—OFFICE—Allis Chalmers Mfg. Co., 1126 S. 70 St., plans by Fritz von Grossmann, 5455 W. Burleigh, Milwaukee, 7 story, 60x100 ft., steel, brick office, $1,500,000. CD 6/26.

B. C., Nanaimo—STORE—T. Eaton Co. Ltd., plans by C. B. K. Van Norman, 540 Seymour, Vancouver, 2 story, rein.-con. department store to replace existing one here. $800,000.

▲ **Ont., Toronto**—COMMUNITY—Consolidated Building Corp., 89 Avenue Rd., plans by Faludi & Simonson Associates, consult. engrs. and archts., 614 Church St., Toronto, Satellite Community, incl. 1,600 homes, 100-acre industrial area schools, shopping center, parking and swimming pool and 700 garden-type apartment units, 400-acre tract bounded by No. 401 Highway, McCowans' Rd. and Hydro right-of-way, $30,000,000.

▲ **Que., Alma**—HOUSING, etc.—M. Georges Remillard, c/o Richelieu Finance, rue des Cedres, Chicoutimi, housing, incl. community, church, commercial center, and industrial center, 24 acre site, near airport. $3,000,000.

Que., Montreal—OFFICE—Granger & Freres Ltd., 56 Notre Dame St. W., plans by Crevier, Lemieux & Mercier, 1065 Pratt Ave., Outremont, 1 and 2 story, bsmnt., 125x400 ft. brick walls, tar and gravel roof, office and warehouse concrete fdn. Cremazie Blvd. W. near Esplanade Ave. $600,000. Beaulieu, Trudeau, Dubuc, Lalancette & Beaulieu, 5810 Cote St. Luc Rd., consult. engrs.

INDUSTRIAL BUILDINGS

▲ **Ariz., Tempe**—POWER PLANT—Arizona Public Service Co., 501 S. 3 St., Phoenix, 220,000 kw. power plant, near here. $28,000,000. To go ahead 1957.

▲ **Conn., Stratford**—WAREHOUSE—Wm. B. Meyer, Inc., 745 Railroad Ave., Bridgeport, plans by Peter Petrofsky, 177 State St., Bridgeport, storage warehouse, 118,000 sq. ft., Great Meadows, railroad siding, $1,180,000.

▲ **Fla., Orlando**—MANUFACTURING PLANT—Glenn L. Martin Co., in charge of operations, Edward G. Uhl, vice-pres., Middle River, Baltimore, Md., manufactur-

(Continued on page 132)

The SUBMERSIBLE SEWAGE EJECTOR



Engineered for

UNDERGROUND LIFT STATIONS
HIGHWAY UNDERPASS DRAINAGE

The **weil** NON-CLOG Screenless Submersible Sewage Pump with the BLADELESS impeller will pump ALL sewage and drainage water — household sewage, industrial sewage and waste — even rags.

Capacities 35 to 2000 GPM with heads to 70 feet.
Discharges: 3", 4", 5" and 6"; ½ to 20 H.P. Motors.

Illustration shows economical installation which DOES NOT REQUIRE A PUMP HOUSE to mar the landscape. This reduces the overall cost of the Lift Station or Underpass Pumping Station.

Special Bulletin SE-862

New Bulletin SE-862 specially prepared for Lift Station Design is now available upon request. This bulletin gives possible layouts, minimum dimension requirements, specifications on fittings and suggested piping diagram. **Write for it today!**

weil PUMP COMPANY

1528 NORTH FREMONT ST. • CHICAGO, ILLINOIS



GOOD workmanship is one of the most important factors in preventing leaky brick walls.

Good workmanship includes wetting the brick—completely filling the head and bed joints—and back-plastering the face brick before the back-up units are laid.

Expect trouble when the face brick are not parged. Even if the space between the face brick and the back-up units is slushed, it cannot be completely filled with mortar. Voids are left between the mortar and the brick, through which water may enter, trickle down and leak to the inside of the wall.

Brixment mortar enables the bricklayer to back-plaster quickly and easily. Brixment mortar has great plasticity, high water-retaining capacity and bonding quality, great resistance to freezing and thawing, and freedom from efflorescence. Because of this *combination* of advantages, Brixment is the leading masonry cement on the market.

BRIXMENT

LOUISVILLE CEMENT COMPANY, Incorporated, LOUISVILLE, KENTUCKY

Tho'

CAKED WITH CONCRETE

this phone never failed

Moving with the job as it progressed, this phone was one of a series used by the S. A. Healy Company on the Bowery Bay Sewerage Disposal job, almost five miles long.

Being subjected to such hardships is nothing new for HOSE-McCANN Sound Powered Telephones for they are made to operate just about everywhere with the same dependable service . . . under normal conditions or in any emergency.

NEED NO CURRENT Activated by the sound energy of the voice, these phones operate at all times without batteries or other outside sources of current. For permanent installation on industrial projects or for temporary use on construction jobs, HOSE-McCANN Phones offer trouble-free performance with a minimum of upkeep.

INDOOR OR OUTDOOR MODELS
Available in selective or common ringing and semi-selective or common talking.

Write for illustrated catalog

HOSE-McCANN
TELEPHONE CO., INC.
761 THIRD AVENUE
BROOKLYN 32, N. Y.

TIPS FROM GURLEY

Beat the wind with an Optical Plummet Transit

Built-in optical plummet eliminates swing and sway of cord and plumb bob. Positive accuracy of set-up assured. Special tripod is standard equipment. *Write for Bulletin OP-57.*

Have you tried Variable Power?

Variable Power, now standard on all Gurley transits and levels, permits wide range of magnification with one eyepiece. Change magnification to suit weather, light. *Write for "Facts on VP"*

W. & L.E. Gurley
Union Plaza, Troy, N. Y.

SINCE 1845

The BELMONT IRON WORKS

Engineers — Fabricators — Erectors
Contractors — Exporters
Cable address—Beliron

STRUCTURAL STEEL
BUILDINGS & BRIDGES
RIVETED — ARC WELDED
Shops: Eddystone, Pa.—Philadelphia, Pa. Royersford, Pa.

22nd St. & Washington Ave. Philadelphia 46, Pa. Main Office

New York Office 44 Whitehall St., N. Y. 4, N. Y.

HOT DIP GALVANIZING

YOU can profit by our experience of over 50 years in Hot Dip Galvanizing. Our equipment is modern, our men are skilled and our deliveries and prices are right.

We have galvanized thousands of tons of: gratings, beams, bars, perforated screens, sections, forms, tanks, fittings, rails, fastenings, etc. *Excellent facilities for pickling and oiling.*

ENTERPRISE GALVANIZING CO.
2517 E. CUMBERLAND ST. • PHILADELPHIA 25, PA.

(Continued from page 130)

ing plant, manufacturing electronics, nuclonics and missiles, piloted aircraft, 6,400 acres, 4½ mi. south of Orlando, U. S. Hy. No. 441. $21,100,000.

▲ Fla., West Palm Beach—PLANT—Pratt & Whitney Aircraft Div., United Aircraft Co., 1 Charter Oak Blvd., West Haven, Zone 1, Conn., plans by George H. Miehls & Albert Kahn Associated Architects & Engineers, Inc., 345 New Center Bldg., Detroit 2, Mich., industrial plant west of here. $42,000,000. CD 9/10.

Ga., Lithonia—PLANT, etc.—Lithonia Lighting Products Co. plans by Mastin & Summer, 1401 Peachtree St., Atlanta, 109,000 sq. ft., brick, steel, rein.-conc. mfg. plant, 5,000 sq. ft. air conditioned, office. $750,000.

▲ La., Geismar—PLANT—Wyandotte Chemicals Corp., Alkali Square, Wyandotte, Mich., electrolytic chlorine-caustic soda plant, $20,000,000.

▲ Mass., Marlboro—Northboro—INDUSTRIAL DEVELOPMENT—James V. Flaherty, 30 Granite St., Norwood, industrial development Marlboro-Northboro Line, 900 acres owned, $1,000,000. To go ahead in Spring.

▲ Mass., Norwood—INDUSTRIAL DEVELOPMENT—James V. Flaherty, 30 Granite St., industrial development, Nahatan St., 15 acres owned. $1,500,000. To go ahead in April-May.

N. J., Jersey City—FACTORY—C. F. Mueller Co., 180 Baldwin Ave., plans by Harris K. Smith, 508 Summit Ave., 50x220 ft., steel, concrete aluminum factory, $500,000. Work in about 1 month.

N. J., Kearny—WAREHOUSE, etc.—Roadway Express, Inc., 1200 Adams St., Hoboken, 60,000 sq. ft. warehouse and office veneer blocks, brick, Central Ave. and 2nd Ave. $500,000. Louis T. Klauder & Assoc., Phila. Natl. Bank Bldg., Phila., Pa., consult. engrs.

▲ N. Y., Buffalo—AROMATICS RECOVERY UNIT—Frontier Oil Refining Co., Div. Ashland Oil & Refining Co., Ashland, Ky., 1,370 b/d aromatics recovery unit, $15,000,000.

▲ O., Fostoria—LABORATORY, etc.—National Carbon Co. Div. Union Carbide & Carbon Co., 30 E. 42 St., New York 17, N. Y., 2 story, 80x150 ft. brick laboratory-production bldg., and 20,000 sq. ft. aluminum constr. warehouse over $1,000,000.

O., Toledo—WAREHOUSE—Owner, c/o New York Central System, G. T. Donahue, Engr. Maint. & Ways, St. Clair Ave. and W. 3 St., Cleveland 13, warehouse and distribution center, near Angola Rd. and Reynolds Rd., Adams Twp. $500,000.

▲ Tex., Orange—PLANT—Firestone Tire & Rubber Co., Orange, abandoned 75,000 ton styrene mfg. plant. $10,000,000. CD 5/14.

Tex., Dallas—WAREHOUSE—Ray E. Skillern, 520 N. Pearl St., 100,000 sq. ft. masonry, fireproof, warehouse. $700,000.

Tex., Houston—PLANT—Armour & Co., Union Stock Yards, Chicago, Ill., 1st unit meat packing plant site in Roy Hugh Cullen's 650 acre tract for stockyards and processing plants. $750,000.

Tex., Houston—PLANT—Oscar Mayer & Co., 1241 N. Sedgwick St., Chicago, Ill., (1st unit) meat packing plant, site in Roy Hugh Cullens 650 acre tract for stockyards and processing plants. $500,000.

▲ Tex., Saginaw—GRAIN ELEVATORS—C & G Grain Co., National Bank of Topeka Bldg., Topeka, Kan. rein.-conc. grain elevators, Fort Worth and Denver R.R. $3,000,000.

▲ Tex., Sugarland—PLANT—Schlumberger Well Surveying Corp., 5000 Gulf Freeway, plant, Industrial Subdivision. $1,000,000.

▲ Wis., Madison—HALL—University of Wisconsin, plans by Grellinger & Rose, 757 N. Broadway, Milwaukee, addn. to Sterling Hall, $1,200,000. Roger C. Kirchhoff c/o owner, state archt. CD 12/21.

▲ Wis., Wauwatosa—WAREHOUSE—General Merchandise Co., 207 N. Milwaukee St., Milwaukee, plans by A. Epstein, 2011 W. Pershing St., Chicago, Ill., 1 story, 400,000 sq. ft. to 600,000 sq. ft. warehouse, $2,500,000. CD 11/29.

B. C., Vancouver—PLANT—MacMillan & Bloedel Ltd., 837 W. Hasting, plant for mfg. of grocery bags, using multi-purpose kraft paper on North arm Fraser River, $500,000.

▲ Man., Lynn Lake—MINING DEVELOPMENT—International Nickel Co. of Canada Ltd., 25 King St., Toronto, Ont., mining development and townsite for 15,000 persons in new copper nickel area of northern Manitoba. $150,000,000.

▲ Ont., Hamilton—FOUNDRY—Canada Iron Foundries Ltd., Stuart St. W., foundry to produce railway wheels. $5,000,000.

UNCLASSIFIED

▲ California—NATURAL GAS PIPE LINE—Pacific Lighting Gas Supply Co., 810 S. Flower St., Los Angeles, 30-in. natural gas pipe line from Southern part of San Joaquin Valley east of Bakersfield to Newhall, Est. over $10,000,000.

▲ Georgia—RURAL DISTRIBUTION LINES—Blue Ridge Electric Assn., Young Harris, 84 mi. rural distr. lines, 11 mi. 69 kv transmission line and sys. imprvs., Towns Co. $1,040,000. CD 1/13/54.

South Dakota—SUB-STATION—Dakotas Electric Cooperative, Bismarck, sub-station at Glenham and imprvs. $729,114. Ulteig Engr. Co., 1114½ Main St., Fargo, N. D., consult. engr.

▲ Wash., Tacoma—WATERWAYS—Port of Tacoma, Portacoma Rd., bond election Nov. 6, dredging and completion of Hylebos waterway, dredging of pioneer channel in Port Industrial waterway and development of facilities no Sitcum waterway, $5,400,000. CD 9/22/55.



Price

Concrete Pipe for Cincinnati's Montgomery Road

Montgomery Road is a main artery that feeds into Cincinnati from the northeast. It carries a heavy load of traffic, so when an extension of a 36-inch water supply line was planned, ease of installation was an important consideration.

Prestressed concrete cylinder pipe turned out to be a happy choice. The job went smoothly for the contractor, A. F. Jelen & Son Co., and the highway was kept open to traffic even through congested districts like the one in the picture. Basic reason was the steel-and-rubber joint which is made quickly and easily . . . and incidentally makes a bottletight, yet flexible joint that is designed to take heavy traffic loads.

The line is 11,000 feet long and includes both 30 and 36-inch pipe. Along with 620 standard 16-foot lengths, the contractor installed 16 bends, 2 wyes, 3 reducers, 3 tees, 2 closure assemblies, one cross, and a number of short lengths and bevel adapters.

For information on any type of concrete pressure pipe for either water supply or pressure sewer lines, write Price Brothers Company, Dayton, Ohio.

New Heavy-Duty V-8's—206, 226 and 257 hp.



Power to Pull . . . Power to Roll

Out on the job or on the road, new INTERNATIONAL V-Line trucks get loads moving *fast*, keep them moving. They are powered by new heavy-duty V-8's with the most GO under any truck hood. You get economical operation, top performance. You haul big, profitable loads.

Only INTERNATIONAL short stroke, Y-block V-8's have all these long-lasting, cost-cutting features—"wet" replaceable exhaust valve guides, positive type valve rotators, exhaust valve faces and seats of Stellite, neoprene intake valve shields, sodium filled exhaust valves (V-549). Plus many new lightweight features that reduce costs and increase payloads.

With new V-Line design, there's rugged construction that will take all the off-highway punishment you can give these trucks. There's lots of roomy comfort in the sturdy Comfo-Vision cabs, too. Why not drive one today? See your INTERNATIONAL Dealer or Branch.

INTERNATIONAL HARVESTER COMPANY • CHICAGO

INTERNATIONAL TRUCKS

All-Truck Built to save you the BIG money!

Motor Trucks • Crawler Tractors • Construction Equipment
• McCormick® Farm Equipment and Farmall® Tractors

Bids—Low Bids—Contracts—Second Section

NEW ENGLAND

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS

BRIDGES

October 8 Connecticut — October 10 Maine

STREETS AND ROADS

October 8 Connecticut — October 9, 11 Massachusetts

▲ **Conn., Hartford**—BA 10/15—Hartford Bridge Auth., 284 Sheldon St., (selected list of bidders) South Windsor Bridge across Connecticut River, Windsor. $8,000,000. Thomas Worcester, Inc., 85 State St., Hartford, engr. CD 7/17.

▲† **Mass., Falmouth**—STORAGE FACILITIES—BA 10/16—U. S. Eng., 150 Causeway St., Boston, constr. addnl. storage facilities, Otis Air Force Base, ENG-19-016-57-65. $1,500,000-$1,750,000. Plans deposit $25, refundable. CD 9/20.

BUILDINGS—BA

▲ **Mass., Danvers**—PLANT—BA 10/9—Sylvania Electric Products, Inc., C. A. Haines, dir. Facility Planning, 460 Market St., Williamsport, 294x430 ft. concrete plant. $1,500,000. Plans deposit $25. Paul H. Valentine, 699 Belmont Ave., Williamsport, Pa., archt. CD 5/9.

Conn., Avon—SCHOOL—BA 10/11—Town, School Bldg. Comm., Old Town Hall, high school, Route 167. $700,000. Plans deposit $30. Carl J. Malmfeldt & Assoc., 36 Pearl St., Hartford, archts. Paul D. Bemis, 36 Pearl St., Hartford, engr.

▲ **N. H., Hanover**—DORMITORIES—BA 10/15—Trustees of Dartmouth College, Hanover, 4 dormitories, 2 pairs of 3 story bldgs. $1,500,000. Campbell & Aldrich, 38 Newbury St., Boston, Mass., archts. CD 2/10.

▲ **Conn., Meriden**—SCHOOL—BA 10/19—Town, Bd. Educ., 22 Liberty St., West Side High School, Coe Ave., $2,600,000. Plans deposit $60. Willard Wilkins, 945 Asylum Ave., Hartford, archt. Robt. W. Loomis, 32 Maple Ave., Windsor, engr. CD 2/13.

HEAVY CONSTRUCTION—LB & CA

▲† **Consolidated Constructors, Inc.**, 807 Congress St., Portland, Me. LB $1,209,453, buildings, air force station, ENG-19-016-57-55, TOPSHAM, ME. U. S. Eng., 150 Causeway St., Boston, Mass. Bids Sept. 25. CD 9/11.

† **Procurement Office**, Portsmouth Air Force Base, Portsmouth, N. H., rejected bids Aug. 24, site preparation and utilities, Air Force Base, IFB 27-604-57-2, PORTSMOUTH, N. H., LB $880,489, Will re-advertise. (Correction—status). CD 9/6, under LB.

▲ **MASSACHUSETTS**—Commonwealth of Mass., Dpt. P. Wks., 100 Nashua St., Boston,
J. F. Fitzgerald Constr. Co., 1000 Turnpike St., Canton, Mass. LB $1,799,973, highway exten. Rte. 128 Northern Circle Hy., FAP U 331-12 and U 346-1, Gloucester. Bids Sept. 25. CD 9/11.

▲† **Great Lakes Dredge & Dock Co.**, 17 Battery Place, New York, N. Y. CA $4,621,860, est. $4,279,500. imprvt. dredging President Rds., Boston Harbor, CIVENG-19-016-57-5, MASSACHUSETTS. U. S. Eng., 150 Causeway St., Boston, Mass. CD 9/11, under LB.

BUILDINGS—LB & CA

▲ **John W. Galbreath & Co., Inc.**, 150 E. 43 St., New York, N. Y. Owner Builds. $4,500,000 6 story, bsmnt., 100,000 sq. ft. OFFICE, site former Brunswick Hotel, Boylston, and Clarendon Sts., BOSTON, MASS.

M. S. Kelliher Co., 294 Washington St., Boston, Mass. CA Approx. $700,000. DAIRY PLANT addn., alterations, convert 3 units former Maverick Mills, into PLANT, EAST BOSTON, MASS. Whiting Milk Co., 40 Cambridge St., Charlestown, Mass. CD 5/15.

▲ **United Engineers & Constructors, Inc.**, 1401 Arch St., Phila., Pa., CA Est. over $3,000,000 design and construct, 106-kw TURBO GENERATOR PLANT; CA $276,000. BOILER ROOM addn. at electric power plant, DEVON, CONN. Connecticut Light & Power Co., Selden St., Berlin, Conn. Awarded Sept. 13. CD 9/6.

▲ **Hayes Constr. Co.**, 1285 East St., New Britain, Conn., CA, $2,149,000 (3 bidders) Southwestern Junior High SCHOOL, Steele St., NEW BRITAIN, CONN. City, Supt. Schools, 27 Hillside Pl., New Britain, Conn. Bids Sept. 21. CD 9/17.

MIDDLE ATLANTIC

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS

BRIDGES

October 9 Maryland — October 16 New Jersey

STREETS AND ROADS

October 9 Maryland — October 18 New York

▲† **N. Y., Rome**—PAVING—BA On Or About 11/15—U. S. Eng., 111 E. 16 St., New York, Zone 3, r/w paving and apron at Griffiss Air Force Base. Over $5,000,000, Greenberg & Ames and William H. McFarland, 303 Fourth Ave., New York, Zone 10, engrs. CD 8/24.

BUILDINGS—BA

▲ **N. J., Fort Monmouth**—HOUSING—BA 10/25—U. S. Eng., 111 E. 16 St., New York 3, N. Y. construct and finance, 120-units of Capehart HOUSING, ENG-30-075-57-1, $1,500,000-$1,750,000. CD 9/27.

BUILDINGS—SLC

▲ **Pa., Irwin**—ATOMIC REACTOR CENTER—Westinghouse Electric Corp., Gateway Center, Pittsburgh, soon lets contract 3 story, brick, block atomic reactor center, near here. $6,500,000.

HEAVY CONSTRUCTION—LB & CA

▲ **NEW YORK**—Dpt. P. Wks., The Gov. Alfred E. Smith State Office Bldg., Albany,
W. E. O'Neil Constr. Co., 412 Syracuse Kemper Bldg., Syracuse, N. Y. CA $2,408,286. 2.7 (2.11 acc.) mi. Syracuse-Bridgeport, Pt. 1, S.H. 672; Syracuse-Bridgeport, SH 672A; Syracuse-Bridgeport, Pt. 3, FARC 56-47, FASH 56-3, Onondaga Co. Bids Aug. 23, awarded Sept. 18. CD 8/29, under LB.
Stormont Constr. Co., Cornwall, Ont. LB (1) $249,459, (2) $390,430, (3) $541,464, (4) $335,616, (5) $74,084, (6) $713,452 combinations, (7) $799,616 combinations, (8) $844,384 combinations. reservoir clearing between Waddington and Barnhart Island Power Plant, St. Lawrence Co., Spec. No. PA-5-11023, St. Lawrence Contr. No. 31, NEW YORK. The Power Authority of the State of New York, 270 Broadway, New York, N. Y. Bids Sept. 25. CD 9/12;
Macasphalt Constr. Corp., 33-15 Lawrence St., Flushing, N. Y. LB $96,523 (3 bidders) No. 13, asph. repaving roadways of Ross St. from Wythe to Lee Aves. and Withers St. from Meeker Ave. to Humboldt St. (Brooklyn, N. Y.)

▲ **Vanbro Contg. Corp.**, Emery Court, Eltingeville, Staten Island 12, N. Y. LB $1,987,000. (3 bidders) Seaside Blvd. imprvt. Contr. 1 grading, paving, curbs, sidewalks and utilities, Miller Field to Winfield St., Richmond Boro, NEW YORK. President Richmond Boro, Boro Hall, St. George, Staten Island 1, N. Y. Bids Sept. 19. CD 9/4.

▲ **W. J. Barney Corp.**, 101 Park Ave., New York 17, N. Y. CA $2,658,850. Contr. 120.002, transit shed, Pier 11, Atlantic Basin, BROOKLYN, N. Y. Port of New York Auth., 111 Eighth Ave., New York 11, N. Y. CD 9/17, under LB.

▲ **Fehlhaber Constr. Co.**, 217 E. 49 St., New York 17, N. Y. CA $3,472,413. (2 bidders) demolition of Piers 35 and 36, dredging and constr. bulkhead and fill for proposed Pier 11 at Atlantic Basin, Contr. BP-12.001, BROOKLYN, N. Y. Port of New York Auth., 111 Eighth Ave., New York 11, N. Y. CD 6/21, under LB.

▲ **McLean, Grove & George M. Brewster**, 275 Fort Lee Rd., Bogota, N. J. (joint venture) LB $11,771,580. (7 bidders) Contr. 453, constr. portion of West Delaware Tunnel of Delaware Sys., incl. approx. 26,000 lin. ft. tunnel incl. Shaft 4, approx. 380 ft. deep, town of Colchester, Delaware Co. and town of Rockland, Sullivan Co., NEW YORK, N. Y. Bd. Water Supply, 120 Wall St., New York, N. Y. Bids Sept. 25. CD 8/30.

▲ **Slattery Contg. Corp.**, 46-36 54 Rd., Maspeth, N. Y. LB $4,748,389. (2 bidders) Manhattan Plaza imprvs., Brooklyn Bridge reconstr. of bridge approach alterations to subway structures in connection with the wid'n. of Centre St. and Park Row and constr. of pedestrian underpass, ramps, street approaches, paving and landscaping, NEW YORK, N. Y. Dpt. P. Wks., Municipal Bldg., New York 7, N. Y. Bids Sept. 19. CD 8/10.

▲ **Westinghouse Electric Corp.**, 40 Wall St., New York 5, N. Y. CA $1,021,400. (2 bidders) furnishing, installing main power equip. for 59 Street Power Plant, New York City Transit System, Manhattan, Contr. No. P-162, NEW YORK, N. Y. New York City Transit Auth., 370 Jay St., Brooklyn 1, N. Y. Bids Aug. 3, awarded Aug. 23. CD 8/16, under LB.

▲ **Fischbach & Moore, Inc., Slattery Contg. Co., & J. Livingston & Co.**, 226 E. 41 St., New York 17, N. Y. (joint venture) LB $5,950,000. (4 bidders) furnish, install Manhattan and East River portions of 69 kv underground transmission sys., 59th St. sub-station to Third Ave. sub-station, Manhattan and Brooklyn, Contr. P-191, NEW YORK, N. Y. New York City Transit Auth., 370 Jay St., Brooklyn 1, N. Y. Bids Sept. 21. CD 8/24.

▲ **Rao Electrical Equipment Co., Inc., Arc Electrical Constr. Co., Inc.**, and **Poirier & McLane Corp.**, 314 E. 39 St., New York 16, N. Y. (joint venture) LB $3,426,000. (5 bidders) furnish, install Brooklyn portion 69 kv. underground transmission sys., 59th St. sub-station to Third Ave. sub-station, Manhattan and Brooklyn, Contr. P-192, NEW YORK, N. Y. New York City Transit Auth., 370 Jay St., Brooklyn 1, N. Y. Bids Sept. 21. CD 8/24.

▲ **NEW JERSEY**—State Hy. Dpt., State Hy. Office Bldg., 1035 Parkway Ave., Trenton,
Villa Contr. Co., 233 North Ave., Westfield, N. J. CA $1,103,890, grading, paving, bridges 3.242 mi. US Rte. 206. Proj. F-100 (7), Burlington Co. Bids July 17, awarded Aug. 28. CD 7/24, under LB.

▲ **George M. Brewster & Sons**, 275 Ft. Lee Rd., Bogota, N. J., CA $4,998,450 general contract, Contract 355, Newark Bay Pumping Station sedimentation basin imprvs., sludge handling facilities, NEWARK, N. J. Passaic Valley Sewerage Comn., 24 Branford Pl., Newark, N. J. Bids Sept. 10. CD 8/8;
Ernest Jarvis & Co., 236 Chestnut St., Newark, N. J., CA $342,200, Contract 356, electrical contract (Newark, N. J.);
Lafayette Iron Works, 649 Grand St., Jersey City, N. J., CA $364,300. Contract 359, structural steel work (Newark, N. J.).
Globe Contg. Co., P. O. Box 4127, Alexandria, Va. LB $889,713 (10 bidders) Cabin John Branch Interceptor from Rockville Sewage Treatment Plant to Booze Creek, Contr. 1820-S, HYATTSVILLE, MD. Washington Suburban Sanitary Comn., Hamilton St., Hyattsville, Md. Bids Sept. 24. CD 9/13.

BUILDINGS—LB & CA

▲ **Gotham Constr. Corp.**, 501 Fifth Ave., New York 17, N. Y. CA Est. $1,250,000. 4 story RESEARCH LABORATORY and ADMINISTRATION BLDG. at site, BROOKLYN, N. Y. Jewish Chronic Disease Hospital, 86 E. 49 St., Brooklyn 3, N. Y. CD 12/27/55.

▲ **Mars Associates, Inc. & Normel Constr. Corp.**, 271 Church St., New York 13, N. Y. CA $1,063,000. (5 bidders) general constr. for rehabilitation and modernization of main bldg. and laboratory bldg. at Greenpoint HOSPITAL, Jackson St., Skillman, Debevois and Kingland Aves., BROOKLYN, N. Y. Dpt. P. Wks., Municipal Bldg., New York 7, N. Y. CD 7/12, under LB.

▲ **Terminal Constr. Co.**, State Hy. No. 17 and Moonarchie Ave., Wood-Ridge, N. J. CA, $4,980,000. (3 bidders) general constr. 590-unit Ellicott Mall HOUSING, BUFFALO, N. Y. Buffalo Municipal Housing Auth., City Hall, Buffalo, N. Y. CD 9/7, under LB;
Henry M. Dechert, Inc., 181 Allen St., Buffalo, N. Y. CA, $618,200. plumbing work (Buffalo, N. Y.).

▲ **Fallwood Estates**, c/o Karl Bloch, archt., 7 Landsdowne Ave., Merrick, N. Y. Owner Builds. $1,300,000. 81 HOUSES on tract on Fallwood Parkway west of Main St., FARMINGDALE, N. Y.

Jack & Harry Match, c/o Samuel Paul, 89-51 164 St., Jamaica, N. Y. Owner Builds. $380,000. 20 HOUSES on tract at 75 St. and Ditmars Blvd., JACKSON HEIGHTS, N. Y.

W. Goldsmith, c/o Irving Margon, archt., 18 E. 41 St., New York 17, N. Y. Separate Contracts. $850,000. 6 story APARTMENT, Merrick Blvd. and 109 Ave., South Jamaica, JAMAICA, N. Y. CD 9/20/55.

▲ **John Rosenblum, Inc.**, 1860 Broadway, New York, 23, N. Y. CA, $1,556,000. (6 bidders) general constr., Public SCHOOL 8, E. 201 St. and Mosholu Parkway, Bronx Boro, NEW YORK, N. Y. Bd. Educ., Bureau Constr., 42-15 Crescent St., Long Island City, 1, N. Y. CD 8/29, under LB.

▲ **M. Melnick & Co., Inc.**, 225 Willow Ave., New York 54, N. Y. CA, $1,339,860. (5 bidders) general constr. modification addn. to JUNIOR HIGH SCHOOL 52, Academy St. and Broadway, Manhattan Boro, NEW YORK, N. Y. Bd. Educ., Bureau Constr., 42-15 Crescent St., Long Island City 1, N. Y. CD 8/29, under LB.

Owner, c/o Albert Meklenburg Organization, Inc., 1038 Northern Blvd., Roslyn, N. Y. Owner Builds. $945,000. 45 HOUSES on tract at Christian Ave. and Quaker Path, STONEY BROOK, N. Y.

▲ **Frank Brisco Co.**, 287 S. 19 St., Newark, N. J., CA Est. $2,900,000. 4 story, 118,000 sq. ft. brick, steel, rein.-con. LABORATORY and WAREHOUSE, BERKELEY HEIGHTS, N. J. Bell Telephone Laboratories, 463 West St., New York, N. Y., Lockwood Greene Engineers, Inc., 41 E. 42 St., New York, N. Y., engr. CD 5/4.

▲ **Lewis Epstein**, 51 Skytop Rd., Cedar Grove, N. J. Owner Builds. $1,215,000. HOMES, Fairview Ridge Estates, Skytop Rd., CEDAR GROVE, N. J. Rudolph L. Novak, 89 Central Ave., Clifton, N. J., archt.

Glen View Manor, c/o James V. Virgona, archt., 272 State Highway No. 5, Palisade, N. J. Owner Builds, $800,000. 36 HOUSES on tract on Ell Rd., HILLSDALE, N. J.

▲ **B. & L. Construction Co.**, Wilson Ave., Middletown, N. J., Owner Builds, $3,200,000. 162 HOMES, New Monmouth Section, MIDDLETOWN, N. J. Erwin Gerber, 11 Commerce St., Newark, N. J., archt.

▲ **Glen-Meade**, c/o Russell & Albert Edwards, Moorestown, N. J., Separate Contracts, $1,500,000. 114-unit RESIDENTIAL DEVELOPMENT, sewage treatment plant and sewers, Cinnaminson Twp., MOORESTOWN, N. J. Dante J. D'Anastasio, 1815 Federal St., Camden, N. J., archt.

▲ **Alexander Caplan**, 407 Main St., Chatham, N. J. Owner Builds. $1,420,000. DWELLINGS, Normandy Heights and Woodruff Rd., MORRISTOWN, N. J. Walter Pheiffer, 322 Morris Ave., Elizabeth, N. J., and Wm. Chirgotis, 968 Stuyvesant Ave., Union, N. J., archts.

▲ **Modern Constr. Co.**, c/o Wm. G. Chirgotis, 968 Stuyvesant Ave., Union, N. J. Owner Builds. $1,175,000. split level HOUSES, Brookside Rd. to be known as "Indian Valley Estates" MORRISTOWN, N. J. Wm. G. Chirgotis, 968 Stuyvesant Ave., Union, N. J., archt.

▲ **Gibraltar Homes, Inc.**, Gerard Berman, Hamburg Turnpike, Preakness, N. J. Owner Builds, $2,500,000. final sections of HOMES in Gibraltar Park Estates, Wayne Twp., MOUNTAIN VIEW, N. J. Erwin Gerber, 11 Commerce St., Newark, N. J., archt.

▲ **Carl S. Carlson**, P. O. Box 199, Ridgewood, N. J., Owner Builds, $1,300,000. 58 HOMES, Preakness

DIG
in the
DRY
with a
MORETRENCH
WELLPOINT SYSTEM

MORETRENCH CORPORATION
World's Oldest . . . Largest . . . Most
Experienced Predrainage Specialists
Catalogue on request
90 West St., New York 6, N. Y.
Chicago, Ill. Tampa, Fla. Houston, Tex.
Rockaway, N. J.

from
●
●
OFFICE MANAGER
●
to
●
GENERAL MANAGER
●
●
yes, that is the quality of the personnel available to your organization through the Classified Advertising pages of ENGINEERING NEWS-RECORD.
Classified Advertising Division
ENGINEERING NEWS-RECORD
330 W. 42nd St. New York 36, N. Y.

FROM STOCK
IMMEDIATE SHIPMENT
STRUCTURAL WIDE FLANGE BEAMS
ASTM-A-7
400 TONS 10"x5¾"x21#x40'
200 TONS 12"x6½"x27#x40'
PRICE: $12.60 per cwt., net
All Extras Included
FOR QUICK ACTION
WRITE OR WIRE
Box No. 3117,
Engineering News Record
330 W. 42 St., New York 36, N. Y.

Ave. "Valley Ridge Estates", Wayne Twp., MOUNTAIN VIEW, N. J. R. L. Novak, 89 Central Ave., Clifton, N. J., archt.

Arthur Anderson, 222-D Fallen Dr., New Milford, N. J., Owner Builds, $780,000. 30 HOUSES on Spring Valley Rd., Bear Brook Manor, PARK RIDGE, N. J.

Carmen Jannarone, 70 Ravine Ave., Nutley, N. J., Owner Builds, $800,000. RESIDENTIAL DEVELOPMENT, "Pompton Knolls," Jackson Road and Boulevard, Pequannock, POMPTON, N. J. Bernard Hersch, 507 Boulevard, East Paterson, N. J., archt.

Dominic Ruta, 433 Highland Ave., Palisades Park, N. J., Owner Builds, $800,000. 40 HOMES, Saddle River Ave. and Weariness Road "Rambling Brook Estates," RIDGEWOOD, N. J.

▲ **Albin Obal** c/o Kahn Agency, Inc., 517 Market St. Rochelle Park, N. J., Owner Builds, $2,500,000. 170 HOUSES on 35-acre tract near Market St., SADDLE BROOK, N. J.

▲ **Briar Park Homes**, c/o Fenick Vogel, archt., 309 Bloomfield Ave., Caldwell, N. J. Owner Builds, $1,725,000. 64 HOUSES on tract on Brian Rd. near Passaic Ave., WEST CALDWELL, N. J.

▲ **Weinstein Brothers**, c/o Fenick Vogel, archt., 309 Bloomfield Ave., West Caldwell, N. J., Owner Builds, $2,000,000. 64 HOMES in Briar Park, Briar Road off Passaic Ave., WEST CALDWELL, N. J.

Alyson Homes Corp., 282 Trenton Ave., Paterson, N. J., Owner Builds, $750,000. 30 HOMES, Lafayette and Washington Aves., WESTWOOD, N. J. Bernard Hersch, 507 Boulevard, East Paterson, N. J., archt.

▲ **Waterford Constr. Co.**, 5603 Spruce St., Phila., Pa. Separate Contracts. $2,680,000. RESIDENTIAL DEVELOPMENT, 134 units, Lawrence Rd., BROOMALL, PA. Henry S. Berg, 1411 Walnut St., Phila., Pa., archt.

▲ **David Miller**, Vincentown, N. J. Separate Contracts $1,695,000. RESIDENTIAL DEVELOPMENT, Big Oak Rd., FALLSINGTON, PA.

▲ **H & L Builders**, 1530 York Rd., Abington, Pa. Separate Contracts. $1,280,000. RESIDENTIAL DEVELOPMENT, Edgehill Rd., HUNTINGDON VALLEY, PA.

▲ **S & M Building Corp.**, c/o Adolph Stein, Phoenixville, Pa. and **James D. Scully**, 6718 Broad St., Phila., Pa. Separate Contracts. $1,053,000. RESIDENTIAL DEVELOPMENT, 81 units, Garfield Rd., PHOENIXVILLE, PA.

▲ **Navarro Corp.**, 6219 Broad St., Pittsburgh, Pa. LB $2,566,000. 8 story, 150x165 ft., brick, block L-shaped HOSPITAL addn., alteration, PITTSBURGH, PA. St. Francis Hospital, 45 St., Pittsburgh, Pa. Bids Sept. 14. CD 8/28.

Stratford Development Co., c/o M. Segal, 6701 N. Broad St., Phila., Pa. Separate Contracts. $700,000. RESIDENTIAL DEVELOPMENT, 28 units, Washington Lane, RYDAL, PA. S. Sherman Rochlis, 1325 Walnut St., Phila., Pa., archt.

D. C. Govt., Dir. Bldgs. & Grounds, 499 Pa. Ave. N.W., Wash., D. C., rejected bids Aug. 24, Anacostia Senior HIGH SCHOOL addn., 16 and "B" Sts. S.E., WASH., D. C. LB $975,700. CD 9/4, under LB.

▲ **S. & S. Builders, Inc.**, 1337 Greenfield Rd., Oak Hill, Wilmington, Del. Separate Contracts, $1,250,000. 110 RESIDENCES, Ryan Ave., etc., WILMINGTON, DEL.

SOUTH

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS
BRIDGES
October 11 Florida
STREETS AND ROADS
October 11 Florida, Kentucky

HEAVY CONSTRUCTION—LB & CA

† **Reid & Hope**, Suffolk, Va., CA $706,111, supply facility and supply warehouse, Naval Air Station, NBy 631, Spec. 631/56. OCEANA, VA. P. Wks. Office, Fifth Naval Dist., U. S. Naval Base, Norfolk 11, Va. CD 8/3, under LB.

Williams-Austin Co., Grant Bldg., Pittsburgh, Pa., CA, $845,700. 17.7 mi. natural gas pipe line to Du Pont Bell Works from the Coco Compression Station, Kanawha Co., WEST VIRGINIA. United Fuel Gas Co., 1033 Quarrier St., Charleston, W. Va. CD 5/3/54.

▲† **W. Harley Miller, Inc.**, 132 S. Queen St., Martinsburg, Wis., LB $1,376,845; Base Bid plus Alt. A, $1,375,645; Base Bid plus Alt. B, $1,407,681; Base Bid plus Alt. C, $1,403,629. Base Bid plus Alt. A plus Alt. B, $1,406,481. Base Bid plus Alt. A plus Alt. C, $1,402,429. buildings, fuel storage facilities, Air National Guard, Martinsburg Municipal Airport, ENG-46-022-57-4, MARTINSBURG, W. VA. U. S. Eng. 237 Fourth Ave., Huntington, W. Va. Bids Aug. 22. CD 7/27.

▲ **NORTH CAROLINA**—State Hy & P. Wks. Comn., Raleigh,

N. C.—**Nello L. Teer Co.**, Trust Bldg., Durham, N. C. LB $620,529, est. $400,000-$500,000, fine grading, CABC b. conc. binder and surf. 6.2 mi. US 70. Proj. No. 2153, F-168 (13), Craven Co.; LB $713,325, est. $400,000-$500,000, grading CABC bit. surf. tr. 6.95 mi. US 19-A and 23, Proj. No. 9515, F-70 (3), Jackson, Co.;

N. C.—**Wayne Engr. & Constr. Co.**, Box 306, Mount Olive, N. C., LB $355,278, est. $400,000-$500,000, grading, STBC, b. conc. binder and surf. 9.72 mi. US 421. Proj. 4375, F-609 (3), Harnett Co.;

N. C.—**A. R. Thompson Contr. Inc.**, Rutherfordton, N. C., LB $272,724, est. $300,000-$400,000, CABC, bit. surf. tr. 5.11 mi. US 221 (reloc.). Proj. 8504, SF-231 (7), McDowell Co.;

N. C.—**Dickerson, Inc.**, Monroe, N. C., LB $109,081, est. $100,000-$125,000 STBC bit. surf. tr. 3.75 mi. County Rd. Proj. No. 9-105 S-842 (1), Alexander Co.;

N. C.—**E. B. Towles Constr. Co.**, Box 1617, Wilmington, N. C., LB $107,679, est. $100,000-$125,000. b. conc. surf. course, Class I, 9.7 mi. US 17. Proj. B. S. 3-6-25-141, New Hanover Co. Bids Sept. 25. CD 9/14.

J. A. Jones Constr. Co., 354 Aero Dr., Shreveport, La. LB $679,700, est. $892,000, (10 bidders) Proposal No. 13486, North Pier and Tower at Moisant International Airport, Kenner, NEW ORLEANS, LA. City, 302 City Hall, New Orleans, La. Bids Sept. 20. CD 8/21.

BUILDINGS—LB & CA

▲ **Colt Sommers Co.**, Vidalia, Ga., CA, $1,093,700. Springfield Elementary SCHOOL (colored), Bostwick Elementary SCHOOL (colored), Rutledge Elementary SCHOOL (colored), Pearl High & Elementary SCHOOL (colored) Bostwick Elementary SCHOOL addns., mech. remodeling to Rutledge Elementary SCHOOL Madison Elementary SCHOOL, Morgan County High SCHOOL addn. and Buckhead Elementary SCHOOL addn., Morgan County MADISON, GA. State SCHOOL Bldg. Auth., 244 Washington St. S.W., Atlanta, Ga. Bids Sept. 18.

▲ **Ruscon Constr. Co.**, Box 837, 149 E. Bay St., Charleston, S. C., CA, $1,024,439. foundations for TEACHING HOSPITAL, University of Florida, GAINESVILLE, FLA. State Bd. Control, University of Florida, Gainesville, Fla. Awarded Aug. 30. CD 1/25, under LB.

▲ **S. S. Jacobs Co.**, Hildebrandt Bldg., Jacksonville, Fla., est. $1,000,000. DOCTORS OFFICE BLDG., Miami Rd. and Palm Ave., JACKSONVILLE, FLA. Mallin Developers, Inc., c/o Norman H. Freeman & Clements, archts., 1201 San Marco Blvd., Jacksonville, Fla. Tribble, Lee & Warren, Hildebrandt Bldg., Jacksonville, Fla., mech.-engrs., Mead & Smith, Hildebrandt Bldg., Jacksonville, Fla., struct. engrs.

▲ **Mackie Co., Inc.**, 2818 Coral Way, Miami, Fla., CA, $1,106,402, 144 RESIDENCES, S.W. 47 Terrace, Third Addn., MIAMI, FLA. Westwood Lake, Inc., 2818 Coral Way, Miami, Fla. James E. Vensel, 2820 Coral Way, Miami, Fla., archt.

▲ **Hargett Constr. Co.**, 113 Walton St., Lexington, Ky., LB $1,972,700. (5 bidders) Shawneetown Student APARTMENTS, 6 bldgs., 186 units, University of Kentucky, LEXINGTON, KY. State, Div. Purchases, Frankfort, Ky. Bids Sept. 25. CD 8/31.

MIDDLE WEST

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS
BRIDGES
October 8 Connecticut October 10 Maine
STREETS AND ROADS
October 16, Ohio, Wisconsin

BUILDINGS—BA

▲ **Ill., Chicago**—SCHOOL—BA 10/16—Franciscan Sisters, 3150 N. Pulaski Rd., 2 story, Madonna High School, paving, southeastern corner Belmont and Karlov St. $2,000,000. C. I. Krajewski, 225 N. Michigan Ave., archt.

Ind., Rushville—GENERATING PLANT—BA 10/25—Utility Service Bd. of Rushville, Box 112, electric generating plant, new boilers and generating unit, $849,000. Bevington-Taggart & Fowler, 738 K of P Bldg., Indianapolis, consult. engrs.

HEAVY CONSTRUCTION—LB & CA

▲† **Maxon Constr. Co., Inc.**, 2600 Far Hills St., Dayton, O., LB $7,892,512, est. $7,320,309 (7 bidders) nuclear engineering test facility, engineering test reactor bldg., light water moderate reactor capable of operation up to and incl. 10 thermal megwatts, guard house, water softening plant, site preparation, utilities, DAYTON, O. U. S. Eng., 830 W. Broadway, Louisville, Ky. Bids Sept. 25. CD 7/20.

Keno Constr. Co., 1800 Skokie Valley Rd., Highland Park, Ill., CA, $539,588, water reservoir and pumping station, PARK RIDGE, ILL. City, City Hall, Park Ridge, Ill. Bids Sept. 4. CD 9/13, under LB.

WISCONSIN—State Hy. Comn., State Office Bldg., Madison,

Wis.—**Murphy Constr. Co.**, Route 1, Black Creek, Wis., CA, $698,094. base, c. conc. 2.917 mi. Proj. T 0338 (2) and T 0338 (5), Outagamie Co.;

Wis.—**McLean-Astleford Co.**, 7701 Harriet Ave. S., Minneapolis, Minn., CA, $189,235. grading, ballast, base 5.071 mi., Proj. T 0282 (2), St. Croix Co. Bids Sept. 18. CD 9/24.

MICHIGAN—State Hy. Dpt., Stevens T. Mason Bldg., Lansing.

Denton Constr. Co., 20415 Mack Ave., Grosse Pointe, Mich. CA **$948,411**, est. $1,300,000. (8 bidders) c. conc. 5.398 mi. Fort St. extension and Toledo Expressway from intersection of Fort Allegen and Gibralter Rds. to intersection of Sibley and Fort Rds., M 82211 C2-U (SP 82-191), M 82211 C3-R (SP 82-191), Wayne Co. Bids Sept. 19. CD 9/13.

BUILDINGS—LB & CA

▲ **Duffy Constr. Co.**, 50 Public Square, Cleveland, O. CA Est. **$2,000,000**. general constr. LAMP GLASS ADMINISTRATION and ENGINEERING BLDG., RICHMOND HEIGHTS, O. General Electric Co., 202 State St., Schenectady, N. Y. Bids Aug. 31. CD 8/14.

▲ **George A. Rutherford Co. Inc.**, 2725 Prospect Ave., Cleveland, O. CA general constr. QUARTZ MANUFACTURING BLDG., WILLOUGHBY, O. Est. **$1,000,000-$1,500,000**. General Electric Co., 202 State St., Schenectady 5, N. Y. Bids Aug. 28. CD 8/14;
Grant Electric Co., Inc., 3016 Payne Ave., Cleveland, O. CA electrical work (Willoughby, O.);
Spohn Heating & Ventilating Co. Inc., 1775 E. 45 St., Cleveland, O., CA, mechanical (Willoughby, O.).

Sumner Sollitt Co., 307 N. Michigan Ave., Chicago, Ill., CA, Est. **$800,000** design and construct 2 story, bsmnt., 52x78 ft. LABORATORY, 40x120 ft. OFFICES, 1 story, bsmnt., 60x202 ft. PROCESSING BLDG., HAMMOND, IND. Standard Oil of Indiana, 2400 New York Ave., Hammond, Ind. CD 5/31.

▲ **Hagerman Constr. Co.**, 403 Strauss Bldg., Fort Wayne, Ind., LB **$1,000,000**. 1 and 6 story, part bsmnt. STUDENT CHAPEL, VALPARAISO, IND. University of Valparaiso, Valparaiso, Ind. Bids Sept. 17. CD 8/30.

▲ **Klefstad Eng. Co.**, 4444 W. Montrose St., Chicago, Ill., Owner Builds, **$1,800,000**. design and construct 1 story, 165,000 sq. ft., brick, steel PLANT with 2 story air-conditioned OFFICE section, 8220 Austin Ave., MORTON GROVE, ILL. Radiant Mfg. Co., lessee.

B. W. Handler Constr. Co., 223 W. Jackson Blvd., Chicago, Ill., CA, **$900,000**. 1 story OFFICE, NILES, ILL. Greyhound Motors & Supply Co., 5700 Jarvis Ave., Niles, Ill. CD 6/12.

Fullerton Constr. Co., 19156 Filer St., Detroit, Mich. CA Est. **$800,000**. JUNIOR HIGH SCHOOL, CLINTON, MICH. Bd. Educ., Clinton Valley Schools, Thomas G. Lightbody, secy., Clinton, Mich. Bids Sept. 5. CD 8/16.

O. W. Burke Co., 1032 Fisher Bldg., Detroit, Mich. CA **$624,345**. general constr. HOSPITAL addn., East Jefferson Ave., DETROIT, MICH. Deaconess Hospital, 3245 E. Jefferson Ave., Detroit 7, Mich. CD 9/6, under LB.

▲† **Birchard & Roberts**, 23931 Kean Ave., Dearborn 7, Mich. CA **$1,175,000**. SCHOOL addns., incl. Lathers. Street School, Burger Junior High School, South Junior High School No. 2, Burger Junior High School No. 2, South Junior High School No. 1, GARDEN CITY, MICH. City Pub. Schools, William Fischer, secy., Bd. Educ., 29128 Dover St., Garden City, Mich. Bids Aug. 28. CD 8/6, and 8/10.

WEST OF MISSISSIPPI

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS
BRIDGES
October 18 Texas
STREETS AND ROADS
October 11 Kansas October 17, 18 Texas

BUILDINGS—BA

▲ **Okla., Oklahoma City**—HIGH SCHOOL—BA 10/11—Bd. Educ., 900 N. Klein St., John Marshall High School addn. $1,000,000. Hudgins, Thompson & Ball, 1411 Classen St., archts. CD 3/30.

Minn., St. Paul—RESIDENCE HALLS—BA 10/18—Regents of Univ. of Minn., C. A. Smith, purch. agt., 404 Admin. Bldg., Minneapolis Campus, married students' residence halls, 100 apartments, on St. Paul Campus, $785,000. Plans deposit $25. Magney, Tusler & Setter, 303 Roanoke St., Minneapolis, archts. CD 10/12.

Minn., Kasson—SCHOOL—BA 10/24—Bd. Educ. Joint Indpt. Consolidated School Dist. No. 90, Dodge and Olmsted Counties, C. E. Palmer, clk., 1 story U shaped high school between Kasson and Mantorville, $800,000. Plans deposit $30. Swanson, Matson & Wegleitner, 500 Sexton Bldg., Minneapolis, archts. CD 4/16.

Wyo., Cody—AUDITORIUM—BA 10/25—School Dist. No. 6, 1 story, 150x240 ft. brick bldg. for auditorium and gymnasium $750,000. Tresler & McCall, 1276 Sheridan St., engrs.-archts. CD 6/29/55.

HEAVY CONSTRUCTION—LB & CA

S. R. Brunn Constr. Co., 206 Rainbow St., Kansas City, Mo. LB **$619,000**. 2 hangars on west side Municipal Air Terminal, KANSAS CITY, MO. City, City Hall, Kansas City, Mo. Bids Sept. 21. CD 9/6/54.

▲† **Stupp Brothers Bridge & Iron Co.**, 3800 Weber Rd., St. Louis, Mo. LB **$1,297,809**, est. $1,166,567. superstructure for Long Creek Bridge connected with relocation of Hy. 87 around Table Rock Dam, Branson, Mo., MISSOURI and ARKANSAS. U. S. Eng., P. O. Box 867, Little Rock, Ark. Bids Sept. 19. CD 8/27.

Announcing

Milcor Ribform

...a new, stronger form for short-span concrete slabs

Milcor Ribform is a new, permanent, high-strength steel form for concrete floor-and-roof-slabs poured over steel joists or beams. It is quickly laid in sheets and welded to the steel supports where it becomes a rigid, non-porous base for the concrete.

This newest addition to Milcor's growing family of quality building products is fabricated from a high-tensile steel and has a unique ribbed shape that is stronger than ordinary corrugated patterns.

Being a rigid type of centering, Ribform never need be stretched during installation. It cannot twist or deform the joists. No expensive temporary bracing is required.

Ribform can be used to form concrete slabs over pipe trenches or other inaccessible locations where it is impractical and expensive to "strip" wood forms.

Send for Technical Bulletin 2.5.11.

MILCOR® Ribform



Ribform is easy to handle. Just weld it to the joists —the rigid sheets need no supplementary bracing.

INLAND

INLAND STEEL PRODUCTS COMPANY
DEPT. J, 4147 W. BURNHAM ST. • MILWAUKEE 1, WISCONSIN
BALTIMORE • BUFFALO • CHICAGO • CINCINNATI • CLEVELAND
DALLAS • DENVER • DETROIT • KANSAS CITY • LOS ANGELES
MILWAUKEE • MINNEAPOLIS • NEW YORK • ST. LOUIS

M-176A

† **Wm. G. Cook Constr. Co.**, Box 8466, Jackson, Miss. CA $860,120, est. $927,665. constr. Missouri River Agricultural Levee Unit 497-L located along left bank of Missouri River, near Forest City, Holt Co., Eng. 57-9, MISSOURI. U. S. Eng., Federal Office Bldg., Kansas City, Mo. Bids Sept. 18, awarded Sept. 19. CD 9/25, under LB.

† **McCormick-Erling Co.**, 633 1st Ave. N., Fargo, N. D. LB $849,623, Schedule 1; LB $826,678, Schedule 1a, (5 bidders) airfield paving (ANG), Hector Field, Inv. 25-066-57-16, FARGO, N. D. U. S. Eng., 1709 Jackson St., Omaha, Neb. Bids Sept. 21. CD 9/7.

▲ **TEXAS**—State Hy. Dpt., Austin,
Killian-House Co., 4600 Broadway, San Antonio, Tex. CA $1,096,093. grading, paving 3.249 mi. Hy. Loop 13, Proj. F 1075 (6), Bexar Co. Bids Sept. 11. CD 9/24, under LB.

Markham & Brown and McCullum & Larson, 1961 N. Industrial Blvd., Dallas, Tex. CA $893,210. dam and spillway, relocation farm to market road 1971, CARTHAGE, TEX. Panola Co. Fresh Water Dist. 1, c/o W. C. Smith, Carthage, Tex. Bids Sept. 6. CD 9/14, under LB.

† **Commercial Contracting Co.**, Port Lavaca, Tex. CA $760,000. radar unit, Matagorda Bay area, PALACIOS, TEX. Dpt. Air Force, The Pentagon, Wash. 25, D. C. CD 12/14/55.

BUILDINGS—LB & CA

G. I. Johnson & Son Co., 848 W. 79 St., Minneapolis, Minn. LB $988,400. (8 bidders) general constr. first unit, ADMINISTRATION-HOSPITAL BLDG., BRAINERD, MINN. State Dpt. Admin., 19 State Capitol, St. Paul, Minn. Bids Sept. 21. CD 8/29.

▲ **Standard Constr. Co.**, 250 Builders Exchange Bldg., Minneapolis, Minn. LB $1,721,400. (6 bidders) general constr. two BUILDING addns. at Cambridge State School and Hospital, CAMBRIDGE, MINN. State, Dpt. Admin., 19 State Capitol, St. Paul, Minn. Bids Sept. 19. (Correction-location of project). CD 9/24, under Mass., Cambridge.

▲ **Joseph H. Vatterott, Inc.**, 1500 S. Florissant Rd., Florissant, Mo. Owner Builds. $1,250,000. 123 addnl. brick, concrete RESIDENCES, in Grenoble Subdivision off Derhake Rd., adjacent to Washington Ave., FLORISSANT, MO.

Gast Building & Realty Co., 7930 Croydon St., St. Louis 14, Mo. Owner Builds. $700,000. 38 addnl. RESIDENCES in Briarwood subdivision adjacent to Daniel Boone Parkway off Warson Rd., LADUE (ST. LOUIS 24 P.O.), MO.

▲ **L. J. Wenneker Constr. Co.**, 8400 Clayton Rd., Ladue 24, Mo. CA Est. $1,250,000. 97 RESIDENCES, Tanglewood Subdivision off 8400 Clayton Rd. and 8800 Ladue Rd., LADUE (ST. LOUIS 24 P. O.), Mo. Burt Wenneker, 1 Ladue Forest, Ladue 24, Mo.

▲ **Vescovo Building & Realty Co.**, 9620 Gravois Rd., Affton 23, Mo. Owner Builds. $1,800,000. 240 one story, bsmt. RESIDENCES in Maple Hills subdivision on Green Park Rd. south of Union Rd., LEMAY (ST. LOUIS 23 P. O.), MO.

▲ **Glick-Kaiser, Inc.**, 9617 Olive Street Rd., St. Louis 24, Mo. Owner Builds. $1,750,000. 175, full bsmnt. RESIDENCES in 197 acre Indian Meadows Subdivision 9500 Olive Street Rd., OLIVETTE (ST. LOUIS 14 P. O.), MO.

▲ **B & S Constr. Co.**, 4 Watson Court, St. Louis 24, Mo., Owner Builds. $1,200,000. 44 RESIDENCES of Williamsburg type on Conway Rd., ST. LOUIS COUNTY, MO.

▲ **Michael Macken & Co.**, 8614 Watson Rd., St. Louis County 23, Mo. Owner Builds. $1,000,000. 20 or more RESIDENCES in Bridle Trail Meadows subdivision ¼ mi. west of Lindbergh Blvd. off Gravois Rd., ST. LOUIS COUNTY, MO.

▲ **Parkchester Development Co.**, Sulphur Springs Rd. south of Manchester Rd., St. Louis County, Mo. Owner Builds. $1,850,000. 185 RESIDENCES, Winston Park subdivision, ST. LOUIS COUNTY, MO.

▲ **Riegel Development Co.**, Bellefontaine Rd. and Trampe Lane, St. Louis County 15, Mo. Owner Builds. $1,500,000. 170 RESIDENCES in Broadlawns subdivision off Trampe lane adjacent to Criterion Ave., ST. LOUIS COUNTY, MO.

Suburban Building Co., 441 Dickens St., Kirkwood 22, Mo. CA Est. $900,000. 80 addnl. RESIDENCES in Sturdy Estates subdivision off Sturdy Dr. and Maebern Terrace south of U. S. No. 66, ST. LOUIS COUNTY, MO. Preferred Homes, Inc., Ed. R. Linn, pres., 1405 Robin Hood Court, Kirkwood 22, Mo.

L. J. McNeary Realty & Constr. Co., 9715 Gravois Rd., Affton 23, Mo. Owner Builds. $950,000. 106 brick, RESIDENCES in Sappington Acres Estates No. 2, SAPPINGTON (ST. LOUIS 23 P. O.), MO.

▲ **Michael Macken & Co.**, 8614 Watson Rd., St. Louis 23, Mo. Owner Builds. $2,250,000. 100 RESIDENCES in Webster Gardens south of U. S. 66 and west of Elm Ave., WEBSTER GROVES (ST. LOUIS 19 P. O.), MO.

▲ **Assenmacher Constr. Co.**, 627 N. 17 St., Lincoln, Neb. CA $2,000,000. general constr. incl. mechanical and electrical home OFFICE, Cotner Blvd. and O Sts., LINCOLN, NEB. Bankers Life Insurance Co. of Nebraska, 1345 "N" St., Lincoln, Neb. Bids Sept. 7. CD 8/15.

Henger Constr. Co., 1600 Simmons Bldg., Dallas, Tex. CA $682,600. HOSPITAL expansion DALLAS, TEX. Parkland Memorial Hospital, 5201 Harry Hines Blvd., Dallas, Tex. CD 9/26, under LB.

Thad Dederick Constr. Co., Box 13067, Houston, Tex. LB $664,000. M.D. Anderson HOSPITAL and Tumor CLINIC alterations and expansion in Medical Center, HOUSTON, TEX. University of Texas, Bd. Regents, Austin, Tex. MacKie & Kamrath, 2713 Ferndale St., Houston, Tex. archts. Walter P. Moore, 2 Pinedale St., and R. L. Jenkins, 2622 Richmond St., Houston, Tex. engrs. Bids Sept. 18. CD 8/28.

Herman Weber, Inc., 800 N. Pearl St., Beaumont, Tex. LB $516,000. Southside Elementary SCHOOL; LB $438,995, Westside and Northside Elementary SCHOOLS, SILSBEE, TEX. Silsbee Independent School Dist., Silsbee, Tex. Bids Sept. 13. CD 9/5.

FAR WEST

HEAVY CONSTRUCTION—BA

▲† **Washington**—BA 11/28—U. S. Eng., City-County Airport, Walla Walla, south shore constr., Ice Harbor Lock & Dam, Walla Walla and Franklin Counties, CIVENG-45-164-57-16. Plans deposit $200.

BUILDINGS—BA

Calif., Sacramento—SCHOOL—BA 10/15—Sacramento City Unified School Dist. c/o supt. 16th and N Sts., Joaquin Miller Junior High School addn. $800,000. Plans deposit $25. Baravetto & Thomas, 718 Alhambra Blvd., archts. CD 7/14/55.

HEAVY CONSTRUCTION—LB & CA

ARIZONA—State Hy. Dpt., 1739 W. Jackson St., Phoenix.
Isbell Constr. Co., 2808 N. 27 Ave., Phoenix, Ariz., CA, $741,571, base, bit. paving 5.8 mi. divided hy., State Route 86-Benson-Stelns Pass Hy., Cochise Co. Bids Aug. 30. CD 9/5, under LB.

† **Transocean Eng. Corp.**, 7807 Russell City Rd., Hayward, Calif., CA $869,631, Schedules 1 and 2 county road relocation for Trinity dam, access road for Lewiston Spring Creek tunnel, and piers, abutments and approach for Trinity River bridge, Central Valley Proj., Trinity River Div., Spec. DC 4737. CALIFORNIA. Bureau Reclamation, Dpt. Interior, Weaverville, Calif. Bids Aug. 30. CD 9/6, under LB.

▲ **CALIFORNIA**—State Div. Hys., 1120 N St., Sacramento,
A. Teichert & Son, Inc., 1931 Stockton Blvd., Sacramento, Calif., CA, $1,847,302. grading, paving 6.8 mi. 4-lane divided highway, underpass and bridge, existing underpass alteration between Mossdale and Richards Ave. on U.S. 50 and Sign Rte. 120, San Joaquin Co. Bids Sept. 5, awarded Sept. 20. CD 9/10.

† **San Francisco Bridge Co.**, 140 Montgomery St., San Francisco, Calif., CA, $740,229 dredging in Richmond Harbor, Richmond, Contra Costa Co., CIVENG-57-1, CALIFORNIA. U. S. Eng., 100 New Montgomery St., San Francisco, Calif. CD 8/22, under LB.

▲ **Guy F. Atkinson Co.**, Box 459, Long Beach, Calif., LB $8,176,489 (6 bidders) constr. Ninth St. Bridge over Los Angeles Flood Control Channel, LONG BEACH, CALIF. Long Beach Bd. Harbor Comrs., 1333 El Embarcadero, Los Angeles, Calif. Moffatt & Nichols, 122 W. 5 St., Long Beach, Calif., engrs. Bids Sept. 11.

BUILDINGS—LB & CA

▲ **Hilp & Rhodes**, 299 Kansas St., San Francisco, Calif. CA, Est. $20,000,000. 650,000 sq. ft. rein.-con. SHOPPING CENTER, 68-stores, 6,000 car parking facility, 54-acre site, OGDEN, UTAH, Hilp & Rhodes Realty Corp., 299 Kansas St., San Francisco, Calif. CD 9/17.

North Kitsap School Dist. 400, Poulsbo, Wash. rejected bids Aug. 22, HIGH SCHOOL, POULSBO, WASH. LB $977,621. Will re-advertise. CD 8/30, under LB.

▲ **H. Halvorson, Inc.**, Ziegler Bldg., Spokane, Wash., CA $935,924. general contract two 5 story RESIDENCE HALLS for Women, PULLMAN, WASH. Washington State College, Pullman, Wash. Bids Aug. 31, awarded Sept. 22. CD 9/7, under LB;
J. G. Watts Constr. Co., Salem, Ore., CA $525,440. general contract 9 frame, 2 story each married student's HOUSING buildings, (Pullman, Wash.).

Cawdrey & Vemo, 3601 Fremont Ave., Seattle 3, Wash., CA $719,510 (5 bidders) general contract 5 story, 60,000 sq. ft., rein.-con. CLASSROOM BLDG., SEATTLE, WASH. Seattle University, Broadway and E. Madison St., Seattle, Wash. Bids Sept. 21. CD 9/18.

Crown Constr. Co., 5059 W. Pico Blvd., Los Angeles, Calif., LB $944,514 (4 bidders) second increment at Azusa HIGH SCHOOL, AZUSA, CALIF. Citrus Union High School Dist., 18824 E. Foothill Blvd., Azusa, Calif. Bids Aug. 31. CD 8/7.

▲ **R. J. Daum Constr. Co.**, 12537 S. Cerise Ave., Hawthorne, Calif., CA $1,049,566. new SCHOOL and Hoffman and Rockwood SCHOOLS addns., CALEXICO, CALIF. Calexico School Dist., 7 and Herber St., Calexico, Calif. CD 8/21, under LB.

▲ **Robert E. McKee General Contractors, Inc.**, 4701 San Fernando Rd. West, Los Angeles, Calif., CA, $2,530,000. general contract HOSPITAL ADMINISTRATION and ACUTE INFIRM WARDS, Fairview State Hospital, COSTA MESA, CALIF. State Div. Architecture, 1120 N St., Sacramento, Calif. CD 4/24.

Howard J. White, Inc., 870 Charlestone Rd., Palo Alto, Calif., LB $749,037. (8 bidders) 2 Elementary SCHOOLS, Eisenhower Elementary SCHOOL, Garden Gate Elementary SCHOOL, frame, stucco constr. CUPERTINO, CALIF. Cupertino Union Elementary School Dist., c/o supt., P. O. Box 155, Cupertino, Calif. Bids Sept. 18. CD 8/30.

Carl O. Larsen, 1246 S. Main St., Santa Ana, Calif., LB $712,160. (10 bidders) Proj. 20, 45,000 sq. ft., INTERMEDIATE SCHOOL, GARDEN GROVE, CALIF. Garden Grove School Dist., Garden Grove, Calif. Bids Sept. 21.

Haas, Haynie & Frandsen, 8913 Olympia Blvd., Beverly Hills, Calif., CA, $751,000. 130,000 sq. ft. coffee processing and packaging PLANT, LENNOX, CALIF. J. A. Folger Co., 101 Howard St., San Francisco, Calif. Quinton Engineers Ltd., 812 W. 8 St., Los Angeles, Calif., engrs.

▲ **MacDonald Young & Nelson**, 600 California St., San Francisco, Calif., CA Est. $1,500,000. (10 Bidders) GROCERY WAREHOUSE and TRUCK REPAIR SHOP, RICHMOND, CALIF. Safeway Stores, Inc., 366 Grand Ave., Oakland, Calif. Bids Sept. 18. CD 8/29.

Wm. Simpson Constr. Co., 2401 W. Beverly Blvd., Los Angeles, Calif., CA $800,000. 2 story 96x130 ft. concrete PLANT OFFICE, 1700 Main St., SANTA MONICA, CALIF. Rand Corp., 1700 Main St., Santa Monica, Calif.

CANADA

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS
STREETS AND ROADS
October 10 Ontario

HEAVY CONSTRUCTION—LB & CA

▲ **BRITISH COLUMBIA**—B. C. Govt., Parliament Bldgs., Victoria,
Highway Constr. Co. Ltd., 836 River Rd., Lulu Island, Vancouver, B. C., LB $2,321,039 (2 bidders) constr. 4.62 mi. Trans-Canada Hy., Bell Crossing-Saddle Rock Sect., Proj. 792. Bids Sept. 14. CD 9/7.

▲ **Dominion Bridge Co. Ltd.**, Lachine, Que., CA $3,031,097, superstructures 2 vertical lift bridges near Caughnawaga in Lachine Section, QUEBEC, St. Lawrence Seaway Auth. No. 2 Temporary Bldg., Ottawa, Ont. Bids Aug. 28. CD 9/4, under LB.

▲ **Atlas-Winston Ltd.**, 4781 St. Catherine St. W., Montreal, Que., CA $3,259,525. excavation of channel and constr. dyke, Station 900 plus 00 to 930 plus 00, embankments and CPR bridge substructure Lachine Section, QUEBEC, St. Lawrence Seaway Auth., No. 2 Temporary Bldg., Ottawa, Ont. Bids Aug. 21. CD 8/27, under LB.

BUILDINGS—LB & CA

▲ **Fluor Corp. of Canada Ltd.**, 200 Bloor St. E., Toronto, Ont., CA $3,800,000 design and construct, detergent alkylate PLANT, SARNIA, ONT. Imperial Oil Co., 56 Church St., Toronto, Ont. CD 2/6.

LATIN AMERICA

HEAVY CONSTRUCTION—BA

▲ **Brazil, Sao Paulo**—SUBWAY—BA 10/15—Municipal Comn. Collective Transport, Sao Paulo, construct subway, incl 100 kilometers track and 100 stations. CD 7/1/48.

HEAVY CONSTRUCTION—LB & CA

Empresa Constructora, Lima and Piura, Peru, CA constr. whaling station for processing sperm oil and other products, comprising flensing deck, warehouse, storage tanks, etc., near PAITA, PERU. Archer-Daniels-Midland Co., Investors Bldg., Minneapolis, Minn, U. S. A., and Peruvian Interests.

U. S. POSSESSIONS

BUILDINGS—LB & CA

▲ **Theo. G. Meyer & Sons**, 200 Quint St., San Francisco, Calif. LB $21,504,993. construct and finance, 1,326 units (Capehart) HOUSING, Schofield Barracks, HONOLULU, T. H. U. S. Eng., Box 2240, Honolulu, T. H. Bids Sept. 19. CD 8/13.

FOREIGN

HEAVY CONSTRUCTION—BA

▲ **India, Bombay**—BA 10/23—At office K. V. Ekambaram, ch. engr., Kosi Proj., Patna, (Bihar), constr. Hanumannager Barrage, Kosi Proj. at Bihar, North East India. Proj. includes main and diversion spillways, intervening and guide bunds, two earth dams, for Govt. of India, Bombay. $19,000,000.

Australia—BA 1/29—Country Roads Board, Exhibition Bldg., Carlton, Melbourne, Australia, (1) bridge over Yarra River, 410 ft. long, 149 ft. wide, of which the central portion (63 ft. over-all width) is continued as an elevated structure for an addnl. length of 1,880 ft., (2) vehicular and tramway overpass in Flinders St., 600 ft. long and 58 ft. between kerbs, in Melbourne and South Melbourne. Plans deposit £100.

HEAVY CONSTRUCTION—LB & CA

▲ **Vianini (Liberia) Ltd.**, Monrovia, Liberia, LB $6,124,533, (concrete pipe); LB $5,925,066 (metal pipe) (2 bidders), constr. Gbarnaga-Kailahun Projects SH1-B (2), SH 1-C, SH 1-D and SH 1-E, approx. 144.6 mi. Liberian Govt. Highways Program in Western Province, LIBERIA. Dpt. P. Wks. & Utilities, c/o Secy., Monrovia, Liberia. Bids Aug. 15. CD 6/22.

(Proposal Advertisement see pp. 150 to 153)

Another **Big Office Building**

by

AMERICAN BRIDGE

This imposing 30-story steel-frame structure is the latest New York office building to be fabricated and erected by American Bridge. Known as 425 Park Avenue, it fronts 201 feet on the avenue, 146 feet on Fifty-fifth Street and 132 feet on Fifty-sixth Street.

Approximately 5,900 tons of structural steel went into its framework. Field connections were made with high strength bolts, regular bolts and welding—which held construction noises to a minimum.

Working in crowded areas like this is routine to American Bridge. From the old Flatiron Building in 1901, to the Empire State Building in 1930, to the Socony Mobil Building in 1956, American Bridge has become more and more dexterous in handling big jobs in big cities.

The experience thus acquired over the past fifty-five years qualifies American Bridge to handle any type of structural steelwork with skill and speed. For more information concerning our ability to help you with your construction problems, contact the nearest office, or write direct to our Pittsburgh headquarters.

AMERICAN BRIDGE DIVISION, UNITED STATES STEEL CORPORATION
GENERAL OFFICES: 525 WILLIAM PENN PLACE, PITTSBURGH, PA.
Contracting Offices in: AMBRIDGE • ATLANTA • BALTIMORE • BIRMINGHAM
BOSTON • CHICAGO • CINCINNATI • CLEVELAND • DALLAS • DETROIT • DENVER
ELMIRA • GARY • HOUSTON • LOS ANGELES • MEMPHIS • MINNEAPOLIS • NEW YORK
ORANGE, TEXAS • PHILADELPHIA • PITTSBURGH • PORTLAND, ORE. • ROANOKE
ST. LOUIS • SAN FRANCISCO • TRENTON
UNITED STATES STEEL EXPORT COMPANY, NEW YORK

The
425 Park Avenue
Building
Manhattan, New York City

• • •

Designed by
Kahn and Jacobs, Architects, and
Charles Mayer, Engineer

• • •

General Contractor
George A. Fuller Company

INTERESTING MOTION PICTURES AVAILABLE—"Building for the Nations" and "The Suspension Bridge," two entertaining and educational films, are now available without charge to business, fraternal and civic organizations, churches, schools and colleges. Write to Pittsburgh office for bookings.

USS

UNITED STATES STEEL

Construction Scoreboard

Activity this Week

* 6 Day Week in 1955

AMOUNT OF CONTRACTS LET

By Ownership	This Week	Cum. 40 wks 1956	Chge %
	$ millions		
Federal	$46.6	$1,367.5	+5
State and Municipal	199.3	5,052.0	+21
Total Public	245.9	6,419.5	+17
Total Private	245.1	10,579.1	+16
U. S. Total	$491.0	$16,998.6	+16
By Type of Work			
Waterworks	$14.4	$276.4	+33
Sewerage	14.7	470.9	+51
Bridges	21.5	472.1	+24
Highways	71.8	1,901.9	+11
Earthwork, Waterways	32.9	611.4	+49
Buildings:			
Public, Excl. Housg.	45.9	1,587.5	+19
Public Housing	23.7	268.5	+22
Private Housing	103.9	4,356.7	−12
Commercial	84.2	1,496.6	+15
Industrial	51.7	4,199.5	+93
Unclassified	26.3	1,357.1	−15
U. S. Total	$491.0	$16,998.6	+16

NOTE: Minimum size projects included are: Waterworks and waterways, $44,000; other public works, $73,000; industrial buildings, $93,000; other buildings, $344,000.

NEW CAPITAL FOR CONSTRUCTION

	Week of Sept. 27	Cum. 39 wks 1956	Chge '55-'56 %
	$ millions		
Corporate Securities	$68.8	$3,784.2	+45
State and Municipal:			
All Except Housing	101.3	3,398.0	+10
Housing	...	42.3	−41
Federal Loans	...	125.7	+16
Federal Aid	...	1,070.0	+25
Total Nonfederal	$170.1	$8,420.1	+25
Federal Appropriations:			
In U. S.	$...	$3,460.3	+2
Outside U. S.	...	15.9	−81
Total New Capital	$170.1	$11,896.3	+17

Cost Indexes as of Now

ENR INDEXES (1913 = 100), 20-cities' average	Week of Sept. 27, 1956	% Change from Aug. 30, 1956	% Change from Sept. 29, 1955
Construction Cost	703.88*	−0.15	+4.5
Building Cost	499.54*	−0.1	+4.1

* Official Monthly Index for October.

To convert above indexes to 1926 = 100: Divide Construction Cost by 2.080; Building Cost by 1.850. 1949 = 100: Divide Construction Cost by 4.770; Building Cost by 3.518.



WAGE RATES, 20-cities' average	Sept. 1956	% Change from August 1956	% Change from Sept. 1955
Common	$2.192	0	+4.7
Skilled (average 3 trades)	3.423	+0.2	+4.2
Bricklayers	3.695	+0.2	+4.3
Structural Ironworkers	3.399	+0.2	+3.8
Carpenters	3.175	+0.2	+4.5
MATERIAL PRICES, 20-cities' average			
Structural Steel (average 3 mills), per cwt	$5.000	0	+8.7
Lumber, 2x4 Fir, per M fbm	117.290	−1.2	−3.2
Lumber, 2x4 Pine, per M fbm	103.330	−0.8	+2.5
Cement, bulk, per bbl	3.750	+0.8	+5.5
Sand, per ton	2.411	+0.1	+1.6
Ready-mixed concrete, per cu yd	13.430	0	+6.3

ENR INDEX REVIEW

	Construction Cost 1913 = 100	Construction Cost 1949 = 100	Building Cost 1913 = 100	Building Cost 1949 = 100	Volume 1913 = 100	Volume 1949 = 100
1955						
Oct.	673.89	141.27	479.99	136.44	628	182
Nov.	673.20	141.13	479.30	136.25	561	162
Dec.	673.13	141.11	478.70	136.08	544	157
1955 Av.	659.72	138.31	468.80	133.33	600	173
1956						
Jan.	676.36	141.79	480.48	136.58	645	186
Feb.	680.21	142.59	483.08	137.32	736	213
Mar.	680.20	142.59	488.14	137.34	786	227
Apr.	683.28	143.24	485.56	138.02	764	221
May	688.43	144.32	487.36	138.54	684	198
June	692.13	145.09	488.70	138.92	636	184
July	694.75	145.64	489.23	139.07	740	214
Aug.	696.31	145.97	491.22	139.63	583	168
Sept.	704.91	147.77	500.10	142.16	580	168
Oct.	703.88	147.56	499.54	142.00	...	...

MATERIAL SHORTAGES

- **Brick**—Still short in Birmingham; now plentiful in Los Angeles.
- **Cement**—Short in Baltimore, Denver, Toronto. Now adequate in New Orleans.
- **Stainless steel building sheets**—Birmingham deliveries, 6-8 months; Boston, one week for regular customers, December or January for new customers; Denver, four months for rated orders, six to eight months for non-rated orders; Philadelphia, to three months; San Francisco, 30-45 days; Seattle, 90-120 days; Montreal, to 40 days; Toronto, to 126 days; Minneapolis and New York, slow deliveries.
- **Aluminum building sheets, flat**—Short in Denver, New Orleans, Montreal, Toronto taking no new customers.
- **Aluminum corrugated roofing**—Short in Denver and Montreal.

Awards Set September Record

Industrial building bounces back, federal work is nearly double last month, and commercial building jumps ahead

Heavy construction contract awards, as reported by ENGINEERING NEWS-RECORD and CONSTRUCTION DAILY, set a new record for the month of September.

Contracts totaled $1,480 million for the month. The $370-million per week pace was nearly 4% above the rate for September 1955.

Industrial building contracts bounced back from their August slump to average $90 million a week, more than double the September 1955, rate. But even this was well below the high volumes posted in March, April, May and July of this year when contracts ranged from $120 million to $160 million a week.

Other types of construction also showed strong gains last month.

Commercial building awards shot up to an average of $49 million a week—about equal to the year's peak rate (set in January). Contributing to last month's total was a $75-million office building to be built in New York City for Vincent Astor.

Federal construction awards were more than double the low August pace, averaging $34 million a week. Although this volume was not unusually large, it helped to pull the federal award total—on a cumulative basis—into the "plus" column. At the end of the first nine months, federal awards are 2% ahead of the same period last year.

Highway awards dropped in September. This was reflected in the overall decline in state and municipal contract awards, which were down for the third consecutive month. This was true even though the $113 million a week average in municipal contracts was nearly 4% higher than September 1955—and was the best September on record in terms of average weekly volume.

Earlier this year, state and municipal awards started off far ahead of 1955 but the margin of gain has been shrinking rapidly. May and June awards were 20% to 27% ahead of 1955; July was up 18%; August, 11% and September, up only 4%.

Several municipal contract categories were strong, however, last month. These included sewerage, earthwork-irrigation-drainage, bridges, public housing and other public buildings. All of these topped the August award rate. However, waterworks contracts slipped to the lowest level of the year.

Housing volume was disappointing in September. The sharp upturn in August contracts for private mass housing was followed by an even sharper downturn in September.

This drop is significant because September is generally a strong month for housing awards, which follow a U-shaped seasonal pattern with a big spring, a drop in the summer, and then another upsurge in the fall.

This year, the September average weekly rate plummeted to $71 million, 41% under September 1955, and the lowest rate in two years.

ENR Cost Indexes Steady; Lumber Dips; Cement Rises

Weakness in the lumber market led to a further softening of lumber prices this month. Douglas fir prices were down 1.2%; southern pine was down .8%. These declines offset cement price increases in four eastern cities and kept ENR Construction and Building Cost Indexes relatively steady.

The ENR Construction Cost Index edged down 0.15% during the month, from a September value of 704.91 to an October reading of 703.88 on the same basis, the ENR Building Cost Index creeped down from a September figure of 500.10 to an October reading of 499.54, both indexes are based on 1913 equals 100.

Boston, New York and Philadelphia reported price increases of 15 cents a barrel for cement, while the mill price in Baltimore moved up 19 cents. The increases took effect Oct. 1.

(*B&F continued on page 142*)

Engineering Construction Contracts September 1956

ENGINEERING NEWS-RECORD *reports continental U. S. Construction projects of the following minimum costs—Waterworks, excavation, drainage and irrigation,* $44,000; *other public works,* $73,000; *industrial buildings,* $93,000; *other buildings,* $344,000

Four Weeks—Thousands of Dollars (000 Omitted)

	September, 1956							U. S. Cumulative		%	Canada
	New England	Middle Atlantic	South	Mid-West	West of Mississippi	Far West	Total U. S.	Nine Months 1956	Nine Months 1955	Change '55 to '56	September 1956
Public Works											
Waterworks	608	1,351	5,010	3,470	3,778	2,801	17,018	262,174	205,061	+28	1,252
Sewerage	838	6,260	8,807	12,578	10,946	9,902	49,430	456,370	300,936	+52	5,014
Bridges	3,147	4,267	6,980	17,606	5,291	4,325	41,616	446,556	357,081	+25	7,620
Earthwork and waterways	8,536	5,533	10,589	5,523	8,934	21,129	60,244	578,356	406,647	+42	18,279
Streets and roads	7,717	27,975	36,221	32,111	51,293	20,700	176,017	1,829,935	1,662,296	+10	12,677
Public buildings, residential	984	965	9,344	7,300	6,572	1,444	26,699	244,541	229,318	+11	7,190
Other public buildings	13,222	22,028	37,178	35,768	30,442	17,938	156,576	1,841,477	1,311,572	+18	16,255
Unclassified	3,776	4,376	12,174	5,624	30,161	4,119	60,230	814,175	878,241	− 7	6,115
Total Public	**38,828**	**72,764**	**126,393**	**120,070**	**147,417**	**82,358**	**587,830**	**6,173,584**	**5,342,152**	**+16**	**74,402**
Federal government (included in above classifications)	7,418	5,575	47,516	8,324	39,118	27,805	135,756	1,320,746	1,280,102	+ 2	31,567
Private											
Bridges	.....	.....	.....	.....	.....	.....	.....	4,404	1,829	+141	.....
Industrial buildings	3,920	19,266	73,870	83,098	111,563	68,473	360,190	4,147,809	2,055,192	+102	20,792
Mass housing	6,652	115,580	34,033	46,919	54,180	24,726	282,090	4,253,209	4,777,739	−11	3,840
Commercial buildings	12,683	121,424	5,836	32,036	17,404	7,946	197,329	1,412,365	1,272,740	+11	8,570
Unclassified	.....	711	228	19,000	12,603	20,511	53,053	516,314	684,519	−25	339
Total private	**23,255**	**256,981**	**113,967**	**181,053**	**195,750**	**121,656**	**892,662**	**10,334,101**	**8,792,019**	**+18**	**33,541**
Total Engineering Construction:											
September, 1956—4 weeks	**62,083**	**329,745**	**240,360**	**301,123**	**343,167**	**204,014**	**1,480,492**	.....	.....	.....	**107,943**
August, 1956—5 weeks	76,153	488,823	185,248	411,392	418,098	248,778	1,828,462	.....	.....	.....	277,354
September, 1955—5 weeks	67,251	566,423	252,091	331,885	401,959	166,680	1,786,199	.....	.....	.....	146,961
Nine Months—1956	**589,506**	**4,190,768**	**1,914,100**	**3,547,270**	**3,576,138**	**2,389,971**	.....	**16,507,685**	.....	**+17**	**1,765,651**
Nine Months—1955	676,815	3,954,746	1,540,648	3,109,125	3,296,703	1,555,134	.....	.....	14,134,171	.....	1,266,585
% Change '55 to '56	+31	+6	+24	+14	+8	+54	.....	.....	.....	.....	+39

Consulting Engineer* New Business in 1955 – by Type of Work

As reported by ENGINEERING NEWS-RECORD and CONSTRUCTION DAILY

1,224 firms took on 4,344 heavy construction projects costing an estimated $6,492 million

Type of Work	All Engineers Number of Firms	All Engineers Number of Projects	All Engineers $ Volume Millions	Total '55 Volume of All Types $1,000,000 or More Number of Firms	$1,000,000 or More Number of Projects	$1,000,000 or More $ Volume Millions	$500,000-$1,000,000 Number of Firms	$500,000-$1,000,000 Number of Projects	$500,000-$1,000,000 $ Volume Millions	$100,000-$500,000 Number of Firms	$100,000-$500,000 Number of Projects	$100,000-$500,000 $ Volume Millions
Other Than Building												
Waterworks	296	896	$506.4	152	624	$473.2	52	109	$18.4	92	133	$15.8
Sewerage	374	941	447.1	182	659	394.0	67	123	30.3	125	159	22.8
Bridges	75	149	664.7	52	117	655.5	11	15	7.0	12	17	2.2
Highways	176	323	1,101.0	119	251	1,089.5	19	28	5.6	38	44	5.9
Earthwork, irr., drain	78	168	876.2	55	122	871.4	7	21	2.5	16	25	2.2
Airports	99	191	135.4	64	145	123.1	12	21	7.0	23	25	5.3
Unclassified	224	430	515.9	136	312	489.1	31	58	15.7	57	60	11.1
Total	...	3,008	4,246.7	...	2,260	4,094.8	...	375	86.5	...	463	65.3
Building												
Industrial buildings	264	383	1,212.3	137	242	1,177.9	30	38	14.2	97	103	20.2
Mass housing, commercial and public buildings	425	863	1,033.1	259	673	960.6	82	103	48.0	84	87	25.5
Total	...	1,346	2,345.4	...	918	2,137.5	...	141	62.2	...	190	45.7
Federal (incl in above)	103	209	353.2	67	144	336.9	18	40	11.2	18	25	5.1
All Heavy Construction	1,224	4,344	6,492.1	836	3,178	6,232.3	226	516	148.7	462	653	111.0

* Not including architect-engineers who will be reported separately.

Consulting Engineers' Business Up 5% in 1955

Dollar volume of consulting engineers' new business climbed another 5% in 1955.

They were called upon to handle a sharply higher volume of industrial plant design and the design load also increased substantially for other key types of construction.

This is clear from the latest annual ENGINEERING NEWS-RECORD and CONSTRUCTION DAILY analysis of consulting engineers' new business.

Last year, 1,224 consulting engineers took on a total of 4,344 design jobs. These projects had a total estimated cost of nearly $6.5 billion. (The survey covers only those firms starting new projects reported in ENR and CD adding up to $100,000 or more.)

There was a slight decline during 1955 in the number of consulting engineers in the $100,000-and-up class. Last year's total dipped 2% below the 1954 count.

Most of this dip—if not all—came in the number of firms active in the highway design field. The volume of new highway work received by consulting engineers was large last year, but it could not match 1954's record $2-billion rate, which reflected the peak of the toll highway era.

Offsetting the 1955 drop in new highway business were increases in industrial building, waterworks, bridges, earthwork-irrigation-drainage, and federal military airport design jobs. The result was a 5% increase from 1954 to 1955 in the estimated cost of all projects started by consulting engineering firms covered in the survey. This 5% increase in dollar value was significant because it came on top of a seam-bursting 30% rise in 1954.

Last year's high level of activity made it possible for some of the smaller firms ($100,000 to $500,000) to move up into the medium size bracket ($500,000 to $1 million). And, the group of consulting engineer firms in the million-dollar bracket stayed at 1954's high level.

There were 23% more consulting engineers—226—with total new business of $500,000 to $1 million in 1955 than in 1954. In contrast, the number of firms in the smaller $100,000 to $500,000 category shrunk 13% to a total of 530.

All three size groups shared in the 1955 upsurge in industrial building plant design contracts.

(*Continued on page 144*)

How Consultants'* New Business in '55 Compared with '54

As reported by ENGINEERING NEWS-RECORD and CONSTRUCTION DAILY

Type of Work	All Engineers Per Cent Change '54-'55 Number of Firms %	All Engineers Number of Projects %	All Engineers $ Volume %	Total '55 Volume of All Types $1,000,000 or More Per Cent Change '54-'55 Number of Firms %	$1,000,000 or More Number of Projects %	$1,000,000 or More $ Volume %	$500,000-$1,000,000 Per Cent Change '54-'55 Number of Firms %	$500,000-$1,000,000 Number of Projects %	$500,000-$1,000,000 $ Volume %	$100,000-$500,000 Per Cent Change '54-'55 Number of Firms %	$100,000-$500,000 Number of Projects %	$100,000-$500,000 $ Volume %
Other Than Building												
Waterworks	– 7	–11	+55	– 9	–14	+59	+11	+19	+33	–13	–13	– 1
Sewerage	– 4	–12	– 0.4	+ 4	–12	0	+12	– 5	+ 9	–19	–20	–16
Bridges	+ 3	+23	+111	– 9	+16	+112	+120	+150	+93	+ 9	+21	– 2
Highways	–26	–25	–46	–13	–11	–46	–27	–39	–35	–51	–57	–56
Earthwork, irr., drain	–19	+11	+27	+10	+40	+27	–12	+162	+71	–45	–55	–49
Airports	+36	+10	+ 6	+39	+ 7	+ 2	+50	+50	+126	+21	+ 4	+76
Unclassified	–16	–23	– 7	– 4	–21	– 6	+ 3	+38	+40	–40	–51	–42
Total	....	–12	– 8	....	–10	– 8	....	+11	+25	....	–31	–23
Building												
Industrial buildings	+25	+20	+79	+34	+26	+82	+20	+ 9	+ 1	+14	+12	+26
Mass housing, commercial and public buildings	+ 5	– 2	+ 9	+ 7	– 4	+ 1	+17	+17	+22	– 7	– 8	– 2
Total	....	+ 4	+33	....	+ 3	+34	....	+15	+17	....	+ 2	+ 9
Federal (incl in above)	+43	+14	+177	+52	+ 5	+179	+157	+344	+348	–15	–34	+19
All Heavy Construction	– 2	– 8	+ 5	0	– 6	+ 5	+23	+12	+21	–13	–24	–13

* Not including architect-engineers who will be reported separately.

REINFORCED CONCRETE

lowers bridge costs . . .

saves construction time



Rosepoint Multiple Span Bridge west of Butler, Pa.

Designed by Bridge Department, Pennsylvania Division of Highways.

Osborne Construction Company, Franklin, Pa., Contractors.

Make your bridge appropriation dollars go further with reinforced concrete. Time and again, comparison cost studies have proved the economy of reinforced concrete. Equally important, reinforced concrete bridges and overpasses start sooner . . . go up faster, because all necessary materials can be delivered *in a matter of days* from local stocks. These faster starts, plus the faster construction made possible with reinforced concrete, save months of delay.

Reinforced concrete has many other advantages as well. No other method of construction is so flexible. No other construction medium permits so infinite a variety of imaginative and beautiful designs.

Structures built with reinforced concrete are rugged, too . . . highly resistant to wind, shock, and quake. They are more weather resistant, and require less maintenance. On your next bridge or overpass, design for *rugged beauty plus economy* . . . design for reinforced concrete.



Compare . . .

YOU'LL SAVE WITH REINFORCED CONCRETE

CRSI

CONCRETE REINFORCING STEEL INSTITUTE

38 South Dearborn Street • Chicago 3, Illinois

(Continued from page 142)

The number of consulting engineers active in the industrial field jumped 34% for the $1 million-and-over group; 20% for the firms in the $500,000 to $1 million bracket; and 14% for those in the smaller business category.

From a dollar standpoint, the most spectacular climb was an 82% increase in the dollar value of industrial building work signed up by the $1-million-and-over group.

(This survey will be supplemented in a later issue by an analysis of new business of architect-engineer firms, which may include some building work which is not shown in the accompanying tabulation.)

Sewerage Work Goal

Department of Commerce sees $22.2 billion outlays for work in next two decades

The United States should spend $22.2 billion in the 20 years from 1955 through 1975 to build an adequate sewerage system.

That's the goal set forth by Walter L. Picton and A. T. Levie of the U. S. Department of Commerce Business and Defense Services Administration in a new study just released.

Needs of the 20-year program—projected in constant 1954 dollars—were summarized as follows:

- **$5.8 billion to eliminate present deficiencies.**
- **$8.1 billion to offset obsolescence and depreciation.**
- **$8.3 billion to provide for growth in population and the resultant increased water use.**

One of the basic projections in the study calls for a rise in population from 164,600,000 in 1955 to 206,600,000 in 1975.

Along with this, the study assumes a continued increase in population gains in cities as against rural areas (where fewer families are served by public sewerage systems).

In 1955, approximately 100,000,000 persons were served by public sewerage systems. By 1975, this figure is expected to climb to 134,000,000.

The projections on needs for sewerage construction ". . . are considered conservative with respect to population served and requirements for service, but with respect to annual construction and accumulated investment value, they present the most optimistic picture considered to be within the range of realism," Picton and Levie pointed out in their report.



PLANNED CITY of Forest Park, Ohio, is private enterprise sequel to federally-built "greenbelt" towns of 1930s, one of which lies just south of this new community.

10,000-Home City Now Under Way

Depression-inspired community planning by the federal government has a direct link to a 10,000-home completely-planned city officially "opened" last week 13 mi north of Cincinnati.

The new city-Forest Park—is separated only by a heavily-wooded county park from its publicly built predecessor —Greenhills, a 700-acre development (represented by shaded area in diagram).

Of the six neighborhoods slated for Forest Park, three are under construction or completed. But, even in its unfinished form, the new city is worth noting for a number of reasons:

- It's being built on a 3,700-acre tract that was part of the land purchased by the federal government 20 years ago after planning officials picked the site as one of the four best in the nation for a completely-planned suburban community.
- Houses will range in price from $14,000 to $60,000.
- Architectural and landscaping review is required before any house can be built in the city—regardless of price.
- Improved lots will be sold to homebuilders for development according to the city's master plan; individuals who want to build custom houses also will be able to buy improved lots.
- Developers of Forest Park have agreed to subsidize construction of schools by paying the school board a fixed amount for each house built and by selling school sites to the school board at a substantial discount.
- The shopping and business center will cover 450,000 sq ft, will include department stores, variety stores, supermarkets and other shops.
- Forest Park will have 239 acres for office and light industrial development.

Forest Park has had a unique history. When the government assembled 5,930 acres through the Federal Resettlement Administratioin, it selected Justin R. Hartzog, a wellknown town planner, to prepare a master plan for the entire tract.

The plan provided for immediate development of the 700-acre south central area with a community that was later incorporated as Greenhills.

In 1952, the U. S. Public Housing Administration planned to sell the tract at public auction. A local group formed a non-profit organization, the Cincinnati Community Development, and bought the 3,400 acres offered.

The group checked with developers, finally selected the Warner-Kanter Companies and resold the land to them under stipulation that a mutually-acceptable master plan be followed.

To produce the plan, Warner-Kanter employed Vogt, Ivers, Seaman and associates, Cincinnati architects-engineers, and Justin R. Hartzog.



WHEELING

GALVANIZED CORRUGATED

CULVERT PIPE

delivered where you want it when you want it!

Wherever you build, *whatever* you build, Wheeling stands ready to immediately deliver the type of Wheeling Galvanized Corrugated Culvert Pipe or Pipe Arch that best answers your needs. You may specify Copper Steel or Pure Iron plain galvanized or bituminous coated (with or without paved invert) in a wide range of gauges and diameters.

Wheeling's network of warehouses is strategically located throughout the country to assure you immediate job-site delivery on most items.

For full details and specifications contact the Wheeling warehouse or sales office nearest you.

Manufactured to comply with Federal and all state highway specifications.

Wheeling

Use these other Wheeling products for economical, long-lasting construction



Tri-Rib Steel Roof Deck—Lighter, stronger, saves structural steel, cuts gross weight as much as 40%.



Steelcrete Expanded Metal for Reinforcing — Distributes concentrated loads over a larger area.



Expanded Metal Railings, Guards, Treads, Walkways. Cuts maintenance. Permits full visibility and ventilation.



Gutters and Leaders—Heavy pure zinc coating. Provides long life, rust-resistance, sure protection.



Metal Lath—Provides the best plaster bond for crack-free walls, complete design flexibility.



SOFTITE, Cop-R-Loy: the tightest-coated Galvanized Sheet. Coating won't peel no matter how severely formed.

WHEELING CORRUGATING COMPANY, WHEELING, WEST VIRGINIA

Wheeling's Warehouses are strategically located throughout the country to give you speedy, on-time delivery on all warehouse-stocked items. Consult the 'Yellow Pages' for the Wheeling warehouse or sales office nearest you. ***Warehouses:*** Boston, Buffalo, Chicago, Columbus, Detroit, Kansas City, Louisville, Minneapolis, New Orleans, New York, Philadelphia, Richmond, St. Louis. ***Sales Offices:*** Atlanta, Houston.

10 cf. load of concrete for the Railporter trailer.



360-foot unattended round trip every 2¼ minutes.

Rail stands straddle reinforcing mesh and conduit.

Look! No runways!

REX RAIL PORTER

"The Rex Railporter proved the most economical method of performing this pour," states General Superintendent Fred Shelong of Klug & Smith, Inc. "Not only did it reduce manpower, it also eliminated the need for runways."

On this job, the Rex Railporter, complete with trailer unit, covered an average round-trip distance of 360 feet every 2¼ minutes with a 20-cubic-foot load of concrete... better than 18 yards an hour with only six men to charge, convey, place and puddle.

The Rex Railporter can save real money for you, too. A portable transport for construction materials, it runs on a single rail which is easily handled and laid by two men. Rail stands are adjustable for rough terrain. On this job the rail straddled the reinforcing mesh and conduit, eliminating the need for runways.

The Railporter is self-powered, runs unattended between loading and discharge points, stops automatically where desired and can be dumped to either side. Power and trailer units each carry 13 cubic feet of material (liquid level) or 10 cubic feet of concrete.

The Railporter is available with curved rail sections and switches and because of its adjustable rail stands, operates over any ground condition ...reinforcements, mud, open cuts, excavations, tunnels, water or elevations.

The gasoline power unit can haul a trailer unit of equal load capacity and the two units move along the rail at a clip of better than 300 feet a minute. See your Rex Distributor or write for Bulletin 56-47. Chain Belt Company, 4633 W. Greenfield Ave., Milwaukee 1, Wis.

CONSTRUCTION REX MACHINERY®



CHAIN BELT COMPANY

Shades of the American Plan

Southern communities use local ordinances to hamstring union growth but success is dimmed by courts and labor

Following the lead of several other southern communities, Eupora, Miss., a small city 100 mi northeast of Jackson, has passed an ordinance imposing a costly privilege license on persons engaged in organizing or promoting labor unions.

Such ordinances have come under heavy attack by the building trades, which view them as part of an open shop campaign to weaken and destroy unions. They reflect some of the conditions the AFL-CIO is up against in its organizational efforts in the South. And they point up the federation's interest in political action on the local as well as on state and national levels.

The Eupora ordinance becomes effective Oct. 4. Its requirements are these:

- No one can engage in the practice of organizing or promoting a labor union without first applying to the Mayor and Board of Aldermen for a license.
- To be eligible for a license, one must be of good moral character and a resident, for at least three months, of the city.
- The license fee is $1,000.

Violation of the ordinance carries a fine of $100, or 30 days in jail, or both.

• **Not unique**—Cities in which similar ordinances have been tried include Madison, Fla., Charlotte, N. C., and Baxley and Carrollton, Ga.

The future of the ordinances is shaky. The Madison law, which imposed an annual fee of $300 plus $25 for each member organized, was killed earlier this month by a Florida Circuit Court on two grounds: It violated the state constitution and was in conflict with the Taft-Hartley Act because it impaired the right of workers to organize.

The validity of the Carrollton ordinance, which imposes a $1,000 license fee plus $100 for each day the license is effective, was questioned last July by the Federal Court of Appeals, Fifth Circuit. In directing a Federal District Court to enjoin enforcement of the ordinance in a State Court, the Circuit Court said the effect of the ordinance is "exorbitant and punitive."

Meanwhile, a Georgia court has refused to rule on the validity of the Baxley ordinance, which imposes a $2,000 annual license fee plus $500 for each union member obtained. But the court's refusal was based on procedural grounds only.

• **Open shop and politics**—The Madison ordinance, shortly after its enactment earlier this year, was described by Richard Gray, President of the AFL-CIO Building and Construction Trades Department, as "fantastic."

It was cited by Gray at the department's legislative conference last March as one of the examples of open shop efforts on the local political level to weaken and destroy all trade unions, including the building trades. "This," he said, "typifies the forces that are opposing us. Ours is not a local, state or federal fight alone. Ours is a fight against the open shop, the present day American Plan which to me is much more dangerous, much more intensified. . . ."

The American Plan, a carefully organized anti-labor campaign sponsored in the 1920's by a number of employer associations, promoted open shop conditions through such devices as yellow-dog contracts, propaganda and injunctions.

Local anti-labor legislation like the Eupora ordinance is one of the targets of the AFL-CIO's current political activity now being conducted under the direction of its Committee on Political Education.

COPE, which has reminded the federation's membership that "gains won at the bargaining table can be whittled down or wiped away" by a city council as well as by Congress or a state legislature, is—through its local agencies—taking an active interest in local elections. Here, as on the other levels, the aim is election of officials friendly to working people.

• **Organization**—At the same time, the AFL-CIO is approaching the problem from another direction—education.

When the Executive Council of the AFL-CIO met in Forest Park, Pa., last month, one of the problems on the agenda was organization of unorganized workers, a task now under the direction of John Livingston. One of the principal obstacles to membership drives in the South, where the campaign was launched most vigorously, is the anti-union attitude reflected by ordinances such as the Eupora one.

In an effort to overcome that attitude, the Executive Council approved preparation of plans for an educational program to be conducted in the South in the hope of convincing employees and businessmen alike that unions are beneficial to both the individual worker and his community as a whole.

Nonunion Contractors Unite

Nonunion contractors in the Phoenix area have formed the Independent Contractors Association of Arizona.

The organization is pledged to fight violations of the state's right-to-work and anti-picketing laws and of the Taft-Hartley Act.

President of the 52-member association is Douglas Dana of Phoenix.

A Truce Is Reached

Temporary solution found in Hanford labor dispute

Unions and contractors involved in a dispute over isolation and travel pay for construction workers at the Hanford Plutonium Works near Richland, Wash., have agreed to a one-year extension of the status quo while a labor relations panel seeks to resolve the issue.

The extension was requested by the Atomic Energy Commission Labor Relations Panel in telegrams to the eastern Washington Chapter, Associated General Contractors, and the teamsters, operating engineers and cement masons.

Following a 76-day strike after the union members were taken out from under the project agreement and put under existing AGC agreements, the panel had recommended continuation of free bus service and isolation pay of $2.62½ to workers on construction projects within the reservation.

Under the extension, pre-strike conditions will be maintained for a year without prejudice to either side. Contractors have taken the position that isolation pay has not been written into contracts for Army construction in the same area and that such pay is not given other workers who are not members of the disputing unions.

Still to be resolved are two lawsuits. One is by Morrison-Knudsen Co. against the teamsters and operating engineers for damages sustained during the strike. The other is by unions against contractors to recover approximately $800,000 in isolation pay.

(*Labor continued on page 148*)

Fringe Benefits

Chamber of Commerce sees expanding element of cost

Hourly wage rates are no longer an accurate measure of worker income or labor costs, according to the U.S. Chamber of Commerce, because of the growing significance of fringe benefits.

Based on a survey of 1,000 firms, the Chamber of Commerce estimates that the cost of fringe benefits in 1955 averaged $819 per employee, representing an increase of $99 since 1953. Items included in this element of cost were payments and contributions for such things as pensions, vacations, holidays, insurance, social security and unemployment compensation.

"During recent years pensions, social security and a host of other benefits have substantially increased both the well-being of employees and the cost of doing business," said Emerson Schmidt, director of the association's Economic Research Department. "Vacations, holidays, rest periods and other payments for time not worked have given workers increased compensation for each hour actually on the job. They have at the same time increased the employer's cost of each hour of productive labor."

Highest payments, the survey disclosed, were made by companies in the Northeast. The grand total for the nation as a whole was estimated to be $36 billion. But the amounts paid by individual employers was found to vary considerably, ranging from 5% to more than 50% of payroll.

When broken down, the 1955 average of $819 had these components: pensions and insurance—$254; vacations and holidays—$254; programs imposed by law (social security, unemployment insurance, workmen's compensation, etc.)—$145; rest period—$89; miscellaneous—$77.

Results of the survey have been put in booklet form—"Fringe Benefits 1955", available from the national organization.

Eisenhower, Nixon, Reuther Discuss Shorter Workweek

At his press conference last week, President Eisenhower expressed his approval of a four-day workweek in principle but made it clear that shorter working hours should be achieved through normal economic forces and not by government edict.

His remarks stemmed from a Colorado Springs prediction of Vice-President Nixon that a four-day workweek and a fuller life for every American are goals that may be achieved in the not too distant future. Since then, Walter Reuther, head of the United Auto Workers union, has been seeking commitments from Republican leaders to support federal legislation to reduce the workweek.

"Now, workweeks, length of workweeks, prices, wages come about as a result of great economic forces and economic developments," President Eisenhower said. He noted that an Administration can help to establish a climate in which everybody's efforts can be rewarded fully but added: "We do not, by any manner of means, believe that government should go and establish these things by fiat and say 'this is it'."

The UAW, which proposes to seek a four-day workweek in 1958 collective bargaining, has suggested that immediate steps be taken through federal legislation, including amendments to the Fair Labor Standards Act, toward a gradual reduction of hours of work.

Nonunion Contractors Face Union Alliance in Toronto

Five of the building trades in Ontario have joined forces in an effort to unionize construction work in Metropolitan Toronto.

The multi-million-dollar industry previously had defied organizational drives by the unions separately. Nonunion contractors doing municipal construction work form the immediate target, but the unions also have their eyes on building contractors in the home construction field, where nonunion contractors reportedly are paying wages far below going union rates.

Those making up the united front are the teamsters, laborers, carpenters, operating engineers and iron workers.

Union Membership Drives Are Under Way in Hawaii

As contractors in Hawaii get set for one of their busiest seasons with the start of a $100-million military housing program, renewed efforts are under way to unionize the islands' construction workers.

Latest development is the bidding for the trowel trades by rival groups.

Arthur A. Rutledge, leader of the teamsters in Hawaii, announced that he has been given the signal to organize by John E. Rooney, president of the Operative Plasterers and Cement Masons International Assn., AFL-CIO.

Two days later, Solomon Aki and Revocato Medina, officials of Local 368 of the laborers union, reported that leaders of the trowel trades had come to them and said they didn't want to come under the Rutledge leadership.

Rutledge seeks to organize plasterers, cement masons, bricklayers and tile setters as a new division of his teamsters. He sees a potential membership of 1,500.

In addition to the Rutledge drive, two other membership drives have been launched on the islands. John Montrone, international representative of the painters union, has been in Hawaii for six months. And Charles F. Nicholes, general representative of the carpenters union, has been there since July. Both report "satisfactory" progress.

Canadian Project Stalled By Internal Labor Dispute

Several major British Columbia construction projects were stalled last week by a wildcat strike of tunnel and rock workers.

The strike stems from an internal dispute in Local 168 of the laborers union over existing labor contracts executed last January by the union's international officers. After the contracts were rejected by local members, the officers were suspended by the international and the local was placed in trusteeship. A group of local members opposed the move, reinstated the officers and have attempted to gain recognition and negotiate as an independent tunnel and rock workers union.

Court hearings ensued and an injunction against picketing by the independents was obtained by contractors. This has been ignored. The Building Trades Council and affiliated unions in Victoria have urged management to implement "full procedures of the law" to remove pickets from two of the projects—British Columbia Power Commission's Campbell Lake and Ladore Falls hydro projects on Vancouver Island. Meanwhile, the Canadian Labor Congress has been asked to attempt conciliation between the conflicting labor groups.

Preferential Hiring Change Is Urged by Michigan Union

A new form of preferential hiring was recommended by one of the unions last week—extension of seniority rights, for hiring purposes, to employers other than the one for whom the employee works.

The recommendation came from the International Executive Board of the United Auto Workers. The board suggests that employers who have contracts with the union be required, when hiring, to give preference in order of sen-

(Continued on page 150)

Look!



NO STUFFING BOXES

Mechanical Shaft Sealed

PEERLESS PUMPS

handle chilled water for new LUTHERAN BROTHERHOOD BUILDING, Minneapolis, Minnesota

PERKINS & WILL, Architects-Engineers
Chicago, Illinois; White Plains, New York

BUILDING AIR CONDITIONERS are served by these 3 chilled water pumps. Because they employ mechanical shaft seals, there is no messy leakage. Occupy ½ the usual space, too. Truly modern pumps for a modern building.

MODERN PUMP CONSTRUCTION for A MODERN BUILDING . . .

Modern Peerless Type AS pumps, designed for and with mechanical shaft seals, instead of a stuffing box usually associated with this type of horizontal split case pump, are the choice of the architects-engineers for this most modern of air conditioned buildings.

Here are a few of the features that Type AS Peerless pumps offer: short shaft reduces shaft deflection, increases pump life; mechanical shaft seal eliminates leaks; pump is about ½ as wide as conventional pumps, size for size; pump performance is several points higher in efficiency; and finally, pump is easily serviced because rotating element lifts out of case in one piece for easy inspection and maintenance.

Figure your next job around Peerless Type AS pumps; gain the space saving, maintenance saving advantages of these modern shaft-sealed pumps for all water handling installations.

PEERLESS PUMP DIVISION
FOOD MACHINERY AND CHEMICAL CORPORATION
301 WEST AVENUE 26, LOS ANGELES 31, CALIFORNIA

PEERLESS PUMPS — fmc

Factories: Los Angeles 31, California and Indianapolis 8, Indiana

Offices: New York; Atlanta; Chicago; Indianapolis; St. Louis; San Francisco; Phoenix; Fresno; Los Angeles; Plainview and Lubbock, Texas; Albuquerque.

Distributors in Principal Cities. Consult your Telephone Directory.

☐ *Please send me a Peerless Type AS pump Bulletin No. B-1350.*

NAME _____

TITLE _____ COMPANY _____

ADDRESS _____ CITY _____ STATE _____

ENR

STUMBLING HAZARD
ELIMINATED

Spilled materials on a solid walkway caused workmen to stumble and turn ankles. Installation of 80% open Irving Mesh Grating allowed materials to fall through and minimized the hazard.



★

For Safe, Strong, Slip-Proof Stair Treads Specify
IRVING "VIZABLEDG" TREADS

★

Manufacturers of Riveted, Pressure-Locked, and Welded Gratings of Steel, Aluminum and other metals.

"A FITTING GRATING FOR EVERY PURPOSE"

IRVICO

IRVING SUBWAY GRATING CO., Inc.
Originators of the Grating Industry

Offices and Plants at
5063 27th St., LONG ISLAND CITY 1, N. Y.
1863 10th St., OAKLAND 23, CALIFORNIA

iority to workers laid off by other employers in the same area and industry, taking into consideration the individual's seniority with former employers. This would be accomplished at the present time by negotiation of supplemental labor agreements.

Action of the board was occasioned, according to UAW, by the current unemployment of thousands of union members laid off by a number of manufacturing and supply plants recently closed down. In line to benefit most from such a change are older workers who find it difficult to obtain jobs under existing employment practices.

Teamster Pension Plan Aids Early Retirement

Agreement has been reached on a new pension plan for 150,000 teamsters in central and southern states. Designed to encourage early retirement, the program provides for voluntary retirement at age 60 with monthly payments of $90 for the first five years.

Participants are members of teamster locals in the Central States and Southern Conferences and National Truckaway and Driveaway Conference.

Provision is made for optional retirement between the ages of 60 and 70. Monthly payments, which are exclusive of social security, will drop to $22.50 after the first five years. Cost of the program will be borne by employers.

Payments under the plan are scheduled to commence in February, if the program is approved by the U.S. Treasury Department for income tax purposes.

More Apprentices Sought By Bricklayers Committee

The Bricklayers National Joint Apprenticeship Committee has launched an annual Local Joint Apprenticeship Committee Awards Program to encourage the training of a larger number of apprentices.

Awards will be presented to members of local committees that come closest to meeting the apprentice-journeymen ratio recommended by the national committee. The national ratio now approximates one apprentice to every 10 journeymen. The Bricklayers National Joint Apprenticeship Committee has recommended a ratio of one to five.

Serving on the national committee are representatives of the Bricklayers, Masons and Plasterers International Union, the Mason Contractors' Association of America and the Associated General Contractors of America, Inc.

Labor Briefs . . .

• **Road rates**—Gov. George Leader of Pennsylvania has extended to all of the state's 67 counties the requirement that prevailing wages must be paid by contractors on all state road jobs. The requirement previously applied to only 12 of the larger counties, including Philadelphia and Allegheny.

• **Right-to-work**—The Manufacturers Association of Connecticut says it will ask the State Assembly for a right-to-work law next year. Taking issue with the State Board of Mediation and Arbitration, it denies that its opposition to the union shop has lessened.

• **Zoning laws**—Decrying the decline in construction volume and loss of jobs for its members caused by zoning laws, Westchester County, N. Y., building trades have petitioned all cities and villages in the county to revoke "unrealistic, capricious and unnecessary building restrictions."

• **Older workers**—The carpenters union in Hamilton, Ont., is seeking through the Canadian Labor Congress to get the Unemployment Insurance Commission to remove the age of workers from their jobless insurance books. It says disclosure of age has resulted in discrimination against some older workers.

• **Segregation**—Local 434 of the painters union in Montgomery, Ala., has expelled a union member for fostering segregation and racial discrimination. Charges included attempts to form a rival union and to promote secession from the AFL-CIO.

• **Trouble again**—City and county officials in Florida's Orange County have protested determination of prevailing wage rates by the state's Industrial Commission. They claim the rates, improperly fixed, are high and unrealistic and will put needed construction beyond the government's financial reach.

• **Safety** — Cooperation, consultation education and persuasion were stressed as some of the keys to safety at the Governor's Conference on Worker Safety in Albany, N. Y., last week. Conference marked the launching of a statewide program to cut down the number of on-the-job accidents. Annual cost of such accidents in the state is now estimated to be $750 million.

SAVE on EXPENSIVE Pit Costs!

THURMAN portable scales . . . . .
Need NO concrete pits!



Move easily from job to job! Set-up in minutes

Thurman *Portable* Truck Scales perform best in the field year after year. They're engineered to move rapidly from job to job on a moment's notice. No concrete pits are ever needed. Set on any flat level ground, ramp the earth on each end and roll trucks on. Thurman *Portable*s are made for a lifetime of accuracy under rugged field conditions. Capacities: 20 to 50 ton Deck Lengths: 18 to 43 ft. Write today for bulletin 601.

EASY TO INSTALL AS A PERMANENT PITLESS SCALE saves on expensive pit cost



other THURMAN scales

Batching Scales	Pit Scales
Liquid Weighing Scales	Warehouse Scales
Portable Truck Scales	Wheelbarrow Scales
Industrial Scales	Electronic Scales

THURMAN

Precision Products since 1918

THURMAN MACHINE COMPANY, DEPT. D, 156 N. 5th STREET, COLUMBUS, OHIO

3 Simple Reasons Why MC TRANSCRETES Put Bigger Profits in Your Pocket!



❶ FASTER CHARGING

❷ MORE THORO MIXING

Take features like TRANSCRETE'S time-tested outswinging hopper and floating drive — add to them NEW SHORTER OVERALL LENGTH — and it's no wonder TRANSCRETE beats 'em all a country mile for pouring more and better concrete — easier, faster — and at less cost!

There's a size TRANSCRETE (4 models, from 3½ to 7 yard mixing capacities) to do any job in the books.

New Model 700 hauls up to 8 plus yard loads — mixes any 7-yard batch. Write CONSTRUCTION MACHINERY CO., Waterloo, Iowa.

❸ QUICKER DISCHARGE

ALSO MANUFACTURER OF A COMPLETE LINE OF
BUILDING MIXERS • CENTRAL PLANT MIXERS • PLASTER & MORTAR MIXERS
PUMPS • HOISTS

OFFICIAL PROPOSALS

RATE: The rate for Official Proposal advertising is $2.10 per line or fraction set solid. Where the advertisement is set other than solid, the space is measured by total space occupied and charged on basis of 12 lines to the inch.

CLOSING DATE: Friday 10:30 A.M. for issue dated the following Thursday.

SEND COPY TO: Official Proposal Division, Engineering News-Record, 330 West 42nd Street, New York 36, N. Y.

Bids: October 19, 1956

New York State Road Work

NOTICE TO CONTRACTORS: STATE DEPARTMENT OF PUBLIC WORKS, ALBANY, N. Y.,—Pursuant to the provisions of the Highway Law, Canal Law, and Article 2, Title 9 of the Public Authorities Law, and special provisions for projects financed with Federal Aid Funds, sealed proposals will be received until ten-thirty o'clock A.M., advanced standard time, which is nine-thirty o'clock A.M., eastern standard time, on the 18th day of October 1956, by Henry A. Cohen, Director, Bureau of Contracts and Accounts, 14th Floor, The Governor Alfred E. Smith State Office Building, Albany, N. Y., for the following projects:

County	Contract No.	Name	Miles	Type	Deposit	Estimated Cost of Work
DISTRICT No. 2, Lacy Ketchum, District Engineer, 100 No. Genesee St., Utica, N. Y.						
Herkimer	U. S. 92	Lock 18 Erie Canal near Herkimer		New Lock Gates and Lowering Lower Sill	5% of Bid Plans $10	Not Published
Oneida	MTC 56-5	New York State Thruway-Mohawk Section-Sub. 9 (Thruway Connection to Utica: North-South Arterial)	1.21 (0.62 Acc.)	Grading & Drainage Hy. Sep. Weld. Plate Girder 102'	$35,000 Plans $15	$659,000
DISTRICT No. 3, Wm. Robinson, District Engineer, Weigh Lock Building, 301 E. Water St., Syracuse, N. Y.						
Onondaga	FIC 56-11 FIRC 56-77	City of Syracuse: Oswego Boulevard (James St. to S.H. 54-3) Syracuse-Mattydale, S.H. 54-3 Phoenix-Syracuse, S.H. 5274 Project No. I-IG-463(13)	2.67 (5.96 Acc.)	ASP. Conc. Ty. 2A = 6.13 Mi. ASP. Conc. Ty. 1A = 0.08 Mi. Bit. D.S. Treatment = 0.14 Mi. Grading, Drainage & Misc. Work = 2.28 Mi. 6 Hy. Seps. Comp. I-Beams 135.0', 181'; 125.3' 153.1', 109.3' and 196.2' 1 RR-Hy. Sep. Comp. I-Beam 390' 1 Double Box Frame Bridge 38'	$440,000 Plans $100	$8,147,000
DISTRICT No. 5, E. G. H. Youngmann, District Engineer, State Office Bldg., 65 Court St., Buffalo 2, N. Y.						
Erie	EIST 56-9	Connection Between New York State Thruway-Niagara Section-Sub. N8 and Base Line Road (Buckhorn Island State Park)	1.16	APS. Conc. Opt. = 1.16 Mi. Misc. Work = 0.02 Mi. Comp. I-Beam Bridge = 60'	$10,500 Plans $15	$188,000
Erie	FINTC 56-1	New York State Thruway-Niagara Section-Sub. N4 (Washington St. to Franklin Sts.) Project No. I-865(7)	0.21 (0.11 Ramp)	16 Span Viaduct Structure 7 Span Elevated Ramp	$190,000 Plans $50	3,408,000
Erie	FINTC 56-2	New York State Thruway-Niagara Section-Sub. N6, Pt. 3 (Amherst to Ontario Sts.) and 5 Cross Sts. or Acc. Rds. Project No. I-865(8)	0.83 (0.74 Acc.)	9" Cem. Conc. Pavt. 2 @ 24' Var. Wide = 1.02 Mi. Asp. Conc. Pavt. = 0.04 Mi. Bit. Mac. Pavt. = 0.11 Mi. Misc. Work = 0.04 Mi. 4 Hy. Seps. Comp. W. F. Beams 134.5', 96', 120.3' & 86' 1 RR-Hy. Sep. W. F. Beam 221'	$245,000 Plans $100	4,457,000
Erie	NTC 56-3	New York State Thruway-Niagara Section-Sub. N6, Pt. 1 (Porter Ave. to Ontario St.)	2.38 (0.93 Acc.)	9" Cem. Conc. Pavt. 2 @ 24' Var. Wide = 2.65 Mi. Asp. Conc. Opt. = 0.46 Mi. Misc. Work = 0.20 Mi. 1 RR-Hy. Sep. Comp. I-Beam ±99' Var. 3 Hy. Seps. Comp. I-Beams 106.8', 84.1'; & 162'	$535,000 Plans $100	9,707,000
DISTRICT No. 7, R. W. Sweet, District Engineer, 444 Van Duzee St., Watertown, N. Y.						
St. Lawrence	FATC 56-1	Massena South Side Route Pt. 1, FASH 56-13 Massena South Side Route Pt. 2, FASH 55-7 Massena-Helena Pt. 1, S.H. 1261 Project No. U-580(11)	5.13	Traffic Signal System	$4,500 Plans $10	$85,000
Clinton	CD 56-1	Macomb Military Reservation on the Salmon River at Davis Lake		Remove Existing Dam and Replacing with New Dam	5% of Bid Plans $10	129,500
DISTRICT No. 8, K. G. Rauba, Acting District Engineer, Pleasant Valley Rd., Poughkeepsie, N. Y.						
Westchester	FINETC 56-6 FINET 56-6	New York State Thruway-New England Section-Sub. NE5 (Boston Post Road to Fox Island Road) Project No. I-IN-1068(13)	1.15 (5.19 Acc.)	9" Cem. Conc. Pavt. 2 @ 37' Var. Wide = 3.68 Mi. Grading (Ramps) & Misc. Work = 2.36 Mi. Asp. Conc. Pavt. = 0.30 Mi. 3 Hy. Seps. Comp. I-Beams 139', 207', and 151.6' 1 Hy-RR Sep. I-Beam and Girder 383.9' Ramp B Structure-Sub-Structure Only	$330,000 Plans $100	$5,950,000
DISTRICT No. 10, M. E. Hoyt, District Engineer, 325 W. Main St., Babylon, L. I., N. Y.						
Nassau	FAHHE 56-3	Horace Harding Expressway Extension (Cont. 2) (Shelter Rock Road to Willis Ave.) Project No. U-862(10)	1.76 (4.58 Acc.)	9" Cem. Conc. Pavt. (with Carb. Black) 2 @ 36' Wide = 1.58 Mi. 6" Cem. Conc. Pavt. Var. Wide = 0.77 Mi. Asp. Conc. Pavt. = 3.82 Mi. Misc. Work = 0.20 Mi. 2 Hy. Seps. R.C. Rigid Frames 102.2' and 83.5' 1 Hy. Sep. Comp. Steel Girder 80'	$180,000 Plans $50	$3,377,000

Any projects in this letting that are on the Federal Aid highway systems are subject to the provisions of the "Federal-Aid Highway Act of 1956", being Public Law 627, 84th Congress, approved June 29, 1956, and are also subject to the applicable New York State statutes.

In compliance with the provisions of Section 115 (Prevailing Rate of Wage) Public Law 627, the minimum wages to be paid laborers and mechanics are included in wage schedules that are set out in the bid proposal.

Maps, plans, specifications and proposal forms may be seen and obtained at the office of the State Department of Public Works, Bureau of Contracts and Accounts, Albany, N. Y., and at the office of the District Engineers noted above, and may also be seen at the office of the State Department of Public Works, 270 Broadway, New York City.

The deposit for Plans and Proposal Forms for each contract is indicated above. A refund will be made in full to bidders for return of one set, in good condition, within 30 days of award, or rejection of bids; refund for all other sets in good condition, similar period, will be 50% of deposit.

Special attention of bidders is called to "General Information for Bidders" in the proposal, specification, and contract agreement, and to the special provisions applying to projects financed with federal funds. Award of a contract is subject to priorities and allocations under the Defense Production Act of 1950, as amended, and all regulations issued thereunder.

Proposal for each contract must be submitted in a separate sealed envelope with the name and number of the contract plainly endorsed on the outside of the envelope. Each proposal must be accompanied by draft or certified check payable to the order of the "State of New York, Commissioner of Taxation and Finance" for the sum as specified in the advertisement and the proposal. The retention and disposal of the bidding check, the execution of the contract and bonds shall conform to the provisions of the Highway Laws, as set forth in "Instructions to Bidders".

The right is reserved to reject any or all bids.

JOHN W. JOHNSON
SUPT. OF PUBLIC WORKS

OFFICIAL PROPOSALS

Prequalification Date: October 11, 1956

BOARD OF EDUCATION—BUREAU OF CONSTRUCTION. Notice Re: Prequalification Forms for Contractors. NOTICE IS HEREBY GIVEN THAT The Director of the Bureau of Construction, 4th Floor, Room 407, 42-15 Crescent Street, Long Island City 1, New York, will receive applications for prequalification of bidders, from Contractors who may wish to submit bids for the proposed hereinafter specified contracts, as follows:

For general construction, plumbing and drainage, heating and ventilating, electrical work and lighting fixtures, elevator and escalators for:

BOROUGH OF BROOKLYN
Jr. H.S. 50, new Addition to and Modernization of existing building, South 3rd St. & Driggs Avenue.

BOROUGH OF MANHATTAN
New Jr. H.S. 13, Fifth Ave., 107th and 106th Sts.
New P.S. 144, 120th St. and Lenox Avenue.
New P.S. 2, Pike & Henry Streets.
New P.S. 140, Remington and Suffolk Avenues.
New Fashion Institute of Technology, West 27th & 28th Sts., between 7th and 8th Aves. Including Elevators and Escalators.

BOROUGH OF QUEENS
New P.S. 221, Marathon Parkway and 60th Avenue.

Prequalification application forms will have to be secured and must be submitted to the Director, Bureau of Construction Office, 4th Floor, Room 407, 42-15 Crescent Street, Long Island City, New York.
Bids when advertised will be received from prequalified bidders only.
The time for submitting prequalification application forms for the above contracts will expire on Thursday, October 11th, 1956.

WILLIAM H. CORREALE
Director

Dated: September 27, 1956.

Bids: October 11, 1956

This Is A Re-advertisement With A Change In Specifications

DELAWARE RIVER PORT AUTHORITY
of the
COMMONWEALTH OF PENNSYLVANIA
and the
STATE OF NEW JERSEY
Administration Building
Camden, New Jersey

WALT WHITMAN BRIDGE CONTRACT NO. P-13

Sealed bids will be received for "Installation of New Stacks on the Power Plant of Publicker Industries, Inc., Delaware and Packer Avenues, Philadelphia, Pa.", known as Contract No. P-13, at the office of the Executive Director of the Delaware River Port Authority, Administration Building, Bridge Plaza, Camden, New Jersey, until 2:30 P. M., Eastern Daylight Time, Thursday, October 11, 1956, at which place and time they will be publicly opened and read by the Authority.

A more complete description of the work and full information for bidders are given in the Contract Documents and Specifications for this Contract, which may be obtained upon the deposit of $10.00 check, which will be remitted upon receipt of bid or the return in good condition of the copies so taken within thirty days after the opening of bids.

Each proposal must be accompanied by a certified check in the sum of $20,000 payable to the Delaware River Port Authority and drawn upon a National or State Bank or Trust Company having an office or place of business either in Philadelphia, Pennsylvania, or Camden, New Jersey, and must not be enclosed with the sealed bid. The surety's consent must be shown. The bidder to whom the contract is awarded will be required to furnish a Performance and Labor and Materialman's Bond in the sum of 100 percent.

The Authority will afford prospective bidders an opportunity to inspect the site of the work.

The Authority reserves the right to waive any informalities in the bids received; to reject any or all bids, and to award the contract only to those experienced in this class of work and to the bidder whose proposal is deemed by the Authority to be most advantageous to the public interest.

DELAWARE RIVER PORT AUTHORITY
JOSEPH K. COSTELLO,
Executive Director

9/19/56
McS

Bids: October 18, 1956

New York State Road Work

NOTICE TO CONTRACTORS

STATE DEPARTMENT OF PUBLIC WORKS, ALBANY, N. Y.—Pursuant to the provisions of the Barge Canal Improvement Law and Highway Law, sealed proposals will be received, until 10:30 A.M., DST on October 18, 1956 by Henry A. Cohen, Director, Bureau of Contracts and Accounts, 14th Floor, the Governor Alfred E. Smith State Office Building, Albany, N. Y. for

Contract U.S. 94 for
New Gates and Lowering
the Lower Sill at Lock 11
Erie Canal at Amsterdam
Montgomery County, New York

Maps, plans and specifications may be examined and obtained at the following offices:

(a) Bureau of Contracts and Accounts, 14th Floor, The Gov. Alfred E. Smith State Office Bldg., Albany, New York.

(b) Department of Public Works, 270 Broadway, New York City, N. Y.

(c) In addition to the above mentioned offices, plans, maps and specifications for Contract U.S. 94 may be examined and obtained at the office of Mr. Lacy Ketchum, District Engineer, 109 N. Genesee St., Utica 1, New York.

The deposit for Plans and Proposal Forms for U.S. 94 is $10.00. A refund in full will be made to bidders for return of one set in good condition within 30 days of award or rejection of bids; refund for all other sets in good condition, similar period, will be 50% of deposit.
The Engineer's Estimate of Cost for Contract U.S. 94 is confidential and will be made known at the time of receiving bids. Proposals for U.S. 94 must be submitted in a separate sealed envelope with the name and number of the contract plainly endorsed on the outside of the envelope. Each proposal must be accompanied by draft or certified check, payable to the order of the "State of New York, Commissioner of Taxation and Finance" for the sum of five percentum, (5%) of the bid. The retention and disposal of the bidding check, the execution of the contract and bonds shall conform to the provisions of the Barge Canal Improvement Law and to the Highway Law as set forth in "Instructions to Bidders" in the contract specifications.

JOHN W. JOHNSON
SUPT. OF PUBLIC WORKS

Bids: October 23, 1956

Contract NYA-140.038

ADVERTISEMENT

THE PORT OF NEW YORK AUTHORITY
NEW YORK INTERNATIONAL AIRPORT
UTILITIES TO BUILDING NO. 189

Sealed proposals for the furnishing and installation of utilities to the site of Building No. 189 at New York International Airport will be received at the office of the Chief Engineer of The Port of New York Authority, Room 1100, 111 Eighth Avenue, New York 11, N. Y., until 2:30 P.M. on Tuesday, October 23, 1956, at which time said proposals will be opened and read in Room 1108.

Contract documents may be seen at the office of the Engineer of Design of the Authority, Room 1115. Documents will be furnished upon deposit of $30.00 per set for not more than three sets to any one company (each set including one copy of the contract drawings). Additional sets will be furnished upon payment of $30.00 per set, which payment is not returnable. Deposits and payments shall be delivered to the Treasury Department, Room 1001, where a receipt in duplicate will be issued. A copy of the receipt shall be delivered to Room 1115, where the documents will be furnished.

Those who have submitted a bid on the contract will receive a refund of the deposit for each set of documents, not exceeding three, returned within forty days after the opening of proposals. Those who have not submitted a bid will receive a refund of one-half of the deposit for each set of documents, not exceeding three, returned within forty days after the opening of proposals.

THE PORT OF NEW YORK AUTHORITY
Donald V. Lowe, Chairman

New York, October 4, 1956

Bids: Oct. 17, 26, and Nov. 7, 1956

Construction of Sewers (Approximately 20 Miles)

Arlington Sewer District, Town of Poughkeepsie, Dutchess County, New York.

Sealed proposals will be received by the Town of Poughkeepsie, New York, until 8 PM on the dates designated, at which time they will be opened and publicly read aloud, for:

Contract	2—Outfall Sewer	(October 17)
	3—Sewers	(October 26)
	4—Sewers	(November 7)

Plans, Contract Documents, and Specifications may be obtained from Town Clerk, Anne K. Rogers, Town Hall, Dutchess Turnpike, Poughkeepsie, New York, upon deposit of $25 for each set of plans and specifications for each contract, which sum will be returned to all bidders.

Bids to be accompanied by Bid Bond or Certified Check in the amount of not less than 5% of base bid.

ARLINGTON SEWER DISTRICT
Morrell Vrooman Engineers
Gloversville, New York

Bids: November 1, 1956

New York State Thruway Authority

NOTICE TO BIDDERS

The New York State Thruway Authority invites proposals and quotations for the furnishing and installation of AUTOMATIC TOLL COLLECTION EQUIPMENT for barrier toll stations on the New York State Thruway. Full information on the Automatic Toll Collection System is available and may be obtained from the office of the Director of Purchasing, New York State Thruway Authority, Delaware Avenue Plaza, Elsmere, New York (Mailing Address: P. O. Box 189, Albany, New York).

Each proposal should be enclosed in a sealed envelope and the words "Automatic Toll Collection Equipment" should be shown, for identification, on the face of the envelope, and sealed envelope should be directed to the Authority at the above mailing address. Sealed proposals will be received until 11:00 A. M., E. S. T. on November 1, 1956 when they will be publicly opened and read. The Authority reserves the right to reject any or all proposals.

HOLDEN A. EVANS, JR.
General Manager

U. S. Government

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Specifications No. DC-4767) will be received at Ephrata, Washington, until October 31, 1956, for furnishing labor and materials for White Bluffs Pumping Plant No. 1, Laterals and Discharge Lines, Block 26, Columbia Basin Project, Washington. Location near Othello, Washington. Principal items are 83,900 cu. yds. excavation; 720 cu. yds. concrete; furnishing and laying 1,620 lin. ft. 21-inch and 66-inch concrete pipe; furnishing and erecting 56,000 lbs. steel for pumping plant superstructure; and other work. Completion time 660 days. For particulars, address Bureau of Reclamation, P. O. Box 368, Ephrata, Washington; P. O. Box 937, Boise, Idaho; or Building 53, Denver Federal Center, Denver 2, Colorado. W. A. Dexheimer, Commissioner.

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Specifications No. DC-4770) will be received at Weaverville, California, until October 23, 1956, for furnishing labor and materials for Water Supply System for Trinity Government Community Facilities, Central Valley Project, California. Location near Lewiston, California. Principal items are 2,900 cu. yds. excavation; 4,000 lin. ft. excavation and backfill of pipe trenches; furnishing and erecting chlorination building; furnishing and installing 2 motor-driven pumping units; and other work. Completion time 120 days. For particulars, address Bureau of Reclamation, P. O. Box 2511, Sacramento, California; or Building 53, Denver Federal Center, Denver 2, Colorado. W. A. Dexheimer, Commissioner.

EMPLOYMENT OPPORTUNITIES

DISPLAYED —RATES— **UNDISPLAYED**

The advertising rate is $28.25 per inch for all advertising appearing on other than a contract basis.
An Advertising Inch is measured ⅞" vertically on a column—3 columns 30 inches to a page.
Subject to Agency Commission.

$7.10 per line, minimum 3 lines.
Position Wanted ½ of above rate.
Box Numbers—counts as 1 line.
Discount of 10% if full payment is made in advance for 4 consecutive insertions.
Not subject to Agency Commission.

Send NEW ADS to ENGINEERING NEWS-RECORD, P. O. Box 12, N. Y. 36, N. Y.

PROJECT ENGINEERS
Also
CIVIL & STRUCTURAL
ENGINEERS
DESIGNERS
DRAFTSMEN
For
Industrial Plants

New Offices
Permanent Positions
Excellent Opportunity
for Advancement
Liberal Relocation Allowances
Please Write Fully to
or Inquire

WESTERN-KNAPP ENGINEERING CO.

760 FOLSOM — SAN FRANCISCO
EX 2-4167 — JOHN HAMM

OPPORTUNITIES IN
ARIZONA
for
HIGHWAY ENGINEERS
DESIGNERS-DRAFTSMEN
INSTRUMENTMEN - RECENT
CIVIL ENGINEER GRADUATES

Professional
Sub-Professional
Field and Office

Liberal vacation and sick leave—retirement plan—advancement opportunities—new air conditioned building

ATTRACTIVE PAY
HEALTHFUL CLIMATE

Send resume to Arizona Highway Dept. - 1739 W. Jackson, Phoenix, Arizona

SALARIED POSITIONS $5,000 — $35,000

We offer the original personal employment service (established 40 years). Procedure of highest ethical standards is individualized to your personal requirements. Identity covered; present position protected. Ask for particulars.

R. W. BIXBY, Inc.
555 Brisbane Bldg. — Buffalo 3, N. Y.

ENGINEERS
Are you worth up to
$10,000 A YEAR?

Important permanent positions, paying from $6,500 to $10,000 a year with unusual future opportunity, have been created by the expansion program of our large, long-established engineering and construction firm. We need qualified engineers, designers and draftsmen experienced in structural, concrete, mechanical and piping design. Engineering offices are in several major American cities and Canada. Excellent working conditions. Generous company benefits. Our employees know of this ad.

Investigate this opportunity. Write today, giving age, education and experience. Your inquiry will be kept strictly confidential and will be answered promptly.

P-3067, Engineering News-Record
520 N. Michigan Ave., Chicago 11, Ill.

REPLIES (Box No.): Address to office nearest you c/o This publication Classified Adv. Div.
New York: P. O. Box 12 (36)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)

POSITIONS VACANT

General Supt. Engr. for Sewers and water lines must be well experienced in supervisory installation and estimating, coordinating inside and outside. Old established Company. Resume held in confidence. Columbia Constr. Co. Inc., 2108 Columbia Ave., Indianapolis 2, Ind., WAlnut 3-1567, Mr. Farrer.

General Superintendent, qualified engineer for Kansas contractor, must have proven experience on industrial buildings & gov't. projects. Salary open. P-2754, Engineering News-Record.

Heavy Equipment Engineer with at least 2 to 3 years of Mechanical Engineering Schooling for work in the South. Full information and references in first letter requested. Reply P-2917, Engineering News-Record.

Designers—Steel, Concrete, Electrical Piping, Air-Cond., Power Plants & Industrial Bldgs. Marbarry Corp., 120 Greenwich St., N.Y.C. Rector 2-3749.

Wanted: Registered Professional Engineer specializing in Soil Machanics, capable of taking complete charge of Soil Mechanics office performing soil exploration, laboratory testing, and writing engineering reports with respect to foundation requirements. Experience necessary. Some experience in structural design of foundations preferable but not essential. Good salary commensurate with qualifications. State qualifications in full, experience resume, references and salary requirements. P-2945, Engineering News-Record.

Civil Engineers, Designers, Draftsmen experienced in the design of sewers, pumping stations, sewage treatment plants, water supply systems, structural and hydraulic design, hydraulic computations, specs. O'Brien & Gere, 400 E. Genesee St., Syracuse, N. Y.

Civil Engineers — immediate vacancies for beginners and experienced Civil Engineers. Work related to flood control projects and hydrologic studies. Openings in Chicago and Springfield Illinois. Salary range $400-$600. Reply stating experience, location preferred and salary desired. Box P-2948 Engineering News-Record.

Land Surveyor!—for old established Chicago firm. Permanent position. Salary $6000-$8000 per year. Give experience in first letter. P-2916, Engineering News-Record.

POSITIONS VACANT

Wanted: Senior Structural Designing Engineer. Permanent position with industrial company in upper New York State. Excellent salary and opportunity based on ability. Fine living conditions for family. P-3006, Engineering News-Record.

Architectural draftsman for office with school and church jobs to plan. Experience preferred in preliminary layout, presentation drawings and construction drawings. Permanent position for qualified man. Write P. O. Box 36 Lancaster, Ohio, giving qualifications, experience and salary, or call Lancaster 2243-W for appointment.

Soils Engineer—Civil or mechanical engineering graduate preferred. Training in soil mechanics desirable. Excellent opportunity with internationally known construction firm. Submit complete resume including salary desired. P-3040, Engineering News-Record.

Highways Engineers, Designers, Draftsmen for office work in the vicinity of Louisville, Ky., on highways, expressways and similar civil works. Permanent positions for qualified experienced engineers or recent graduates—with a growing firm of established consulting engineers — Opportunity for advancement based on merit—Liberal transportation and moving allowances. Suburban living available close to office. Liberal Employee Benefits—Immediate openings—Beginning Salary Commensurate with Qualifications. Please write fully to Box P-3056, Engineering News-Record.

Architectural Engineer — Experienced steel and concrete designer for attractive position in office of Central Pennsylvania Architect. Work includes churches, schools and commercial buildings. Permanent position and attractive salary. P-2756, Engineering News-Record.

Estimators and Sales Representatives in Philadelphia, Chicago, and San Francisco areas preferably. Relocation unnecessary. Good pay, plus profit dividends. Address resume and references to Construction Survey Co., 101 Park Avenue, New York 17, N. Y.

Supervisor—Prestressed beam department. Metropolitan area concrete products manufacturer. Should have engineering background with experience in concrete building products manufacturing. Permanent. Company paid welfare plan. Write for appointment. P-3072, Engineering News-Record, 330 W. 42nd Street, New York 36, New York.

Civil Engineer—$5178 to $6326 yearly. In Hydrology Division of Water Resources Commission. Completes field studies concerning water use and water conditions on a statewide, river basin, regional or local basis, such studies to include the gathering and tabulation of hydrologic data from all sources. Analysis of such data for preparation of flood and drought frequencies, back water curves, flow-duration curves, mass diagrams, and other related hydrologic studies. Makes field investigations of problems dealing with beach erosion, ground water pollution floods, drainage and sedimentation. Write Michigan Civil Service, Lansing 13, Michigan.

Soil Engineer. By consulting engineering firm specializing in applied soil mechanics. Capable of supervising field and laboratory investigations and writing engineering reports with minimum supervision. Must be experienced and/or have good academic background in the specialty. Good opportunity for advancement. Please state qualifications in full and salary requirements. P-3083, Engineering News-Record.

Registered Engineer to take complete charge of proposed Chicago office for established firm of Consulting Engineers. P-3079, Engineering News-Record.

City Engineer for city of 26,000 population. Graduate engineer required—salary $6000. State experience, age, availability, and references. Reply City Manager, Gloucester, Massachusetts.

Traffic Engineer. Salary $653-$785. Three weeks vacation, sick leave, vacation. Requires college graduation and two years traffic experience. Apply Contra Costa County Civil Service, Box 710, Martinez, California.

Engineers for municipal and industrial water supply, sewerage and treatment projects. Opportunities for permanent connection with long established firm of consulting engineers in mid-west. Both E.I.T.'s and engineers considered. Full information and references in first letter requested. P-3116, Engineering News-Record.

(Continued on page 157)

Plan Your Future with BECHTEL in California on Hydro Electric Power Design

- Work in Los Angeles
- Liberal relocation allowances for you and your family
- Excellent facilities in area for advanced education
- Advancement based on merit
- Organized program of Personnel Development
- Personal accident insurance paid by the company
- Group insurance with liberal company assistance
- Opportunities in diversified types of engineering and drafting
- Contact with latest technological developments
- Air conditioned modern offices.

Immediate Openings

Supervising Engineers
Hydraulic
Experience

Engineers
Civil
Hydraulic
Structural
Electrical
Mechanical

Designers
Piping
Electrical
Structural

Men experienced in design of earth-fill or concrete dams, spillways, penstocks and hydro electric power stations are desirable. Allied experience acceptable.

Send resume to
Manager of Employment & Placement
Industrial Relations Division

BECHTEL
Corporation
220 Bush St., San Francisco 4, Calif.

For an immediate personal interview you may phone:
Paul Keating, Plaza 7-4400, New York City
Joe Braddick, Fairfax 3-2461, Houston, Texas
Bill Milligan, Tucker 1549, Los Angeles, Calif.
Don Palmer, Douglas 2-4032, San Francisco, Calif.

HIGHWAY ENGINEERS
DESIGNERS
DRAFTSMEN
Drainage Engineers

FOR OFFICE WORK IN ST. LOUIS ON HIGHWAYS EXPRESSWAYS AND ASSOCIATED CIVIL WORKS

- *Permanent employment for qualified men*
- *Ample opportunity for advancement based on merit*
- *Generous transportation & moving allowances*

Plus Employee Benefit and Retirement Plan, Paid Vacations, Holidays, Sick Leave. Blue Cross available.

PLEASE WRITE FULLY TO OR INQUIRE AT

SVERDRUP & PARCEL ENGINEERING CO.
1134 LOCUST ST. ST. LOUIS 1, MO.

Engineers Architects

Highway Designers—Draftsmen
Rochester & Harrisburg, Pa.

Bridge Designers—Draftsmen
Harrisburg, Pa.-College Park, Md.-Ft. Lauderdale, Fla.

Architectural Designers—Draftsmen
Rochester, Pa.

Civil Engineering Draftsmen

Ink Tracers—Computors
Rochester, Pa.

Air Mail Resume TO R. L. SHAW, *Personnel Director*

MICHAEL BAKER, Jr., Inc.
BAKER BLDG. *Consulting Engineers* ROCHESTER, PA.

ENGINEERS

Long established firm of consulting engineers with world-wide practice needs both beginners and experienced civil, electrical, mechanical, and foundation engineers for interesting work on large dams, power-plants, and river control works. Permanent positions. Liberal employee benefits. Starting salaries dependent on qualifications. Please send complete resume to Hugo Niemi, Personnel Manager.

HARZA ENGINEERING CO.
400 W. Madison St. Chicago 6, Ill.

ENGINEERS

Highway Design · Traffic Engineers
Architects · Structural Engineers

Recent graduates and experienced design engineers needed.

Company paid hospitalization, life insurance, retirement and holidays. 40-hour week. Send complete experience and education resume with salary requirements to:

Palmer & Baker Inc.
P. O. Box 346
Mobile, Alabama

STRUCTURAL DESIGNERS

FOR HIGHWAY BRIDGE WORK

SENIORS and JUNIORS

Work in New York City and New Jersey

BROWN & BLAUVELT
468 Fourth Avenue, New York City
44 Cooper Street, Woodbury, New Jersey

ASSISTANT TO SUPT.
For
CONCRETE PRODUCTS PLANT

Large progressive organization seeks young man with technical or engineering background with proven ability and ambition to fill position offering real opportunity.

This opening provides a steppingstone to executive assignment and unlimited potential. Please reply giving personal, business and educational background.

P-2959, Engineering News-Record
520 N. Michigan Ave., Chicago 11, Ill.

ENGINEERS, DESIGNERS and DRAFTSMEN

Permanent positions in an Engineering Department involved in all phases of engineering planning and layout, building and machine alterations, new construction, engineering evaluation and new equipment and processes, for our four paper mills in west central New Jersey.

STRUCTURAL—Reinforced concrete, structural steel, industrial plant experience.

MECHANICAL—Steam and power, service and process piping and equipment, heating and ventilating.

MACHINE DESIGN—Paper mill, finishing and converting equipment.

DRAFTSMEN—Senior and Junior, one year minimum general industrial experience.

Please write stating education, experience, salary expected and availability.

RIEGEL PAPER CORPORATION
Personnel Department
MILFORD, N. J.

HEAD STRUCTURAL DESIGNER

To supervise and administer Structural Designing and Drafting Department in home office of long established Boston consulting engineering firm.

Send resume of experience, references and record of past earnings to

P-2992, Engineering News-Record
Class. Adv. Div.,
P. O. Box 12, New York 36, N. Y.

TOP-FLIGHT ENGINEERS DESIGNERS DRAFTSMEN

McKEE has openings for top men to fill important, permanent positions, with excellent prospects for promotion to supervisory, staff and executive posts in our expanding organization.

Our Metals, Refinery and Industrial Divisions offer you wide choice of opportunity to make fullest use of your talents in the design of refineries, blast furnaces, steel, sintering, chemical and industrial plants and their auxiliaries.

Investigate the advantages of top compensation, ideal working conditions, employment security, advancement opportunity and many generous benefits available to you at McKee.

Telephone TOwer 1-2300, Cleveland, Ohio
or write to Edward A. Kolner,
Arthur G. McKee & Company,
2300 Chester Ave., Cleveland 1, Ohio

Arthur G. McKee & Company
Engineering offices in
CLEVELAND, OHIO • UNION, N.J. • TORONTO, ONT.

THINK

For your family:

Excellent climate, good housing for rent or purchase, 10 to 15 minute drive to office, good schools including a junior college, excellent facilities for golf and all water sports, 3 hours drive to beaches or mountains.

For you:

Opportunity for practicing and advancing in the Engineering Profession in an atmosphere of friendliness and competence.

Our goal is to provide timely service to our clients, proper compensation and recognition to our staff, and dignity to our profession.

Engineers and designers are needed to increase our staff in the following departments

Structural	3 men	5 to 7 years experience
Sanitary	1 man	7 to 10 years experience
Highway	8 men	4 to 10 years experience
Electrical	1 man	7 to 10 years experience
Process	1 man	15 to 20 years experience
	2 men	5 to 10 years experience

Submit experience resumes and references.
Interviews will be arranged

PATCHEN AND ZIMMERMAN, ENGINEERS
AUGUSTA, GA.

STRUCTURAL DRAFTSMEN

FOR HIGHWAY BRIDGE WORK
In New York City and New Jersey

BROWN & BLAUVELT
468 Fourth Avenue, New York City
44 Cooper Street, Woodbury, New Jersey

RESIDENT ENGINEER AND DEPUTY RESIDENT ENGINEER

To supervise construction of $40,000,000 rockfill dam in the Middle East. Four-year completion schedule. Please send detailed experience and personal record. Specify salary expected and earliest date available.

HARZA ENGINEERING COMPANY
400 W. Madison St. Chicago 6, Ill.

EXPERIENCED HYDRAULICS ENGINEER WANTED

Graduate engineer experienced in paper mill hydraulics, planning and development of piping layout systems, etc. for large expanding and progressive mill in Maryland. Good salary, all benefits and excellent opportunity for advancement. Send detailed resume of experience and education to
Director of Personnel
West Virginia Pulp & Paper Company
Luke, Maryland

SANITARY ENGINEER

Experienced in water supply and sewage disposal. Preferably with Masters Degree. Growing organization, good salary and opportunity. Middle Atlantic State. Please state full qualifications, experience, references.

P-3038, Engineering News-Record
Classified Adv. Div., P. O. Box 12,
New York 36, N. Y.

ENGINEER
(CIVIL—OVERSEAS)
HIGHWAY MATERIALS and TESTING ENGINEER

Position: In charge of modern highway testing laboratory and materials survey in Near East.

Requirements: 15-20 years experience. Ability to organize and direct a country wide materials survey and train personnel in testing operations.

Top salary—good living conditions—liberal benefits including paid transportation for wife.

P-2966, Engineering News-Record
Class. Adv. Div., P.O. Box 12, N.Y. 36, N.Y.

CHIEF ESTIMATOR

Well known New Jersey General Contractor needs qualified man to head Estimating Dep't.. Degree Preferred. Engineering background necessary. Must have at least 10 years of successful bidding experience in all phases of heavy construction, such as Highways, Structures, Dams, Drainage, etc.

Salary $10,000.00 up. Unlimited opportunity for properly qualified man. All replies confidential. Our employees know of this ad.

P-2999, Engineering News-Record
Class. Adv. Div., P.O. Box 12, N.Y. 36, N.Y.

CIVIL ENGINEER

With municipal experience on sewers and pavements to supervise field construction. Permanent position under Civil Service with retirement plan.

APPLY PERSONNEL DIRECTOR
City Hall, Royal Oak, Michigan

WANTED

Experienced resident engineer for steam electric station construction. Capable of coordinating project and willing to work in our Chicago office on design specifications, etc. between field assignments. Submit complete resume to:

PIONEER SERVICE & ENGINEERING CO.
231 S. La Salle St. Chicago 4, Ill.

POSITIONS VACANT
(Continued from page 154)

Field Geologist: Carry on field investigations and geological studies for portland cement mfr. for purpose of developing new sources of raw materials and extending knowledge of present deposits. Will hdqr. in Chicago, Ill., but must be free to travel. Will consider recent graduates as well as experienced applicants. Must have degree. Give full details on exp., training, personal data, and salary desired in first letter. Reply to P-2876, Engineering News-Record.

Civil Engineers: Water Distribution—Sewer Design—construction engineering—for a public utility organization in a rapidly expanding locality—ideal working and living conditions—attractive benefits—send resume stating to: Personnel Director, The Metropolitan District, 115 Broad St., Hartford, Connecticut.

Structural & misc. steel detailer—must be experienced, excellent climate, good housing conditions, top wages. Give full particulars. Tucson Iron Works, Box 1949, Tucson, Arizona.

Construction Superintendent wanted for $3,-000,000 school. Location, Grosse Pointe, Michigan. Good organizer with proven record. Work starts at once. Krieghoff Company, 6661 French Road, Detroit 13, Michigan, Walnut 1-3400.

City Engineer for City of Little Falls, N. Y. Has responsible charge of the activities of the Public Works Dept. does related work as required. This is an important administrative position involving responsibility for planning & directing the activities of a Public Works Dept. in accordance with the general policies of the Board of Public Works. General supervision is exercised over all activities of the Department. Acceptable experience and training: Five years of experience in street and highway construction or general engineering construction of which three years shall have been in a responsible supervisory capacity, and graduation with a degree in civil engineering from an engineering school registered by the University of the State of New York; or any equivalent combination of experience and training sufficient to indicate ability to do the work. Special requirements for acceptance of applications—a professional engineer's license issued by the State of New York. Last date for receiving applications October 12, 1956 at 3:30 P.M. Applications may be obtained and filed at the City Clerk's office, City Hall, Little Falls, N. Y.

Town Engineer to serve as Highway and Planning Engineer for Town of 8500. Responsible for engineering in connection with construction and maintenance of roads, streets, bridges, ad storm drains. Apply to Town Manager, Houlton, Maine.

Superintendent or Assistant Superintendent, experienced and capable of running jobs up to 150,000. Prefer carpenter background. Salary commensurate with ability. Permanent position with Central Illinois Company for the right man. Apply to P-3100, Engineering News-Record.

Draftsman—Experienced structural steel detailer. Permanent position in Jersey coast resort town. Apply Park Steel & Iron Company, Evergreen & R. R. Aves., Bradley Beach, N. J.

Construction—The man we are looking for is now employed as an Assistant Superintendent and field engineer. Prefer graduate engineer with approximately five years of field experience with general contractor in commercial and industrial building construction. (Office experience helpful). This man should be ready to run jobs under $1,000,000. as construction superintendent and able in near future to assume responsibility for, and take complete charge of all our field operations. This is an exceptional opportunity with an old well established but growing construction company, in Rhode Island. P-3101, Engineering News-Record.

POSITIONS WANTED

Construction or project manager, 48, engineering background. 30 years experience all phases heavy construction roads, bridges, hydroelectric projects, steel and concrete structures. Proven administrator and producer. Desires short term assignment. Excellent pinch hitting during sick leave, vacations or where job needs a boost. Would consider permanent connection. Available October 15. Domestic or foreign. PW-3002, Engineering News-Record.

POSITIONS WANTED

C.E. and M.E. in power plant engineering including 28 years of diversified experience in heavy and light construction, wishes new connection as a construction manager, general superintendent, project manager, or engineer, foreign work preferred with mild climate. Experience in airfields, water distribution, disposal plants, roads, railroads etc. Now employed in Spain. Available 60 days. PW-3000, Engineering News-Record.

Construction or Maintenance Superintendent (52) Bulk Oil or Gasoline Storage; familiar with the below ground hydraulic; pump and tank, or gravity systems. Army or Navy specifications. Interested in domestic or foreign projects. PW-3019, Engineering News-Record.

Const. Supt. BSCE, age 33. Background bldgs., dams, schools, PW-3042, Engineering News-Record.

Construction Engineer Superintendent. Age 43 BSCE. 20 years office and field experience: roads, airfields, waterworks, sewage, bridge and industrial construction: soils testing. Available for owner or contractor Eastern States. PW-3008, Engineering News-Record.

Project Mgr.—General Superintendent—Engineering background—age 44 yrs. with 20 years experience in heavy construction. Industrial with some municipal work. Seeks permanent connection. Prefer South or Southwestern Area but will consider others. Please describe position and state min. salary and benefits. PW-3024, Engineering News-Record.

Accountant experience office manager in heavy construction, dams and air field buildings and under ground systems. College major accounting special course industrial management, age 45, married, wife and I go anywhere. PW-2897, Engineering News-Record.

Mining Engineer — Production — Exploration — Sales Promotion. Background includes management of surface and dredging operations; geologic exploration and evaluation of non-ferrous deposits including several years in South America; sales, sales promotion and product development of earth moving and drilling equipment, and explosives. Experienced in United States Government contracts. PW-2942, Engineering News-Record.

Mechanical Engineer, eighteen (18) years experience in all phases of mechanical work, usually associated with large consulting engineering offices in New York City, including petroleum piers, oil pipelines, tank forms, airports, tunnels, roads, buildings, etc. Position desired should be of responsibility level, involving reports, design, specifications, bid analysis, supervision, etc., New York or vicinity, Box PW-2944, Engineering News-Record.

Construction Executive sound experience all phases, bid to completion, buildings and heavy construction, available as project manager, chief estimator or similar position where scope and volume require top man. Now employed. Minimum $15,000. PW-2596, Engineering News-Record.

Civil Eng., MS, 33, Regist. Calif., wishes to associate with consulting engineer or purchase practice. West Coast location. PW-3071, Engineering News-Record.

Seasoned Structural Engineer, registered in several states, used to handle large structural projects of any kind, particularly industrial buildings and bridges, is available for new connections, domestic, Europe or S.A. PW-3073, Engineering News-Record.

Construction Engineer, B. C. E. 1954 2 years experience, single, desires foreign employment in construction field. PW-3074, Engineering News-Record.

Sanitary Engineer, BSCE, 27, veteran, presently working for M.S. in sanitary engineering, 2 yrs. experience in design and supervision at construction on sewage and water treatment plants, desires position in consulting or industrial firm, industrial or municipal waste field, middle west, western US or Canada. Available February. PW-3084, Engineering News-Record.

Civil Engineer PE NY water, sewer, grading, drainage, pavements, highways, industrials, institutions, airports, designs, specs, reports —work on job basis only. PW-3077, Engineering News-Record.

Executive, 19 years administrative & supervisory experience in heavy construction, incl. Govt and State projects. Bid to completion. Manage branch or project. $15,000. min. PW-3089, Engineering News-Record.

Exec., Sec., Steno. (female) technical engineering, const., architectural. PW-2748, Engineering News-Record.

Superintendent, heavy & bridge construction, 19 years experience bid to completion, $200, PW-3102, Engineering News-Record.

POSITIONS WANTED

Controller—seeks similar position. Over 12 yrs. engineering & construction contracting accounting experience plus 4 years public accounting. Top supervisor all financial & accounting detail. Or, will work with group of medium & smaller companies on part time arrangement to handle all bookkeeping, cost reports, income tax returns, etc. Will also install system and supervise your personnel. Work area to include N.Y.C. Westchester & Putnam counties and Fairfield county in Conn. PW-3111, Engineering News-Record.

General Foreman or assistant superintendent desires to relocate in west or Pacific N. West. Would like position with growing contractor, 17 years experience in residential and commercial building. 37 years of age. PW-3106, Engineering New-Record.

Florida interested job there—executive, field or sales capacity 15 yrs. experience heavy construction, waterfront work small initial salary acceptable. PW-2879, Engineering News-Record.

Construction Engineer Executive, 20 years experience in all phases of contractual earth moving, both dry land and hydraulic suction dredging, excavation and embankment etc., from initial investigation thru final completion. Co-ordination of labor relations, management diplomacy, both field and administrative, negotiation of special problems that require ingenuity. Either domestic or foreign PW-3108, Engineering News-Record.

Civil Engineer, PE, 44. Soils engineer (Chief) two states, highway & heavy structures construction, materials, presently diversified research administrator, skilled technical writer, speaker. PW-3110, Engineering News-Record.

SEARCHLIGHT SECTION

REPLIES (Box No.): Address to office nearest you c/o This publication Classified Adv. Div.
NEW YORK: P. O. Box 12 (36)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)

SPECIAL SERVICES

Mail Order Opportunity—Exciting home business or office side line. Mail order executive will show you how to net large profits with no investment in merchandise or advertising required. Experience not necessary. Proven practical, fully explained in free confidential letter. Write: Impact! Inc. 2108 Payne Avenue, Dept. 29-10, Cleveland 14, Ohio.

Contract Disputes? Government construction contractors who have contract questions under dispute are offered assistance in the settlement or the appeal of said disputes. SS-2433, Engineering News-Record, P. O. Box 12, New York 36, N. Y.

Engineers—Foremen—Office Men
Learn latest methods to organize and run work. Prepare for the top jobs.
Send post card for details.
GEO. E. DEATHERAGE & SON
CONSTRUCTION CONSULTANTS
P.O. Box 921 Lake Worth, Florida

STRUCTURAL DRAFTSMEN
Fabricators are in desperate need for detailers. Outside detailing is offering the best solution. Get in on this terrific detailing boom. Active list of structural steel fabricators for $5.00. Every state is represented. This is the only list available at this reasonable cost.
PRIDE STRUCTURAL STEEL SERVICE
P. O. Box 3837—Cleveland 10, Ohio

STRUCTURAL ENGINEERING
ARCHITECTURAL ENGINEERING
OUR COURSES of instruction by mail HAVE HELPED THOUSANDS to better positions and to pass State Board Examinations. Forty-third year.
WILSON *Engineering Corp*
HARVARD SQ. CAMBRIDGE MASS.

SEARCHLIGHT SECTION

(Classified Advertising)

BUSINESS OPPORTUNITIES — **EQUIPMENT USED or RESALE**

UNDISPLAYED ——**RATES**—— ***DISPLAYED***

$2.10 a line, minimum 3 lines. To figure advance payment count 5 average words as a line.

BOX NUMBERS count as one line additional in undisplayed ads.

DISCOUNT of 10% if full payment is made in advance for four consecutive insertions of undisplayed ads.

The advertising rate is $23.60 per inch for all advertising appearing on other than a contract basis. Contract rates quoted on request.

AN ADVERTISING INCH is measured 7/8 inch vertically on one column, 3 columns—30 inches to a page.

EQUIPMENT WANTED or FOR SALE ADVERTISEMENTS acceptable only in Displayed Style.

Send NEW ADVERTISEMENTS or Inquiries to Class. Adv. Div. of Engineering News-Record, P. O. Box 12, N. Y. 36, N. Y. October 18th issue closes October 8th

---

JUST RELEASED GOVT. SURPLUS

TENSIOMETER

TRADE NAME DYNAMOMETER

Measures Traction, Tension, or Weight

A PRECISION INSTRUMENT WHERE QUICK TESTS FOR SAFETY ARE ESSENTIAL.

Mfg. by Dillon Co.

5" DIAL
8½ LBS

NEW, FULLY GUARANTEED
10,000 LB TEST
$59.00
GOV'T COST $135.00
Complete with case, illustration of construction, and instructions for use

[Rated firms shipped open account.]

Used by: Leading industrial plants, experimental shops, schools, universities, branches of govt.

To determine strengths of: Bendings ● automobile and aircraft frame and cross piece buckling ● chain and cable ● earth anchors ● draw bar testing hydraulics ● clutch loads ● hardware fixtures ● tractor and truck load pulls.

Simple test arrangements: Simply apply: winch, block and fall, hydraulics, jack, or turnbuckle.

This is NOT a spring measuring device . . . operates by deflection of special ultrasensitive alloy beam. Registers a full scale reading in pounds with only .040 deflection. Certified by U.S. Bureau of Standards. Portable . . . rugged . . . retains sensitivity indefinitely . . . unaffected by temperature.

(FREE Illustrated Brochure on Request.)

JOB LOT TRADING CO., Box 352, Church St. Station, N. Y. 8, N. Y.

CRANES FOR RENT

CRAWLERS — Capacities to 80 tons, Booms to 180 ft.
TRUCK CRANES — Capacities to 35 tons, Booms to 130 ft.

P and H, Lima and Manitowoc.
Top-Condition erection cranes

ROGER SHERMAN

CRANE SERVICE, INC.
East Hartford, Connecticut JAckson 8-4106

FORSYTHE EQUIPMENT CO., INC.

MANITOWOC SPEEDCRANES

RENTALS

Capacities to 70 Tons
Booms to 140 ft. and 30 ft. jibs.
Special rates on long rentals

Exeter 2-6125 — **37-11 Vernon Blvd.**
Long Island City 1, New York

WANTED
Blocks 10-15-20-25 Ton
Single Sheave Blocks
With Swivel Hook

ANDERSON EQUIPMENT CO.
Box 1737, Pittsburgh 30, Pa.
Phone: LEhigh 1-6020

FOR SALE OR RENT

LORAIN Model TL20 Hoe, S/N 19551, Year 1949, completely rebuilt

LORAIN Model TL25K Hoe, S/N 27394, Year 1956, used less than three months

LORAIN Model TL25 Hoe, S/N 20941, Year 1950, used three months after being rebuilt

LORAIN Model TL26 Shovel, Crane or Dragline, S/N 26402, Year 1955, used three months

QUICKWAY Model E Shovel, S/N 609, Year 1948, 4/10 cu. yd., mounted on standard 1942 Coleman 4x4 truck

P&H Model 255, S/N 6828 with 45' Crane Boom, Rudomatic Tagline and Fairlead, Waukesha Gas Engine, Mounted on Mack 4x6 with Cummins Diesel Engine, good operating condition

BUCYRUS ERIE Model 10B Shovel, ¾ cu. yd. S/N 13040, Year about 1936, good operating condition

MARION Model 331, ¾ yd., Shovel-Hoe-Crane, 40 ft. boom with fairlead, S/N 8518, Year 1947, Cat. D4600 Diesel Power, good operating condition

LINK BELT Model LS51, ½ cu. yd. Hoe, S/N 6G493.

Also available in limited territory

New Lorain Hoes, Model 25J-36" Bucket, Model 25K-40" Bucket.

L. B. SMITH, INC.

357 W. Fayette St. — **Syracuse, N. Y.**

Phone 75-2196

FOR SALE

DIESEL ELECTRIC LOCOMOTIVES

STANDARD GAUGE

25 - 35 - 40 - 50 - 65 - 75 - 100 tons

Write for Details

FRANK M. JUDGE & CO., INC.
7010 Empire State Building
New York 1, N. Y.

FABRICATIONS *FAST DELIVERY*

- Heavy Plate & WF Sections—New & used.
- Plate ½", 5/8", & ¾" any size
- WF to 33" @ 152#

Also Light & Heavy Channels, Angles & I Beam Fabricating

SEND DRAWINGS AND SPECIFICATIONS TO:

Stokvis Edera & Co. Inc.
18 Secatoag Ave.
Port Washington, N. Y.—Port Was. 7-3390

Buffalo Iron Worker, will punch 18" wide Flange beams in the flange and web. Will shear 3½" x 3½" angles, and shears ½" plates. Practically new.

Also Lincoln welder capable of welding any piece of Structural Steel. And portable Grinder suitable for finishing ends of small columns.

Apply Mr. H. C. GERRY

184, HIGH POINT RD. SPARTANBURG S. C.
PHONE 2-1669 Spartanburg.

8½ YD. SMITH
TRUCK MIXER

Used as Demonstrator for short time.
Excellent Condition.

Hodge & Hammond, Inc.
720 Garrison Avenue, Bronx, N. Y. C.
New York Phone—Kilpatrick 2-2400
New Jersey Phone—Market 3-5424

PRACTICALLY NEW

310 PARSONS

$21,000.00

Worked only 500 hours.
Bought for a job that "blew up"
H&L removable teeth, Reinforced Boom—Conveyor extension—Diesel. You can't tell from new machine

LATIMER CONSTRUCTION CO.
930 Wyandote St., Denver, Colo. Cherry 4-0783

BUCYRUS ERIE 38-B

1½ yd. Shovel Attachment Only

Complete with necessary turntable equipment (no fagging). New in 1952. Excellent condition. Available now, price $4,850.00.

EDWARD EHRBAR, INC.
29 Meserole Avenue, Brooklyn 22, New York
EVergreen 3-5000

FOR SALE or RENT

1—25 Ton Bay City Truck Crane, 95' Boom, New 1952.

B. M. WEISS CO.
Girard Trust Bldg. — **Philadelphia 2, Pa.**

FOR SALE

1—D8 CaterpillarDozer, Serial 2U17840

1—Transport Trailer—50 Ton Capacity—New May 1956

Charter Oak Construction Co., Inc.
325 Main St. — **Hartford 3, Conn.**

DON'T WAIT
WF-H BEAMS
PILE SECTIONS
NEW • USED • IN STOCK

8" B P	36#	19/35'
10" B P	42#	45/50'
12" B P	53#	60/65'
14" B P	73#	60/65'
14" B P	89#	60/65'

We are also interested in purchasing your surplus material.

We assure you our prices will be the best obtainable.

Call HY DRACHMAN
STEEL CORPORATION
14-23 34th Ave., Astoria, N. Y.
Phones: AStoria 8-4484 8-8023

LOW COST INSTALLATION AND OPERATION
CABLEWAYS
IMMEDIATE SHIPMENT
ELECTRIC, STEAM or DIESEL
CAPACITY 3 to 20 TONS
SELL, RENT or BUY
FOR DAMS, BRIDGES, BREAKWATERS, FILTRATION AND SEWERAGE PLANTS
FOR SPEED, ECONOMY, EFFICIENCY, FLOOD SAFETY, LABOR REDUCTION
AMBURSEN DAM CO. INC.
295 MADISON AVE. NEW YORK

PRICE AND QUALITY
IN
FIVE USED EQUIPMENT BUYS

Marion 93M 2½-yard Shovel powered by Caterpillar D-1700 diesel engine. Location Robbinsville, N. J. Excellent condition. No repairs required. (New price—over $75,000) $38,000.00

Caterpillar D-6 equipped with pipe-laying side boom and cable bulldozer blade $5,300.00

Allis-Chalmers HD-16 diesel crawler tractor with Torque Converter equipped with hydraulic bulldozer. Used only eight months. 60-day warranty. $15,000.00

Gradall Model 2460 mounted on International KB-8-F 10-wheel truck $6,000.00

Link-Belt LS-85 Crawler-Liftcrane-Dragline, 45' boom, 20" shoes, powered by International UD-16 diesel engine $4,500.00

FRANTZ EQUIPMENT
WYNNEFIELD AVE. AND 50th ST. PHILA. 31, PA.
GReenwood 7-7200

EUCLIDS
Used 13 yd. bottom dumps
Cummins & General Motors Powered
Located - Texas - Pa. - N. Y. State
Write, wire or Phone
L. B. SMITH, INC.
Camp Hill, Penna.
Tel: Harrisburg, Regent 7-3431

FOR SALE or RENT
25 ton Ohio Diesel Loco. Crane. 1947.
30 ton Browning Diesel Loco. Crane. 1947
40 ton Ind. 8H. Steam Loco. Crane. 1942.
25 ton American Stiffleg. 100' Bm.
30 ton American #2 Guy Derrick. 90' Bm.
140 HP 2D Diesel Hoists 15000# SLP.
110 HP Amer. 3D #100 Hoist w/ Swinger.
45 ton Davenport Diesel Elec. Loco. 1942.
65 ton Whitcomb Diesel Elec. Loco. 1945.
1½ yd. Northwest #a Diesel Crane New 1948.
1½ yd. Bucyrus Erie 38B Diesel Crane. 1948.
60 ton Manitowoc 3900 Erection Crane. Rent.
100 HP Lucey Portable Boilers. 200# WP.
MISSISSIPPI VALLEY EQUIPMENT CO.
509 Locust St. St. Louis 1, Mo.

COMPRESSOR DIRECTORY
World's Best Rebuilts

55' Lindsey	(2) wheels
60' Worth. or LeRoi	(2) wheels
70' Smith	(2) wheels
75' Worth.	(2) wheels (5)
105' Worth.	(2) wheels
105' Worth.	(4) wheels
125' Worth.	(2) wheels
105' Joy	(2) wheels
105' Sullivan	(4) wheels
120' Smith	(2) wheels
210' Worth.	(4) wheels (3)
315' Worth. Diesel	(4) wheels
315' Jaeger Diesel	(4) wheels
500' Worth. Diesel	(4) wheels (4)
600' Worth. Diesel	(4) wheels (5)
630' Joy Diesel	(4) wheels (3)

American
AIR COMPRESSOR CORP
DELL AVE & 48th ST. NORTH BERGEN, N. J.
Telephone UNion 5-4848

FOR SALE or RENT—EASY TERMS
Rebuilt—A 1 Condition
48B Bucyrus Erie Shovel 2 cy Diesel
Northwest Model Shovel, 1½ cy
Comb. Caterpillar D8 & 88 Scraper
10 ton Buffalo Springfield Gas Roller
International Vibro-Tamper
WILLIAMS CONSTRUCTION COMPANY
Box 145 Balto. 20, Md. Murdock 6-6600

NEW AND REBUILT
STORAGE BATTERY
LOCOMOTIVES
1½ to 10 Ton — 18" to 56" Track Gauge
GREENSBURG MACHINE CO.
Greensburg, Pennsylvania

CONSTRUCTION EQUIPMENT
IMMEDIATE DELIVERY
INTL TD24 CABLE BULLDOZER $6500
GUTTER SNIPE STREET SWEEPER ... $1500
BACK HOE ON RUBBER-TIRED TRACTOR, 14" AND 18" BUCKETS $1950
ADAMS MODEL 30 TRAVELOADER, 24' CONVEYOR DEMONSTRATOR.
SPECIAL
MOBILE STREET SWEEPER
MODEL 2MS DEMONSTRATOR
SAVE $3600
SERVICE SUPPLY CORP.
50TH & ERIE AVE PHILA. 39, PA.

LIMA 44 25 TON CAPACITY CRANE
50' boom. Budomatic Group C Counterweight. Excellent Condition $10,500.00
Available Immediately
EDWARD EHRBAR, INC.
29 Mesorole Avenue, Brooklyn 22, New York
EVergreen 3-5000

DRAGLINE
LIMA Model 1201
With G-M Diesel, 80' Boom,
3 Yd. Page Bucket—Price • $25,000.00
ANDERSON EQUIPMENT CO.
Box 1737 Pittsburgh 30, Pa.
Phone: LEhigh 1-6870

SAVE THOUSANDS!

UNUSED 6x6 ARMY TRUCKS

2½-TON, GMC & INTERNATIONAL

- From Government Storage!
- Unused and Guaranteed!
- Factory-New Condition!
- Reconditioned trucks also available!

Why invest in expensive new trucks and equipment needed to get the roughest off-road jobs done when you can save up to $3,000 on ONE truck alone—and get the job done right!

Compare our tandem axle trucks with front wheel drive, 10 forward speeds, overdrive and new mud and snow tires with similar equipment elsewhere. See for yourself how TWO of our trucks cost you even LESS than one new truck!

If planning to buy a truck, get in touch with us right away. There's no obligation . . . and we deliver on approval!

For Specifications, Prices, Delivery Write, wire or phone COLLECT—JAckson 5-7841
Milton Y. Toombs, Jr. Sales Manager

MEMPHIS EQUIPMENT CO.
Construction and automotive equipment and parts
766 S. THIRD ST. • MEMPHIS, TENN.

EUCLID BOTTOM DUMPS FOR SALE OR RENT

Four Model 22TDT—17 cu. yd. struck
300 H.P. G.M. Diesels Engines

Used less than three months. Location—Syracuse, N. Y. Immediately available subject to prior sale or disposition.

L. B. SMITH, INC.
357 W. Fayette St. Syracuse, N. Y.
Phone 75-2196

SURVEYING INSTRUMENTS

USED • REBUILT • SALE
RENT • REPAIRING

TRANSITS AND LEVELS

New or Rebuilt
Sale or Rent

Headquarters for REPAIRS — any make — Factory Service. We will also buy your old instruments or take them in trade.

A complete line of Engineering Instruments and equipment for field or office. Write for Catalog NRL 610.

WARREN-KNIGHT CO.
Manufacturers of Transits and Levels
136 No. 12th St., Philadelphia 7, Penna.

PILING

We do a Nation-Wide business in
STEEL SHEET PILING

IMMEDIATE SHIPMENT

156 pcs. 60 ft. Corn. MP-112—Illinois
310 pcs. 60 & 50 ft. Beth. ZP-32—New York
220 pcs. 60-30 ft. Corn. MP-116—Illinois
115 pcs. 50-40 ft. Inland 1-23—Kansas
210 pcs. 30 ft. corn. MP-116—Colorado
44 pcs. 25 ft. Corn. MP-115—Kansas
58 pcs. 20 ft. Corn. MP-116—Tennessee
Other Lengths & Sections at Various Locations

PILE DRIVING EQUIPMENT

Vulcan and McKiernan-Terry
Steam Pile Hammers and Extractors
Hoists and Boilers

MISSISSIPPI VALLEY EQUIPMENT CO.
509 Locust St., Chestnut 1-4474, St. Louis, Mo.

RENT STEEL SHEET PILING

Get the exact lengths and sections you need of all standard sections, delivered *on time*—and at Foster's usual low rental rates

H-BEARING PILE
PIPE FOR PILING
LIGHT-WEIGHT STEEL PILING
PILE HAMMERS & EXTRACTORS

L.B. FOSTER Co.

PITTSBURGH 30 • NEW YORK 7 • CHICAGO 4
ATLANTA 8 • HOUSTON 2 • LOS ANGELES 5

LARSSEN SHEET PILING

WESTERN SERVICES CORPORATION
representative of SIDELOR FRANCE
601 E. Linden Ave., Linden, N. J.
HUnter 6-4000
STOCK AVAILABLE IN LINDEN, N. J.

STEEL SHEET PILING

AVAILABLE FOR PROMPT SHIPMENT

Pcs.	Section	Length	Location
100	M-115	60'	Chicago
210	M-116	29 to 30'	Colorado
190	M-115	16 to 20'	Kansas City
125	M-112	12 to 18'	Kansas
100	M-116	19 to 24'	Arkansas
100	M-116	19 to 22'	Iowa

CONMACO PHONE DExel 1-3930
CONTRACTORS MACHINERY COMPANY
804 KANSAS AVE., KANSAS CITY, KANSAS

When you need PILING . . . fast

use this section, as many contractors do, as a piling buying directory. It can save you time when you want to know, quickly, where to buy good new or used piling.

TRANSITS & LEVELS

Various Makes
NEW & REBUILT

Fully equipped modern shops — all makes and models repaired — all work guaranteed — prompt service — complete line field supplies.

INSTRUMENTS RENTED

Midwest Representative: W. & L. E. Gurley

NATIONAL BLUE PRINT CO.
Established 1918
210 S. Canal St. Chicago (6), Ill.

RE-BUILT REPAIRS RENT REAL EXPERTS

ALL MAKES
BUFF

69 Day St., New York WOrth 2-2797

GURLEY

FACTORY REPAIRS

Send your instrument directly to Gurley for repair, rebuilding, adjustment. Write for "Repair Service" leaflet plus 20-page "Surveyor's Notebook Tips."

W. & L. E. GURLEY
Dept. R, Troy, New York

SPECIALIZED REBUILDING

of surveying and engineering instruments. All makes and models expertly repaired in modern shop. All work guaranteed.

Distributors for Brunson Instruments
Hickerson Instrument Co.
29 North Edmondson Avenue, Indianapolis 19, Indiana

ROLLER
SALE or RENTAL
GALION 10-Ton, 3-Wheel,
Hercules Gasoline Engine,
24" Rolls. Serial No. CG-15594
New 1951. Excellent Condition.
ANDERSON EQUIPMENT CO.
Box 1737 Pittsburgh 30, Pa.
Phone: LEhigh 1-6020

RAILS - TIES
TRACK ACCESSORIES
NEW and RELAYING

Railway Track Material
NOW DISMANTLING

18 miles 90# ARAB; 3 miles 90# ASCE; 5 miles 85# ASCE; all 33' lengths; 20 miles 76# section, all 30' lengths. All rails relaying quality, complete with angle-bars and tie-plates punched to conform. Also over 50,000 excellent used, creosoted, 6x8x8'6" cross ties.

Address inquiries carload or more to S. FELDMAN

Morrison Railway Supply Corp.
Rand Bldg. Buffalo, N. Y.
Phone: MOhawk 5820

RAILS—New & Relaying from Largest Warehouse Stocks in U.S.
LB FOSTER co.
PGH. 30 • N.Y. 7 • CHI. 4 • ATL. 8 • HOUST. 2 • L.A. 5

RAILS
NEW — RELAYING — TRACK ACCESSORIES
MIDWEST STEEL CORP.
502 DRYDEN STREET
CHARLESTON, W. VA.
IMMEDIATE DELIVERY

1000 tons new 100# rail in stock with bars. Also relaying rails most all sections.
M. K. FRANK
480 Lexington Ave., Park Bldg.
New York, New York Pittsburgh, Penna.
105 Lake Street, Reno, Nevada

RAILROAD Cross and Switch **TIES**
Promptly from adequate stocks
NEW and USED *(as available)*
GILLIS & COMPANY
29 East Madison St. Chicago 2

RAILS - TIE PLATES
Frogs & Switches—Track Accessories
W. H. DYER CO., INC.
2110-X Railway Exchange Bldg., St. Louis 1, Mo.

GOOD USED COAL STRIPPING EQUIPMENT

9-W Bucyrus Erie Drag, 165', 10 yd.
625 Page Diesel Drag, 150', 10 yd.
625 Page Diesel Drag, 160', 9 yd.
6160 Bucyrus Monighan Elec. Drag, 160', 8 yd.
621 Page Diesel Drag, 135', 5 yd.
621 Page Diesel Drag, 125', 7 yd.
7200 Marion Drag, 120', 7 yd.
200-W Bucyrus Monighan Drag, 140', 6 yd.
2400 Lima Drag, 120', 6 yd.
4500 Manitowoc Drag, 140', 4 yd.
620 Page Diesel Drag, 115', 6 yd.
4500 Manitowoc Drag, 120', 5 yd.
120-B Bucyrus Erie Elec. Drag, 115', 5 yd.
111-M Marion Drag, 80', 5 yd.
1055 P&H Drag, 110', 4 yd.
1201 Lima Drag, 85', 3 yd.
3500 Manitowoc Drag, 80', 2½ yd.
1001 Lima Drag, 80', 2½ yd.
955 P&H Drag, 100', 2½ yd.
54-B Bucyrus Erie Drag, 85', 2½ yd.
80-D Northwest Drag, 65', 2½ yd.
170-B Bucyrus Erie Elec. 6½ yd. Shovel
1600 P&H Elec. 6 yd. Shovel
1500 P&H Elec. 5 yd. Shovel
120-B Bucyrus Erie Elec. 4½ yd. Shovel
111-M Marion 4 yd. Elec Shovel
111-M Marion 4 yd. Diesel Shovel
1055 P&H 3½ yd. Shovel
1201 Lima 3½ yd. Standard Shovel
111-M Marion 3 yd. High Lift Shovel
1201 Lima 2½ yd. High Lift Shovel
3500 Manitowoc 3 yd. High Lift Shovel
80-D Northwest 2½ yd. Shovel
54-B Bucyrus Erie 2½ yd. Shovel
38-B Bucyrus Erie 1½ yd. Shovel
25 Northwest ¾ yd. Shovel
22-B Bucyrus Erie ¾ yd. Shovel
Unit 1020 ¾ yd. Shovel
802 Lima Cranes
600 Reich Heavy Truck Mounted Rotary Air Drills (Both Lever Arm and High Mast)
58-BH Joy Champion Rotary Air Drills
Quarrymaster Drill—with 2—600 c.f. Compressors
Also 42-T, 29-T and 27-T Well Drills

EUCLID TRUCKS — Many to Choose From

FRANK SWABB EQUIPMENT CO., Inc.
313 Hazelton Nat'l. Bank Bldg.
Hazelton, Pa. GLadstone 5-3658

LORAIN 820
2 yard shovel
Rebuilt and Guaranteed. Powered by Waukesha WAKD Diesel. Available immediately.
EDWARD EHRBAR, INC.
29 Meserole Avenue Brooklyn 22, New York
Evergreen 3-5000

FOR SALE

HEAVY CONSTRUCTION EQUIPMENT

Located Downsville, N. Y.
All offered subject prior sale

10—EUCLID Bottom-Dumps Model 43 FDT, 13 c.y.
1—EUCLID Loader, Model 3 BV, Serial BV 22.
8—STERLING Model HCS 297 End-Dump Trucks, 12 c.y.
8—CATERPILLAR Tractor-Dozers, 1 H Series.
2—ROCK RAKES with LE TOURNEAU Bulldozer Connections.
3—CATERPILLAR Model 12 Graders.
1—LIMA Type 604 1½ c.y. Shovel/Crane Combination.
1—BUCYRUS-ERIE 2½ c.y. Shovel/Dragline Combination.
1—LORAIN T20 ½ c.y. Mote-Crane, Shovel/Crane/Backhoe Combination.
1—Shovel Front Complete for Bucyrus-Erie 54-B.
1—Digging Bucket for P. & H. 1055, 3½ c.y.
1—Dipper Handle for P. & H. 1055.
1—Page Dragline Bucket, 1½ c.y., Type AX.
1—Owens Clamshell Bucket, ¾ c.y., Type D.
1—Heltzell Concrete Bucket, 1½ c.y.
1—Blaw-Knox Concrete Bucket, 1 c.y., Model C-31 KB.
1—Wiley Concrete Bucket, 1¾ c.y.
1—REX Model 160 Double Pumpcrete, complete with 7" pipe, fittings and assorted specials.
1—GARDNER-DENVER Grout Pump, Model EF-F5, 10x4x10.
1—MALSBURY Steam Cleaner, Model 322-OMS17, mounted on GMC 6x6 Truck.
4—WORTHINGTON 2-Stage Turbine Pumps, Model 12-QG-H2 (2 electric and 2 diesel driven); capacity 1500 GPM @ 110 ft. head, @ 1770 R.P.M.
GROUP OF 12 ASSORTED PUMPS (Marlow, Carter, Gorman-Rupp, C.H.&E., Worthington, 3" to 6", Centrifugal).
1—FORD Truck, 16 ft. Platform, Model F8, Serial 8EQ-7341.
1—INTERNATIONAL Truck, Model LF172, Serial 661, mounted with 1500 gallon oil tank.
1—INTERNATIONAL Truck, Model L162, Rack Body, Serial 3530, mounted with Lubrication Equipment, Worthington compressor and Wisconsin engine.
1—BRUNNER Electric Compressor, Model HO7-BC.
1—INGERSOLL-RAND Compressor, Model V253-N8, 5x3x3½.
1—INGERSOLL-RAND Compressor, Portable, 315 c.f.m., Cummins diesel engine HB6.
1—WESTINGHOUSE Electric Compressor, Model 3 VC.
1—HOBART Electric Welder, 300 amp. 220/440 V.
1—WESTINGHOUSE Electric Welder, 300 amp. Model DC-Type RA-220/440/550 V.
1—P. & H. Electric Welder, Type WG-301, 60/375 amp. Generator; Chrysler Model IND engine, type 6A-211.

LARGE ASSORTMENT AIR TOOLS (Jackhammers, Paving Breakers, Tampers, Rivet Hammers, Rivet Busters, Impact Wrenches, etc.)
MISCELLANEOUS SMALL EQUIPMENT AND POWER TOOLS (Power Saws, Drills, Sanders, Grinders, Bar Bender, Light Plants, Hydraulic Press, Hydraulic Jacks.)
REPAIR PARTS—Large Stocks—for Allis-Chalmers Tractor and Grader, Baker Bulldozer, Bendix-Westinghouse, Buda, Cummins and G.M.C. diesel engine, Caterpillar Tractor, Delco-Remy, Euclid, International Tractor TD24, International Dodge and Ford Truck, Gar Wood Hydraulic Hoist, Jaeger Mixer, LeTourneau, Lima Shovel, P. & H. Shovel, Rex Pumpcrete, Sterling Truck, and others. Also large stock miscellaneous hardware items (bolts, nuts, etc.) Complete lists furnished on request. Will price right for bulk sales.

"GRIZZLY" EARTH PROCESSING PLANTS
Plant No. 1—designed to produce 2,600 c.y. per hour of "B" Pervious material.
Plant No. 2—designed to produce 1,350 c.y. per hour of "A" Impervious material.
BOTH PLANTS NOW COMPLETELY DISMANTLED
Ask for detailed list of components

BIANCHI CENTRAL, MUNROE-LANGSTROTH, RUGO
A Joint Venture
24 Union Avenue Framingham, Mass.
(Tel. TRinity 2-4341)

Additional Searchlight Advertising on page 162

PROFESSIONAL SERVICES

NEW ENGLAND

Jackson & Moreland, Inc.
Engineers and Consultants

Design and Supervision of Construction
Reports — Examinations — Appraisals
Machine Design — Technical Publications
Boston — New York

Metcalf & Eddy
ENGINEERS

Investigations — Reports — Design
Supervision of Construction
and Operation
Management — Valuation — Laboratory
1300 Statler Building, Boston 16

MIDDLE ATLANTIC

Edwards, Kelcey & Beck
Consulting Engineers

Reports, Design Supervision
Subways, Expressways, Traffic, Parking
Harbor Works, Bridges, Tunnels
Housing and Industrial Developments
Newark, New Jersey
New York — Philadelphia — Boston

John Clarkeson
Consulting Engineer

Civil Engineers — Consulting Services
Highways, Airports, Bridges
Surveys, Waterfront Facilities
Albany and Watertown, N. Y.

Donald J. Belcher & Associates, Inc.
Aerial Photographic Analysis

Engineering Soils Maps
Materials Location Maps
Bedrock Contour Maps
Bedrock Profiles of Center Lines
Soil Profiles of Center Lines
Drainage Maps

For location of highways, dams, pipelines, industrial sites, airports, and watershed development.

130 Forest Home Drive Ithaca, N. Y.

E. Lionel Pavlo
Consulting Engineer

Design, Supervision, Reports
Bridges, Highways, Expressways
Marine Structures, Public Works
Industrial Construction, Airports
7 E. 47th St. — New York 17, N. Y.

Severud-Elstad-Krueger
Consulting Engineers

Structural Design - Supervision
Reports - Buildings - Airports
Special Structures
415 Lexington Avenue
New York 17, N. Y.

D. B. Steinman
Consulting Engineer

BRIDGES
HIGHWAYS
Design, Construction
Strengthening, Investigations,
Reports, Advisory Service
117 Liberty St., New York 6, N. Y.

Lockwood, Kessler & Bartlett, Inc.
Engineers — *Surveyors*

Civil Engineering Investigations, Reports and Designs, Supervision of Construction, Cadastral, Geodetic, Topographic & Engineering Surveys, Photogrammetric Engineering and Mapping.
One Aerial Way — Syosset, N. Y.

Kain and Hooven
Consulting Engineers

Civil—Structural—Industrial
Registered—Pennsylvania, Delaware, New Jersey
44 S. Lansdowne Ave., Lansdowne, Pa.

Robert W. Lowry, Inc.
Consulting Engineers

Robert W. Lowry — M. Lepkaluk
Design, Supervision, Reports, Long Span & Movable Bridges, Expressways, Highways, Airports, Prestress Design, Stress Analysis & Strengthening
237 Pine Street, Harrisburg, Pa.
133 E. 42nd Street, N. Y., N. Y.

Michael Baker, Jr., Inc.

Consulting Engineers, Civil Engineers, Planners & Surveyors; Airports & Highway Design; Water Works & Sewerage Design & Operation; Aerial Topo Maps; Surveys; Reports & Investigations; Irrigation. Home Off.—Rochester, Pa. Br. Off.: Jackson, Miss.; Harrisburg, Pa.; College Park, Md.

Sprague & Henwood, Inc.
Drilling Services

Foundation Investigations, Soil Testing & Test Borings, Grout Hole Drilling & Pressure Grouting, Diamond Core Drilling
Main Office
231 W. Olive Street, Scranton, Pa.
Branches:
1009 Western Savings Fund Bldg., Philadelphia, Pa.
11 W. 42nd St., New York, New York
200 Magee Bldg., Pittsburgh, Pa.
Box 645—Grand Junction, Colorado
Buchans, Newfoundland

Buchart Engineering Corp.
Engineers

Highways — Bridges — Toll Roads
Sewerage — Industrial Waste and Disposal — Water Works — Surveys — Reports — Design — Supervision — Consultation — Industrial — Municipal — Structures
611 W. Market St., York, Pennsylvania

SOUTH

Duval Engineering & Contracting Co.
General Contractors

FOUNDATION BORINGS
For Engineers and Architects.
Jacksonville — Florida

Rader and Associates
Engineers - Architects

Sewage Disposal, Water Works, Ports, Airports, Bridges, Highways, Office and Commercial Buildings, Industrial Plants, Reports, Investigations, Consultations.
111 N.E. 2nd Avenue, Miami 32, Fla.

MIDDLE WEST

Consoer, Townsend & Associates

Water Supply, Sewerage, Flood Control & Drainage, Bridges, Express Highways, Paving, Power Plants, Appraisals, Reports, Traffic Studies, Airports, Gas & Electric Transmission Lines.
351 East Ohio St., Chicago 11, Illinois

Mobile Drilling Contract Division, Inc.
Soil and Foundation Engineering

Foundation Investigation, Analysis & Design — Earth Dam & Embankment Design — Pavement Design — Compaction Control — Soil Sampling & Testing — Core Drilling.
960 N. Penn. Ave., Indianapolis 4, Ind.

Toledo Testing Laboratory
Engineers—Chemists

Concrete — Soils — Asphalt
Inspection — Research
Tests — Development
Foundation Investigation
Borings — Diamond Drilling — Load Tests
Soils Mechanics Laboratory
1810 North 13th St. — Toledo 2, Ohio

The Consulting Engineer

By reason of special training, wide experience and tested ability, coupled with professional integrity, the consulting engineer brings to his client detached engineering and economic advice that rises above local limitations and encompasses the availability of all modern developments in the fields where he practices as an expert.

FOREIGN

Ingenieria Especializada De Mexico, S. A.

Consulting Engineers, Contractors offering a complete engineering service in Latin America cement and lime plants; hydro, thermo & diesel electric plants manufacturing & process plants.

Plaza Santos DeGollado #10-301,
Mexico 1, D. F.

GEOLOGISTS

Geologic Associates
ENGINEERING GEOLOGISTS

Studies and Reports
Foundation Investigations
Specialized Drilling and Sampling
1806 8th Ave. So — Nashville, Tenn.
9-1819 — Phones — 5-4402

INSPECTION & TEST

A. W. Williams Inspection Co.

Established 1921—Member A.C.I.I.
Inspection — Testing — Analyses — Supervision. Foundation Investigations, Soil Borings, Soil Mechanics, Concrete and Asphalt Design and Control, Radiography, Sampling, Calibrations, Timber and timber treatment Inspections. Complete testing laboratory service.
Main Office: 308 Virginia St., Mobile, Ala.

The Haller Testing Laboratories, Inc.

Testing and Inspection of Construction Materials for:
Expressways—Airports
Structures—Bridges
Complete Soils Laboratory
Borings—Drilling—Load Tests
140 Cedar St., N. Y. 6, N. Y.
Boston, Mass.
Plainfield, N. J. — New Haven, Conn.

ALWAYS READY

Yes, these consultants are always ready to help you with any problem concerning engineered construction. Call on them with the assurance that you will be receiving the finest of professional advice.

SEARCHLIGHT SECTION

(Continued from preceding page)

ENGINEERS CONTRACTORS

WE'LL RECLAIM THAT OLD CAST IRON WATER LINE

I Contract to reclaim your Cast Iron Water Pipe, YOU KEEP ALL PIPE.
II Remove Cast Iron Water Pipe for a percentage of the pipe, YOU KEEP PART OF THE PIPE.
III We'll Bury Cast Iron Water Pipe IN THE GROUND.

EXPERT IN SCIENTIFIC RECLAIMING CAST IRON PIPE

W. R. Kershaw Steel & Pipe Company

P. O. Box 435 — Muskogee, Oklahoma

Phones: MUrray 2-2912
MUrray 2-7971

PIPE

SURPLUS NEW and USED — FOR SALE

PILING · PILE FITTINGS · PIPE
CULVERTS · VALVES & FITTINGS
SPECIALISTS IN PRE-FAB. PIPING

ALBERT PIPE SUPPLY — APS

ALBERT
PIPE SUPPLY CO., INC.
Berry at North 13 Sts., B'klyn, N. Y.

PIPE
VALVES and FITTINGS
All Sizes in Stock
NEW—USED
GREENPOINT IRON & PIPE CO. INC
Bogart and Stagg Streets, Brooklyn, N.Y.

ADVERTISERS IN THIS ISSUE

Acker Drill Co. 115
Allied Materials Corp. 42
American Bridge Div., U. S. Steel Corp. 139
American Cable Div., Amer. Chain & Cable Co. 119
American Manganese Steel Div. Amer. Brake Shoe Co. 90
American Sisalkraft Corp. 77
Atlantic Steel Corp. 128
Austin-Western Co. 144

Barco Mfg. Co. 80
Baxter Co., J. H. 114
Bay City Shovels Inc. 129
Belmont Iron Works 132
Bendix Aviation Corp. 12, 13
Bethlehem Steel Co. 98
Blaw Knox Equipt. Div., Blaw Knox Co. 113
Blood Brothers Machine Co. 104
Bower Roller Bearing Co. 111
Bruning Co., Inc., Charles 15
Byers Co., A. M. ..... 2nd cover

Case Foundation Co. 104
Caterpillar Tractor Co. 30, 31
Caterpillar Tractor Co. 33
Ceco Steel Prod. Corp. 96, 97
Chain Belt Co. 146
Cleveland Trencher Co. 86
Clipper Mfg. Co. 11
Columbia Southern Chem. Corp. 127
Commercial Shearing & Stamping Co. 47
Concrete Grinding Corp. 92
Concrete Reinforcing Steel Institute 143
Construction Machinery Co. 151

Dorr Oliver, Inc. 60
Dow Chem. Co. ..... 3rd cover
Dresser Mfg. Div., Dresser Ind. 87
Dudgeon, Inc., Richard 120

Earle Gear & Machine Co. 122
Eastman Kodak Co. 64
Enterprise Galvanizing Co. 132

Michael Flynn Mfg. Co. 101

Garrett Corp. 124
Glazer Steel Corp. 136
Goldblatt Tool Co. 128
Goodall Rubber Co. 68
Goodyear Tire & Rubber Co. 20
Graphic Systems 116
Griffin Wellpoint Corp. 116
Gulf Oil Corp. 17
Gunite Concrete & Construction Co. 122
Gurley, W. & L. E. 132

Hamilton Kent Mfg. Co. 9
Harnischfeger Corp. 6
Hartford Accident & Indemnity Co., Hartford Fire Ins. Co. 76
Heltzel Steel Form & Iron Co. 88, 89
Hendrix Mfg. Co. Inc. 14
Hose-McCann Telephone Co., Inc. 132

Ingersoll Rand Co. 108, 109
Inland Steel Prod. Co. 137
Ins. Co. of North America 16
International Harvester Co. 59, 61, 62, 63
International Harvester Co. (Trucks) 134
Intrusion-Prepakt, Inc. 93
Irving Subway Grating Co. 150

Kern Instrument Co. 107
Kinnear Mfg. Co. 78
Klemp Metal Grating Corp. 115
Koehring Co., The 38, 39

LeRoi Co. 121
Liberty Mutual Ins. Co. 43
Lincoln Electric Corp. 48
Lone Star Cement Corp. 22
Louisville Cement Co. 131
Lufkin Rule Co. 120

Macomber, Inc. 7
Madesco Tackle Block Co. 120
Manitowoc Engineering Works 79
Manitowoc Shipbuilding Inc. 125
Massey-Harris-Ferguson Co. 57
McCabe Powers Auto Body Co. 85
McConnaughay, K. E. 99
McKiernan-Terry Corp. 128
McKinney Drilling Co. 120
Moretrench Corp. 136
Murphy Diesel 1

National Gypsum Co. 67
National Supply Co. 106
New England Carbide Tool Co., Inc. 74
Northwest Engineering Co. 3

D. W. Onan & Sons, Inc. 116

Patent Scaffolding Co. 117
Peerless Pump Div. of Food Machy. Corp. 149
Pennsylvania Drilling Co. 122
Phoenix Bridge Co. 128
Pittsburgh Plate Glass Co. 103
Post Co., Frederick 50
Precision Devices Inc. 125
Price Bros. Co. 133

Ramset Fasteners, Inc. 102
Raymond Concrete Pile Co. 123
Republic Steel Corp. 70, 71
Roebling's Sons Corp., John A. 95
Rust-Oleum Corp. 51
Ryerson & Sons, Inc., Jos. T. 18

St. Paul & Tacoma Lumber Co. 66
Servicised Prod. Corp. 58
Shlagro Steel Prod. Corp. 118
Smith Co., S. Morgan 75
Smith Engineering Works 34
Spencer, White & Prentis, Inc. 69
Standard Dry Wall Prod. 94
Stanpat Co. 156
Stillwater Clay Prod. Co. 103
Summitville Tiles, Inc. 100
Symons Clamp & Mfg. Co. 2

Tapecoat Co. 126
Texas Co. 4, 5
Thurman Machine Co. 151
Timken Roller Bearing Co. ..... 4th cover
Truck Mixer Mfr. Bureau 72

Union Oil Co. 54
U. S. Steel Corp. 52, 53

Viber Co. 8
Vibro-Plus Prod., Inc. 10
Vulcan Iron Works 122

Weil Pump Co. 130
Wheeling Corrugating Co. 145

Professional Services 162

CLASSIFIED ADVERTISING

F. J. Eberle, Business Mgr.

Employment Opportunities 154-157
Educational 157
Proposals 150-153
Equipment (For Rent, Sales Wanted) 157-162

ENGINEERING NEWS-RECORD

330 West 42 St., New York 36—LOngacre 4-3000

ABP Member ABC

Number of copies of this issue printed 75,606

D. S. Robertson, Advertising Manager
D. J. Cassidy, Business Manager

ADVERTISING REPRESENTATIVES

New York, 36—330 W. 42 St.,
C. D. Neulen, H. T. Olsen
J. C. White

Chicago, 11—520 No. Michigan Ave.,
L. H. Hunt, W. G. Payne

San Francisco, 4—68 Post St.,
J. W. Otterson, R. C. Alcorn

Philadelphia, 3—17th and Sansome Sts.,
D. G. Jensen

Cleveland, 15—Hanna Bldg.,
E. E. Duff, Jr., F. P. DiToro

Detroit, 26—Penobscot Bldg.,
J. A. Houghton

St. Louis, 8—Continental Bldg.,
B. F. Horn

Los Angeles, 17—1125 W. Sixth St.,
H. L. Kesler

Atlanta, 3—Rhodes-Haverty Bldg.,
W. D. Lanier

Dallas, 2, Adolphus Tower Bldg.,
G. Jones, D. C. Billian

OTHER SALES OFFICES:

Pittsburgh, 22—919 Oliver Bldg.,
Boston, 16—350 Park Square Bldg.,
London, McGraw-Hill House

Two Sides to the Coin

LOOKED AT FROM THE UNITED STATES, booming Canada has seemed to a number of American construction firms to offer useful opportunities for employment of their capital and talent. In the view of the Canadian construction man, however, Canada's expansion can quite readily be carried on without any outside help.

These opposing attitudes are, of course, historically inevitable—one example, when the current positions were reversed, occurred when British capital and construction firms aided an expanding U. S. in the last century—but they need not tarnish in any way our good neighbor relationship. There is probably something to be said on both sides of the question, and even Canadians are not unanimous in their attitude.

Several weeks ago, for example, the Alberta Highway Minister was quoted in our Construction Week column as saying that lack of competition was causing Canadian construction costs to get out line, and that the cause was too few Canadian construction firms with the essential equipment and staff. He urged the Canadian construction industry to expand or be prepared to face competition from firms in other countries.

His viewpoint was immediately challenged by an editorial in the *Daily Commercial News and Building Record* (Toronto) which said that, if governmental departments were not getting as many bids as they would like, it was more a result of their own business methods than of Canadian contractors being too busy to bid. These business methods were cited as encompassing arbitrary decisions, bureaucratic attitudes, and long delays in final payments, among others.

Similar dissatisfaction with public works construction has, of course, been voiced in this country, although it must be said in fairness to American contractors that they are seldom deterred from bidding even though conditions are not to their liking. There would seem to be a distinct possibility that in Canada competition is so keen on the normal type of "good" jobs that profit margins are cut so thin as to discourage gambling on marginal work, such as public projects may be.

Support for this view is found in comment we received on this situation from a well-known Canadian contractor who says that the margin of profit is "far smaller than the average margin experienced in your country." He points out that Canadian contractor failures are on the increase as a result.

As in so many cases of this kind it may be that everyone is right—the highway minister in his belief that the Canadian construction industry should expand out in his part of the country, the *Daily Commercial News* in its opinion of the unattractiveness of public work, and the Canadian contractors in their certainty that competition is already too keen to be healthy. Even U. S. contractors may be right in sensing opportunities in Canada, which, if followed up on a selective basis, would be a service to that booming nation.

There are always two sides to a coin, but the important requirement is that, together, they add up to something of value. U. S.-Canadian viewpoints on construction opportunities in Canada can, if properly balanced—and made to encompass construction opportunities in the U. S. for Canadians—create something of value, too. Long-time mutual respect makes it practically certain that they will.

New Vistas in Wall Design

SINCE 1951, SPECTACULAR DEVELOPMENTS in new types of exterior curtain walls have followed one another in rapid succession. Thinner, lighter, better appearance, more color—these have been the objectives. And attainment, in major degree, has been accomplished with sandwich-type sections faced with steel, aluminum, concrete, asbestos-cement, porcelain enamel or plastics, accompanied in most cases by large areas of glass.

All this has been at the expense of masonry, which, in sections 12 in. or more thick and weighing some 130 psf, dominated the wall field prior to 1951. In contrast some of these new walls are as little as 1¼ in. thick and weigh only 2 psf. Now, however, masonry has joined the parade, and in a way that promises a real revolution.

At the Modern Masonry Conference last month, conducted by the Building Research Institute, masonry producers disclosed they were ready to enter the thin-wall market with panels they have developed (ENR Sept. 27, p. 24). Facings for these wall assemblies include a prefabricated brick panel only 2½ in. thick, limestone 2 in. thick, marble ½ in. or less thick and ceramic veneer (architectural terra cotta) 1 in. thick. Most of these materials have seldom been used in the past in thickness of less than 4 in.

These facings substantially enlarge the range of architectural treatment of thin walls. They also, it should be noted, increase the responsibility of building designers and of contractor installers.

Designers have new decisions to make—between thick walls and thin, between masonry and metal, between field and factory-assembled panels and between large units and small. They have to gain experience with the newer wall assemblies, for undoubtedly the behavior of a thin facing as part of a sandwich is significantly different from that of a thick, homogeneous wall. And they have to learn to use the new panels to the best advantage.

Similarly, building contractors are faced with the necessity of learning new techniques of handling and installing these thin units, and perhaps may have to revise construction schedules to take advantage of the specific characteristics of the panels.

Such is the price of progress, but paying it opens up new vistas of wall design.

With Dowflake in the mix, concrete attains a strength of 2000 p.s.i. in 7½ days at 25°F!

BETTER CONCRETE FASTER

with Dow Calcium Chloride

Your answer to cold-weather construction problems is Dow Calcium Chloride. It speeds the set of concrete, makes it stronger at every stage. And, as temperature drops, the percentage of time saved increases.

At a temperature of 25°F., for instance, an addition of 2% of Dow Calcium Chloride to the mix provides a strength of 2000 p.s.i. . . . in only seven and one-half days! Compare this to the usual six weeks required by plain concrete at this temperature, and you will readily see why contractors specify it. You'll also notice other marked improvements any time the temperature drops below 70° F.

Dow Calcium Chloride provides more uniform curing in less than one-half the normal time. It makes concrete more workable, easier to finish. It assures complete fill in forms and faster flow through chutes. It saves time and labor, and results in smooth, wear-resistant surfaces.

For further information, contact your Dow distributor. He offers both types of our calcium chloride: Peladow®, a 94-97% concentration in pellet form; and Dowflake®, 77-80% concentration in flake form. Or write to us direct for free literature. THE DOW CHEMICAL COMPANY, Dept. IN 782S, Midland, Michigan.

you can depend on DOW CHEMICALS



The CHAIN Belt Company mounts the main mixer shaft of their 5½-yard Moto-Mixer on Timken tapered roller bearings to keep it turning smoothly, reduce maintenance.

Larger payload without exceeding wheel load limits; mixing drum rolls on TIMKEN® bearings

THIS 5½-yard Rex Adjusta-Wate Moto-Mixer is designed with great attention to correct weight distribution. And Timken® bearings play a big role in the CHAIN Belt Company's claim of "More loads per truck per day—and larger payloads without exceeding wheel load limits." A huge part of the load is in the mixing drum itself where ruggedness counts. This drum is mounted entirely on Timken tapered roller bearings, front and back, for free rolling, longer wear, less maintenance.

The drum shaft is mounted on Timken bearings, too, preventing misalignments which would otherwise occur with the Rex Adjusta-Wate Moto-Mixer operating off-level or going over rough ground. The tapered construction of Timken bearings lets them take radial and thrust loads in any combination and Timken bearing rollers and races have full line contact, which means extra load-carrying capacity. What's more the severe shocks encountered are easily met by Timken bearing *case-carburized* rollers and races; hard, wear-resistant surfaces over tough, shock-resistant cores.

In addition, Rex Moto-Mixers also use Timken bearings to good advantage in the clutch drums, secondary shafts, and in the new, improved water pump—with the pump driven by a V-belt directly from the engine crankshafts. Timken bearings are geometrically designed to give true rolling motion, practically eliminating friction . . . precision-made to conform to their design. To insure highest quality, we even make our own steel, which no other American bearing manufacturer does.

Look for the trade-mark "TIMKEN" on every bearing. The Timken Roller Bearing Company, Canton 6, Ohio. Canadian plant: St. Thomas, Ontario. Cable address: "TIMROSCO".

This symbol on a product means its bearings are the best.

TIMKEN

TRADE-MARK REG. U. S. PAT. OFF.

TAPERED ROLLER BEARINGS ROLL THE LOAD